

1509 Main Street, Suite 900
Dallas, Texas
75201-4809

214/744-1641



ICF TECHNOLOGY INCORPORATED

90068956



Memorandum

TO: Ed Sierra, Region VI RPO

THRU: K.H. Malone, Jr., FITOM

THRU: Tim A. Hall, ICF-AFITOM *ICF for TPAH*

FROM: Victor Cason, FIT Chemist *VC*

DATE: March 21, 1989

SUBJECT: Preliminary HRS Package for Goodson & Son Trucking, Channelview, TX.
TDD# F-6-8809-30, CERCLIS# TXD981052475, PAN FTX0557HAA.

A preliminary HRS evaluation has been completed for Goodson & Son Trucking site in Channelview, Texas. The site consists of a low lying area filled with cement precipitator flue dust and is located in the 17300 block of Market Street, between U.S. Highway I-10 and Market Street. Approximately 4.6 acres are covered by the cement dust. Currently, the site consists of an office for Odeen Hibbs Trucking Company and a truck parking lot.

The cement precipitator flue dust was used for land improvement purposes, to raise the elevation of the property, and was placed at the site in 1979. Complaints from residents regarding the dust created during the dumping of the material were registered with the Harris County Pollution Control Department (HPCPD). On April 29, 1981 the HPCPD performed a site inspection and noticed high pH water on-site and in the runoff collected from the fill area.

The local telephone company had noted complaints from their field workers who performed line maintenance inside an underground work station beneath the fill area. Complaints included dizziness, headaches, nausea and chemical burns. On several occasions the workers had to pump a brown liquid out of the work station. An investigation by the telephone company which involved drilling several monitoring wells around the work station revealed high calcium concentrations and high pH water.

The FIT performed a site inspection on August 3, 1987, and again discovered high pH water in the north and south ditches around the site. A grab soil sample collected during the inspection contained several polynuclear aromatic compounds and high levels of calcium, magnesium, potassium and sodium.

On November 15, 1988, FIT collected eight water samples, seven soil samples and a sample of the fill material for full RAS analysis. Results from the samples revealed that high calcium, potassium and sodium concentrations were

present on-site and in the off-site runoff. Several soil samples contained 4,4'-DDT; however, the compound could not be attributed to the site.

The ground water within a 3-mile radius is used for domestic and industrial purposes. No sampling data for drinking wells have been collected to evaluate the possibility of an observed release. An observed release to surface water is substantiated by the sampling results. The metals calcium, potassium and sodium were found in the south drainage path in concentrations greater than five times the background sample. However, due to the proximity of the site to the Gulf of Mexico, no domestic water supply intakes are located downstream. Therefore, there is no target population for surface water.

On a preliminary basis, the Goodson & Son Trucking site does not meet the requirements for inclusion on the NPL.

Facility Name: Goodson & Son Trucking

Location: 17300 Market Street Channelview, TX

EPA Region: VI

Person(s) In Charge of the Facility: Kyle Goodson

15937 Ridlon

Channelview, TX

Name of Reviewer: Victor Cason

Date: March 17, 1989

General Description of the facility:

(For example landfill, surface impoundment, pile, container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action, etc.)

The site was a low lying area between U.S. Highway I-10 and Market Street which has been filled with cement precipitator flue dust. High pH water was noted in the drainage ditches to the north and south of the site. High concentrations of calcium, potassium and sodium were found in on-site and off-site samples. An observed release to surface water was scored; however, no target population exists. There are no well data available to determine a release to ground water.

Scores: $S_M = 17.59$ ($S_{gw} = 29.93$ $S_{sw} = 5.45$ $S_a = 0$)

$S_{FE} =$ Not Evaluated

$S_{DC} =$ Not evaluated

FIGURE 1

HRS COVER SHEET

Ground Water Route Work Sheet

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref Section
[1] Observed Release	① 45	1	0	45	3.1
If observed release is given a score of 45, proceed to line [4]. If observed release is given a score of 0, proceed to line [2].					
3.2					
[2] Route Characteristics					
Depth to Aquifer of Concern	① 1 2 3	2	0	6	
Net Precipitation	0 ① 2 3	1	1	3	
Permeability of the Unsaturated Zone	0 1 ② 3	1	2	3	
Physical State	0 1 ② 3	1	2	3	
Total Route Characteristics Score			5	15	
[3] Containment	0 1 2 ③	1	3	3	3.3
[4] Waste Characteristics					
Toxicity/Persistence	0 3 9 12 15 ①⑧	1	18	18	
Hazardous Waste	0 1 2 3 4 5 6 7 ⑧	1	8	8	
Total Waste Characteristic Score			26	26	
[5] Targets					3.4
Ground Water Use	0 1 2 ③	3	9	9	
Distance to Nearest Well/Population Served	0 4 6 8 10 12 16 18 20 24 30 32 ③⑤ 40	1	35	40	
Total Targets Score			44	49	
[6] If line [1] is 45, multiply [1] x [4] x [5] If line [1] is 0, multiply [2] x [3] x [4] x [5]			17160	57,330	
[7] Divide line [6] by 57,330 and multiply by 100	$S_{gw} = 29.93$				

FIGURE 2
GROUND WATER ROUTE WORK SHEET

Surface Water Route Sheet

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. Section
---------------	--------------------------------	-------------	-------	------------	--------------

[1] Observed Release	0 (45)	1	45	45	4.1
----------------------	---------------	---	----	----	-----

If observed release is given a score of 45, proceed to line [4].
If observed release is given a score of 0, proceed to line [2].

[2] Route Characterisitics						4.2
Facility Slope and Intervening Terrain	0	1	2	3	1	3
1-yr. 24-hr, Rainfall	0	1	2	3	1	3
Distance to Nearest Surface Water	0	1	2	3	2	6
Physical State	0	1	2	3	1	3

Total Route Characteristics Score		15
-----------------------------------	--	----

[3] Containment	0	1	2	3	1		3	4.3
-----------------	---	---	---	---	---	--	---	-----

[4] Waste Characterisitics						4.4						
Toxicity/Persistence	0	3	6	9	12	15	(18)	1	18	18		
Hazardous Waste Quantity	0	1	2	3	4	5	6	7	(8)	1	8	8

Total Waste Characteristic Score	26	26
----------------------------------	----	----

[5] Targets						4.5		
Surface Water Use	0	(1)	2	3	3	3	9	
Distance to a Sensitive Environment	(0)	1	2	3	2	0	6	
Population Served/Distance to Water Intake Downstream	(0)	4	6	8	10	1	0	40
	12	16	18	20				
	24	30	32	35	40			

Total Targets Score	3	55
---------------------	---	----

[6] If line [1] is 45, multiply [1] x [4] x [5]		
If line [1] is 0, multiply [2] x [3] x [4] x [5]	3510	64,350

[7] Divide line [6] by 64,350 and multiply by 100 $S_{sw} = 5.45$

FIGURE 7
SURFACE WATER ROUTE WORK SHEET

Air Route Work Sheet

Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. Section
[1] Observed Release	① 45	1	0	45	5.1

Date and Location:

Sampling Protocol:

If line [1] is 0, the $S_a = 0$, Enter on line [5].
If line [1] is 45, then proceed to line [2].

[2]	Waste Characteristics											5.2
	Reactivity and Incompatibility	0	1	2	3					1	3	
	Toxicity	0	1	2	3					3	9	
	Hazardous Waste Quantity	0	1	2	3	4	5	6	7	8	1	8

Total Route Characteristics Score		20	
-----------------------------------	--	----	--

[3]	Targets								5.3
	Population Within	0	9	12	15	18	1	30	
	4-Mile Radius		21	24	27	30			
	Distance to Sensitive Environment	0	1	2	3		2	6	
	Land Use	0	1	2	3		1	3	

Total Targets Score		39
---------------------	--	----

[4] Multiply [1] x [2] x [3]		35,100	
------------------------------	--	--------	--

[5] Divide line [4] by 35,100 and multiply by 100 $S_s = 0$

FIGURE 9 AIR ROUTE WORK SHEET

	S	S ²
GROUNDWATER ROUTE SCORE (S _{gw})	29.93	895.80
SURFACE WATER ROUTE SCORE (S _{sw})	5.45	29.70
AIR ROUTE SCORE (S _a)	0.0	0.0
S _{gw} ² + S _{sw} ² + S _a ²	XXXX	925.50
(S _{gw} ² + S _{sw} ² + S _a ²) ^½	XXXX	30.42
(S _{gw} ² + S _{sw} ² + S _a ²) ^½ / 1.73 = S _M	XXXX	17.58

FIGURE 10
WORKSHEET FOR COMPUTING S_M

DOCUMENTATION RECORDS

FOR

HAZARD RANKING SYSTEM

INSTRUCTIONS: The purpose of these records is to provide a convenient way to prepare an auditable record of the data and documentation used to apply the Hazard Ranking System to a given facility. As briefly as possible summarize the information you used to assign the score for each factor (e.g., "Waste quantity = 4,230 drums plus 800 cubic yards of sludges"). The source of information should be provided for each entry and should be a bibliographic-type reference that will make the document used for a given data point easier to find. Include the location of the document and consider appending a copy of the relevant page(s) for ease in review.

FACILITY NAME: Goodson & Son Trucking

LOCATION: 17300 Market Street, Channelview, TX 29°47'22"N, 95°05'13"W

GROUND WATER ROUTE

1. OBSERVED RELEASE

Contaminants detected (5 maximum):

An observed release to ground water was not evaluated.

Rationale for attributing the contaminants to the facility:

HRS Score = 0

2. ROUTE CHARACTERISTICS

Depths to Aquifer of Concern

Name/description of aquifer(s) of concern:

The "Aquifer of Concern" is the lower unit of the Chicot aquifer, also known locally as the Alta Loma Sand. The Chicot aquifer is under water table conditions in Harris County. The base of the Alta Loma Sand is approximately 600 feet.

(Refs. 3, p. 10; 14)

Depth(s) from the ground surface to the highest seasonal level of the saturated zone [water table(s)] of the aquifer of concern:

From the ground surface to the highest seasonal level of the saturated zone of the lower unit of the Chicot aquifer is assigned at the depth of the screen at 218 feet. Well LJ-65-16-717 was used to obtain the depth to the saturated zone.

(Ref. 4, p.113)

Depth from the ground surface to the lowest point of waste disposal/storage:

The cement flue dust was deposited on the ground surface. Therefore, the depth from the ground surface to the lowest point of waste disposal is zero feet.

$$218 - 0 = 218 \text{ feet}$$

(Ref. 5, p. 6, Sec.VIII.L)

HRS Value = 0

Net Precipitation

Mean annual or seasonal precipitation (list months for seasonal):

The normal annual total precipitation for the general location around the site is approximately 48 inches.

(Ref. 1, p. 14)

Mean annual lake or seasonal evaporation (list months for seasonal):

The mean annual lake evaporation for the site is 53 inches.

(Ref. 1, p. 13)

Net precipitation (subtract the above figures):

The net precipitation for the site is -5 inches.

$$48 - 53 = -5 \text{ inches}$$

HRS Value = 1

Permeability of Unsaturated Zone

Soil type in unsaturated zone:

The fill material was deposited on soil from the Kenny and Aldine complexes. The soil is dark grayish brown, fine sandy loam of medium acidity. Layers of clay and sand were found to a depth of 230 feet in the well log of well LJ-65-16-717.

(Refs. 6, pp. 9, 18, and Sheet 98, 15, p. 250)

Permeability associated with soil type:

The permeability of the Aldine soil is 1.41×10^{-3} cm/sec and the permeability of the Kenny soil is 1.41×10^{-2} cm/sec. The Aldine soil permeability was used for the HRS Score.

$$2.0 \text{ in/hr} \times 2.54 \text{ cm/in} = 5.08 \text{ cm/hr} \times 1 \text{ hr/3600 sec} = 1.41 \times 10^{-3} \text{ cm/sec}$$

(Ref. 6, pp. 117 and 119)

HRS Value = 2

Physical State

Physical state of substances at time of disposal (or at present time for generated gases):

The cement flue dust was a fine powder at the time of disposal. Over time the dust has hardened and only the top two or so inches remains powder.

(Ref. 5, p. 4, Sec. VII.D.1)

HRS Value = 2

3. CONTAINMENT

Containment

Method(s) of waste or leachate containments evaluated:

There is no containment method in place at the site. The cement flue dust placed at the site has no cover and the drainage ditches to the north and south empty into the Old River.

(Ref. 5, Sec.VIII.Q)

Method with highest score:

C. Piles: Piles uncovered, waste unstabilized, and no liner.

(Ref. 1, p. 17)

HRS Value = 3

4. WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

The following elements and compounds were detected in the fill material: calcium, potassium, sodium, bis(2-ethylhexyl)phthalate and 4,4'-DDT.

(Ref. 7, pp. 2 and 3)

Compound with highest score:

The following have a matrix score of 18 on the toxicity and persistence matrix: sodium and 4,4'-DDT.

(Attachment 1)

HRS Value = 18

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (give a reasonable estimate even if quantity is above maximum):

Approximately 74,074 cubic yards of cement flue dust was deposited at the site.

(Ref. 5, p. 4, Sec. VII.C.2)

HRS Value = 8

Basis of estimating and/or computing waste quantity:

The FIT calculated the waste quantity from the estimated site dimensions.

200 ft. wide X 1000 ft. long X 10 ft. deep = 74,074 cubic yards

27 cubic ft.

1 cubic yard

(Ref. 5, Attachment A)

5. TARGETS

Ground Water Use

Use(s) of aquifer(s) of concern within a 3-mile radius of the facility:

Domestic, industrial and public supply are the uses of the wells drawing from the lower unit of the Chicot aquifer within a 3-mile radius of the site.

(Ref. 4, pp. 111-116, 146 and 162)

HRS Value = 3

Distance to Nearest Well

Location of nearest well drawing from aquifer of concern or occupied building not served by a public water supply.

The Texaco service station north of Highway I-10 and west of the site has the nearest well, LJ-65-16-717, drawing from the "Aquifer of Concern".

(Ref. 4, pp. 113 and 116)

Distance to above well or building:

The well is approximately 4400 feet west of the site.

(Ref. 4, pp. 113 and 116)

HRS Score = 3

Population Served by Ground Water Wells Within a 3-Mile Radius

Identified water-supply well(s) drawing from aquifer(s) of concern within a 3-mile radius and populations served by each:

There are six domestic wells within a 3-mile radius of the site. Assuming that 3.8 people utilize each of the six wells, 23 people would be using the area domestic wells. There are also eight public water supply wells within the specified area, not including wells designated for roadside parks. Five of the eight wells serve approximately 12500 people.

(Refs. 4, pp. 111-116; 9 and 10)

Computation of land area irrigated by supply well(s) drawing from aquifer(s) of concern within a 3-mile radius, and conversion to population (1.5 people per acre):

There are no irrigation wells within a 3-mile radius of the site. The population affected by irrigation is zero.

(Ref. 4, pp. 111-116)

Total population served by ground water within a 3-mile radius:

The total population served by groundwater within a 3-mile radius of the site is greater than 12,500.

$$12,500 + 0 = 12,500$$

(Refs. 4, pp. 111-116; 9 and 10)

HRS Score = 5

HRS Matrix Score = 35

SURFACE WATER ROUTE

1. OBSERVED RELEASE

Contaminants detected in surface water at the facility or downhill from it (5 maximum):

Calcium, potassium and sodium were detected in the south ditch adjacent to the site in concentrations greater than five times the background.
(Ref. 7)

Rationale for attributing the contaminants to the facility:

The contaminants were found in high concentrations in the fill material and in the drainage path immediately south of the site.
(Ref. 7)

HRS Score = 45

2. ROUTE CHARACTERISTICS

Facility Slope and Intervening Terrain

Average slope of facility in percent:

Name/description of nearest downslope surface water:

Average slope of terrain between facility and above-cited surface water body in percent:

Is the facility located either totally or partially in surface water?

Is the facility completely surrounded by areas of higher elevation?

1-Year 24-Hour Rainfall in Inches

Distance to Nearest Downslope Surface Water

Physical State of Waste

3. CONTAINMENT

Containment

Methods of waste or leachate containment evaluated:

Method with highest score:

4. WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

The following elements and compounds were detected in the fill material: calcium, potassium, sodium, bis(2-ethylhexyl)phthalate and 4,4'-DDT. (Ref. 7, pp. 2 and 3)

Compound with highest score:

The following have a matrix score of 18 on the toxicity versus persistence matrix: sodium and 4,4'-DDT.
(Attachment 1)
HRS Score = 18

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (give a reasonable estimate even if quantity is above maximum):

Approximately 74,074 cubic yards of cement precipitator dust was placed at the site.
(Ref. 5, p. 4, Sec.VII.C.2)

Basis of estimating and/or computing waste quantity:

The FIT calculated the waste quantity from the estimated site dimensions.

$$\begin{array}{rcl} 200 \text{ ft. wide} \times 1000 \text{ ft. long} \times 10 \text{ ft. deep} & = & 74,074 \text{ cubic yards} \\ \hline & & 27 \text{ cubic ft.} \\ & & \hline & & 1 \text{ cubic yard} \end{array}$$

(Ref. 5, Attachment A)
HRS Value = 8

5. TARGETS

Surface Water Use

Use(s) of surface water within 3 miles downstream of the hazardous substance:

The surface water within 3 miles downstream of the site is used for shipping, non-contact recreation, high aquatic life and no domestic water supply.

(Ref. 12)
HRS Value = 1

Is there tidal influence?

There is tidal influence in the river near the site. The San Jacinto River north of the site is named "San Jacinto River Tidal" according to the Texas Water Commission.
(Refs. 12 and 16)

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

There is no coastal wetland within a 2 mile radius of the site.
(Ref. 2)
HRS Score = 0

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

There is no fresh-water wetland within a 1 mile radius of the site.
(Ref. 2)
HRS Score = 0

Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:

There is not a critical habitat or national wildlife refuge within a 1 mile radius of the site.
(Refs. 2 and 13)
HRS Score = 0

Population Served by Surface Water

Location(s) of water-supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static water bodies) downstream of the hazardous substance and population served by each intake:

There are no water supply intakes within 3 miles downstream of the site.
(Ref. 12)

Computation of land area irrigated by above-cited intake(s) and conversion to population (1.5 people per acre):

There are no water supply intakes downstream of the site.
(Ref. 12)

Total population served:

The total population served by surface water is zero.
(Ref. 12)

HRS Score = 0

Name/description of nearest of above water bodies:

NA.

Distance to above-cited intakes, measured in stream miles.

NA.

AIR ROUTE

1. OBSERVED RELEASE

Contaminants detected:

An observed release to the air was not evaluated.

Date and location of detection of contaminants:

Methods used to detect the contaminants:

Rationale for attributing the contaminants to the site:

2. WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

Most incompatible pair of compounds:

Toxicity

Most toxic compound:

Hazardous Waste Quantity

Total quantity of hazardous waste:

Basis of estimating and/or computing waste quantity:

3. TARGETS

Population Within 4-Mile Radius

Circle radius used, give population, and indicate how determined:

0 to 4 mi

0 to 1 mi

0 to $\frac{1}{2}$ mi

0 to $\frac{1}{4}$ mi

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

Distance to critical habitat of an endangered species, if 1 mile or less:

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

Distance to residential area, if 2 miles or less:

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Is a historic landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

ATTACHMENT 1

TOXICITY AND PERSISTENCE

Elements & Compounds	Toxicity (Ref 8)	Persistence (Ref 1, p. 18)
Calcium	Unknown (p. 616)	3
Potassium	Unknown (p. 2267)	3
Sodium	3 (p. 790)	3
Bis(2-ethylhexyl) phthalate	3 (p. 481)	3
4,4' -DDT	3 (p. 854)	3

HRS DOCUMENTATION LOG SHEET	SITE NAME: Goodson & Son Trucking CITY: Channelview STATE: Texas IDENTIFICATION NUMBER: TXD981052475
Reference Number	Description of the Reference
1.	Uncontrolled Hazardous Waste Site Ranking System: A Users Manual, 47 FR 31219-31243, 16 July 1982. (Appendix A: CERCLA).
2.	USGS 7.5 minute series topographic maps, Highlands, TX; 1982. Jacinto City, TX; 1982. La Porte, TX; 1982.
3.	Digital Models for Simulation of Ground-Water Hydrology of the Chicot and Evangeline Aquifers along the Gulf Coast of Texas. Report 289. May 1985. Texas Department of Water Resources.
4.	Ground-Water Data for Harris County, Texas. Volume II Records of Wells, 1892-1972. Report 178. January 1974. Texas Water Development Board.
5.	Pierce, Terry D., FIT Chemist. Potential Hazardous Waste Site, Site Inspection Report, Goodson & Son Trucking, Channelview, TX. TXD981052475. November 10, 1987.
6.	Soil Survey of Harris County, Texas. August 1976. United States Department of Agriculture, Soil Conservation Survey.
7.	Cason, Victor, FIT Chemist. Sampling Inspection Report, Goodson & Son Trucking, Channelview, TX. TXD981052475. February 28, 1989.
8.	Sax, Irving. Dangerous Properties of Industrial Materials, Sixth edition, 1984. Van Nostrand Reinhold Co.
9.	ROC. TO: Rickey Hennigan, Operator, Harris County Water Control and Improvement District #21, Channelview, TX. FROM: Victor Cason, FIT Chemist. EPA Region VI. Re: Location and population served by the wells in district #21. March 6, 1989.
10.	ROC. TO: Steve Early, operator, Harris County Water District #6, Channelview, TX. FROM: Victor Cason, FIT Chemist. EPA Region VI. Re: Location and population served by the wells in district #6. March 6, 1989.

HRS DOCUMENTATION LOG SHEET		SITE NAME: Goodson & Son Trucking CITY: Channelview STATE: Texas IDENTIFICATION NUMBER: TXD981052475	
Reference Number	Description of the Reference		
11.	Rainfall Frequency Atlas of the United States, Technical Paper No. 40. U.S. Department of Commerce.		
12.	ROC. TO: Jim Rice, Field Inspector, Texas Water Commission, Deer Park, TX. FROM: Victor Cason, FIT Chemist. EPA Region VI. Re: Uses of the San Jacinto River upstream and downstream of the site.		
13.	LETTER. TO: Victor Cason, FIT Chemist. EPA Region VI. FROM: Dorinda Sullivan, Data Manager, Texas Natural Heritage Program. November 10, 1988. Re: Sensitive habitats within a 3-mile radius of the site.		
14.	ROC. TO: Ernest Baker, Hydrologist, USGS Austin, TX. FROM: Victor Cason, FIT Chemist. EPA Region VI. Re: The Extent of the Alta Loma Sand near the site.		
15.	Ground-Water Data for Harris County, Texas. Volume I Drillers' Logs of Wells, 1905-71. Report 178. November 1973. Texas Water Development Board.		
16.	ROC. TO: Jim Rice, Field Inspector, Texas Water Commission, Deer Park, TX. FROM: Victor Cason, FIT Chemist. EPA Region VI. Re: Tidal influence of the San Jacinto River near the site.		

REFERENCES


If the entire reference is not available for public review in the EPA regional files on this site, indicate where the reference may be found:

Reference Number	Description of the Reference
1	Uncontrolled Hazardous Waste Site Ranking System: A Users Manual. 47 FR 31219-31243, 16 July 1982 (Appendix A, CERCLA).

Ref 3

Report 289

**DIGITAL MODELS FOR SIMULATION
OF GROUND-WATER HYDROLOGY
OF THE CHICOT AND EVANGELINE
AQUIFERS ALONG THE GULF
COAST OF TEXAS**



TEXAS DEPARTMENT OF WATER RESOURCES

Chicot Aquifer

The Chicot aquifer is composed of the Willis Sand, Bentley Formation, Montgomery Formation, Beaumont Clay, and Quaternary alluvium. The Chicot includes all deposits from the land surface to the top of the Evangeline aquifer. The altitude of the base of the Chicot aquifer is shown in Figures 4 and 5.

In much of the coastal area, the Chicot aquifer consists of discontinuous layers of sand and clay of about equal total thickness. However, in some parts of the coastal area (mainly within the Houston area), the aquifer can be separated into an upper and lower unit (Jorgensen, 1975). The upper unit can be defined where the altitude of its potentiometric surface differs from the altitude of the potentiometric surface in the lower unit. If the upper unit of the Chicot aquifer cannot be defined, the aquifer is said to be undifferentiated. The aquifer is under water-table conditions in its updip part, becoming confined in the downdip direction. Throughout most of Galveston County and southeast Harris County, the basal part of the Chicot aquifer is formed by a massive sand section that has a relatively high hydraulic conductivity. This sand unit, which is heavily pumped in some places, is known locally as the Alta Loma Sand (Alta Loma Sand of Rose, 1943).

Evangeline Aquifer


The Evangeline aquifer, which consists mostly of discontinuous layers of sand and clay of about equal total thickness, is composed of the Goliad Sand and the uppermost part of the Fleming Formation. The altitude of the base of the Evangeline aquifer is shown in Figures 6 and 7. Because the Chicot and Evangeline aquifers are geologically similar, the basis for separating them is primarily a difference in hydraulic conductivity, which in part causes the difference in the altitudes of the potentiometric surfaces in the two aquifers. The aquifer is under water-table conditions in its updip part, becoming confined in the downdip direction.

Burkeville Confining Layer


The Burkeville confining layer, which is composed of the upper part of the Fleming Formation, consists mainly of clay but contains some layers of sand. The Burkeville, which underlies the Evangeline aquifer, restricts the flow of water except in areas where it is pierced by salt domes and in areas where it contains a high percentage of sand.

DESCRIPTION OF THE DIGITAL MODELS

The conceptual model (Figure 8) for the four modeled subregions (Figure 9) consists of five layers. In ascending order, layer 1 is equivalent to the total thickness of the sand beds in the Evangeline aquifer; layer 2 is equivalent to the clay thickness between the centerline of the Chicot aquifer and the centerline of the Evangeline aquifer; layer 3 is equivalent to the Alta Loma Sand of Rose (1943) where present, otherwise it is equivalent to the total thickness of the sand beds in the Chicot aquifer; layer 4 is equivalent to the clay thickness between the land surface and the centerline of the Chicot aquifer; and layer 5 is used as an upper boundary to simulate recharge to



*TEXAS
WATER
DEVELOPMENT
BOARD*



Report 178

*GROUND-WATER DATA FOR
HARRIS COUNTY, TEXAS
VOLUME II
RECORDS OF WELLS, 1892-1972*

January 1974

Records of wells in Harris County

All wells are drilled unless otherwise noted in remarks column.

Water level : Reported water levels given in feet; measured water levels given in feet and tenths.

Method of lift and type of power: A, airlift; B, bucket; C, cylinder; CF, centrifugal; E, electric; G, gasoline, oil, butane, or diesel engine; NG, natural gas; H, hand; J, jet; N, none; Sub, submersible; T, turbine; W, windmill. Number indicates horsepower.

Use of water : D, domestic; Ind, industrial; Irr, irrigation; N, none; P, public supply; S, livestock.

Water bearing unit : C, Chicot aquifer; CU, Upper unit of Chicot aquifer; CL, Lower unit of Chicot aquifer; E, Evangeline aquifer; J, Jasper aquifer.

No.	Owner	Driller	Date completed	Depth of well (ft.)	Casing		Water bearing unit	Altitude of land surface (ft.)	Water Level		Method of lift	Use of Water	Remarks
					Diameter (in.)	Depth (ft.)			Above (+) below land surface datum (ft.)	Date of Measurement			
60-57-202	Mrs. A. F. Knebel	Unknown	1908	52	20	52	C	281	30.8	Oct. 22, 1963	J,E	D,S	Dug and bored to 52 ft. 20 inch tile casing with open end.
301	Ada Oil Co.	Katy Drilling Co.	1959	778	16 1/2	301 778	E	287	135.3	Oct. 1963	T,E 100	Irr,S	Screen from 588 to 778 ft. Supplies lake. 2/
302	B. H. Mohrkam	B. E. Petry	1963	120	4	120	C	260	41.8	Oct. 22, 1963	C,W	S	Screen from 114 to 120 ft.
303	Stokes	Unknown	--	60	4	60	C	266	18.1	Nov. 5, 1931	N	N	Well destroyed.
501	B. F. Quinn	Unknown	--	20	3	20	C	255	3.5	May 13, 1931	N	N	Test well. Well destroyed.
502	Dr. Berry	Unknown	--	42	24	42	C	264	34.0	Apr. 13, 1931	B,H	D	Dug well. Reported dug to 80 ft. Measured 42 ft. in 1931.
503	H. H. Strickland	H. H. Strickland	1918	30	10	30	C	245	7.0 13.4	Apr. 13, 1931 Aug. 2, 1933	N	N	Bored well. Wood casing. Well destroyed.
504	C. H. Burton	Unknown	1931	22	10	22	C	245	7.0 6.9	Apr. 13, 1931 Feb. 12, 1962	N	N	Dug well. Well destroyed. 3/
601	Warren Vincent	Roy Turner	1947	734	18 1/4 14 1/2 12	218 432 734	E,C	277	--	--	T,Ng	Irr	Casing slotted from 100 to 734 ft.
602	Hurricane Fence Co.	Layne Texas Co.	1948	800	20 1/2 12 8	250 614 800	E	271	94	Mar. 1948	T,Ng	Irr	315 ft. of slotted casing between 250 and 775 ft. Reported yield 1,525 gpm with 45 ft. drawdown when drilled. 2/
603	Schindler Farms	Katy Drilling Co.	1951	825	24 1/8 16 10	300 510 825	E,C	264	--	--	T,E 200	Irr	Casing slotted from 104 to 825 ft. 2/
604	B. L. Snowden	B. E. Petry	1938	211	4	211	E	260	37	1938	C,E 1	D,S	Screen from 201 to 211 ft.
605	T. W. Ray	Unknown	1870	71	24 8	40 71	C	276	48.6	Nov. 6, 1931	N	N	Bored well; tile casing; open end. Well destroyed.
606	Elmer Bennett	Unknown	--	100	4	100	C	261	42.1	Nov. 5, 1931	N	N	Bored well. Well destroyed.
607	Schindler Farms	H. H. Strickland	1926	122	4	122	C	256	48.3 78.8	Apr. 13, 1931 Feb. 12, 1971	N	N	1/
608	Schindler Farms Well 2	Layne Texas Co.	1968	857	20 1/2 12	369 857	E	264	131	Apr. 8, 1968	T,Ng	Irr	378 ft. of slotted casing between 250 and 843 ft. Reported yield 3,024 gpm with 136 ft. drawdown when drilled. 2/
609	Charlie Kmalac	Schoppa Water Well Service	1969	265	4 1/2	-- 265	E	275	115	Apr. 29, 1969	Sub,E 1	D	Screen from 255 to 265 ft. 2/
610	Owen Glover, Jr.	do	1969	254	4	254	E	274	115	Apr. 20, 1969	Sub,E 1	D	Screen from 244 to 254 ft. 2/
901	W. O. Dennison and Sons	Katy Drilling Co.	1954	1,453	20 1/2 12	359 1,453	E	229	--	--	T	Irr	Casing slotted from 253 to 1,453 ft. 2/
902	J. C. Jenkins	A. H. Justman	1951	622	20 1/2 12	200 622	E	237	--	--	T,E	Irr	Casing slotted from 272 to 622 ft.
904	J. A. Hafner	Unknown	1931	21	3	21	C	246	4.0 7.3	May 1, 1931 Mar. 13, 1936	N	N	Well destroyed. 3/
905	C. I. Garrett	Hiram Bennett	1905	70	8	70	C	245	44.6 47.8	Apr. 25, 1931 Mar. 4, 1960	N	N	Well destroyed. 3/
906	do	H. H. Strickland	1900	61	6	61	C	246	45.2 50.4	Apr. 13, 1931 Jun. 14, 1956	J,E	D	3/

See footnotes at end of table.

Records of wells in Harris County--continued

No.	Owner	Driller	Date completed	Depth of well (ft.)	Casing		Water bearing unit	Altitude of land surface (ft.)	Water level		Method of lift	Use of water	Remarks
					Diameter (in.)	Depth (ft.)			Abn. (+) below land surface datum (ft.)	Date of Measurement			
65-16-106	Arco Chemical Co.	Layne Texas Co.	1940	312	12 7	194 312	CL	40	65 151.7	Feb. 9, 1940 Feb. 6, 1968	T,E	N	74 ft. of screen between 201 and 291 ft. Reported yield 600 gpm with 88 ft. drawdown when drilled. Supplies swimming pool. 2/ 3/
107	Banana Bend Estate Well 2	T. C. Russell and Son	1963	395	4	395	CL	10	--	--	Sub,E 5	P	Screen from 375 to 395 ft.
109	Southland Paper Mill Well 1	Texas Water Wells, Inc.	1966	1,625	24 14	840 1,625	E	49	101 267	Sept. 11, 1966 Apr. 8, 1970	T,E 500	Ind	342 ft. of screen between 842 and 1,614 ft. Reported yield 2,100 gpm with 48 ft. drawdown Sept. 11, 1966. Test hole drilled to 1,672 ft. 1/ 2/
110	Southland Paper Mill Well 2	do	1966	1,625	24 14	796 1,625	E	48	280 263	Feb. 7, 1969 Apr. 8, 1970	T,E 500	Ind	373 ft. of screen between 806 and 1,610 ft. Test hole drilled to 1,627 ft. 1/ 2/
111	Southland Paper Mill Well 4	do	1966	1,568	24 14	918 1,568	E	46	192 263	Feb. 7, 1967 Apr. 8, 1970	T,E 500	Ind	346 ft. of screen between 923 and 1,551 ft. Reported yield 2,100 gpm with 40 ft. drawdown Feb. 7, 1967. Test hole drilled to 1,595 ft. 1/ 2/
112	Southland Paper Mill Well 5	do	1966	1,593	24 14	845 1,593	E	40	185 259	Dec. 8, 1967 Apr. 8, 1970	T,E 500	Ind	321 ft. of screen between 853 and 1,577 ft. Reported yield 2,100 gpm with 19 ft. drawdown Dec. 8, 1967. Test hole drilled to 1,718 ft. 1/ 2/
113	Southland Paper Mill Well 6	do	1966	1,712	24 14	876 1,712	E	11	182 236	Jan. 1, 1967 Apr. 8, 1970	T,E 500	Ind	378 ft. of screen between 880 and 1,697 ft. Reported yield 2,100 gpm with 39 ft. drawdown Jan. 14, 1967. Test hole drilled to 1,720 ft. 1/ 2/
201	Mills Water Supply	Heffinger	1957	272	6 4	240 272	CL	17	121	1961	T,E 10	P	Supplies Garrett Station.
202	McDermott and Barnhart Ranch	Layne Texas Co.	1949	926	24 14	319 926	CL,E	50	95	Mar. 7, 1949	T,E	Err	329 ft. of screen between 531 and 914 ft. Reported yield 2,919 gpm with 40 ft. drawdown when drilled.
205	Arcadian Gardens Corp.	do	1956	315	8 6	215 315	CL	45	107	Mar. 20, 1956	T,E 25	P	60 ft. of screen between 225 and 297 ft. Reported yield 259 gpm with 14 ft. drawdown when drilled.
206	Lester Schuler	A and L Pump and Well Service	1963	260	4	260	CL	51	110	Jan. 1963	Sub,E 1 1/2	b	Screen from 245 to 260 ft. 2/
301	D. R. Lang	Unknown	--	90	3	90	CU	47	5.2	June 27, 1939	N	N	Well destroyed.
302	R. Sralia	T. E. Reidland	1933	98	3 1 1/2	24 98	CU	44	20	1933	N	N	Screen from 91 to 98 ft. Well destroyed.
303	do	do	--	298 1/2	3	--	C	49	--	--	N	N	
401	Arco Chemical Co.	Texas Water Wells, Inc.	1956	1,575	20 12	725 1,575	E	45	165	Mar. 27, 1956	T,E 400	Ind	250 ft. of screen between 780 and 1,565 ft. Reported yield 2,316 gpm with 73 ft. drawdown when drilled.
402	J. McDonald	J. W. Evans	1941	228	3 2	222 228	CL	30	76	Sept. 1941	N	N	Screen from 222 to 228 ft. Well destroyed.
403	Harris County WC and ID No. 84	Layne Texas Co.	1964	1,125	16 10	702 1,125	E	40	250	Oct. 29, 1964	T,E 125	P	154 ft. of screen between 710 and 1,115 ft. Reported yield 1,010 gpm with 76 ft. drawdown when drilled.
404	Baroid Co.	do	1965	750	10 6	570 750	CL,E	43	222	Dec. 23, 1965	T,E 60	Ind	90 ft. of screen between 580 and 735 ft. Reported yield 350 gpm with 54 ft. drawdown when drilled. Test hole drilled to 880 ft. 2/

See footnotes at end of table.

Records of wells in Harris County--Continued

No.	Owner	Driller	Date completed	Depth of well (ft.)	Casing		Water bearing unit	Altitude of land surface (ft.)	Water Level		Method of lift	Use of Water	Remarks
					Diameter (in.)	Depth (ft.)			Above (+) below land surface datum (ft.)	Date of Measurement			
65-16-405	W. B. Williams	Lowry Water Wells	1967	421	4 2 1/2	402 421	CL	36	210	Aug. 28, 1967	Sub, E 1 1/2	D	Screen from 405 to 420 ft. 2/
406	Conrad Ermel	A and L Pump and Well Service	1968	286	4 2 1/2	263 286	CL	36	188	Mar. 1968	Sub, E 1	D	Screen from 271 to 286 ft. 2/
407	W. B. Wade	H and H Water Well Drilling	1968	292	4	292	CL	37	182	Mar. 1, 1968	Sub, E 1	D	Screen from 282 to 292 ft. 2/
502	Harris County F.W.D. No. 1 Well 1	Layne Texas Co.	1949	482	16 8	415 482	CL	38	--	--	T, E	P	Screen from 429 to 471 ft. Original depth was 551 ft. Well reworked 1963. Reported yield 326 gpm in 1963.
503	Harris County F.W.D. No. 1 Well 2	do	1949	476	12 6	417 476	CL	39	176.7	May 11, 1962	T, E	P	Casing slotted from 421 to 476 ft.
504	Harris County WC and ID No. 1	do	1962	510	16 10 8	380 482 510	CL	41	165.8	Oct. 24, 1962	T, E	P	Screen from 390 to 490 ft. Reported yield 752 gpm with 28 ft. drawdown when drilled. 2/
505	do	McMasters and Pomeroy	1940	606	8 7 6	403 -- 606	CL	39	80	Apr. 1940	N	N	98 ft. of screen between 417 and 589 ft. Reported yield 500 gpm with 92 ft. drawdown when drilled. Well destroyed.
506	do	Layne Texas Co.	1931	537	8 6 4	125 -- 537	CL	40	--	--	N	N	Screen from 502 to 537 ft. Reported yield 100 gpm when drilled. Well destroyed.
507	Elmer Moore, Jr.	A and L Pump and Well Service	1962	103	2	103	CU	43	17	Oct. 1962	J, E 1	D	Screen from 97 to 103 ft. 2/
508	Texas Highway Department	Lowry Water Wells	1966	468	6 4	414 468	CL	30	204.4 221.6	Sept. 9, 1966 Feb. 19, 1971	Sub, E	P	Screen from 413 to 453 ft. Supplies roadside park. 1/ 2/
509	do	do	1966	464	6 4	412 464	CL	34	203.9 221.0	Sept. 9, 1966 Feb. 19, 1971	Sub, E	P	Screen from 415 to 455 ft. Supplies roadside park. 1/
601	Harris County F.W.D. No. 1B	Layne Texas Co.	1949	489	10 6	364 489	CL	39	128	June 1949	T, E 40	P	61 ft. of screen between 375 and 471 ft. Reported yield 318 gpm with 16 ft. drawdown when drilled.
602	Harris County F.W.D. No. 1A	do	1953	498	10 5	390 498	CL	36	138	June 1953	T, E 40	P	Screen from 397 to 477 ft. Reported yield 348 gpm with 25 ft. drawdown when drilled.
603	Harris County F.W.S.D. No. 1	J. H. Morton	1935	500	4	500	CL	36	--	--	N	N	Screen from 460 to 500 ft. Well destroyed.
604	do	C. A. Williams	1939	480	6	480	CL	36	--	--	N	N	Screen from 440 to 480 ft. Well destroyed.
605	L. B. Standley	Lowry Water Wells	1965	431	4 2 1/2	338 431	CL	41	148	Mar. 30, 1965	Sub, E 2	P	42 ft. of screen between 338 and 398 ft. 2/
606	Atlantic Richfield Co.	A and L Pump and Well Service	1968	435	4 2 1/2	390 435	CL	36	200	Dec. 26, 1968	Sub, E 2	Ind	Screen from 420 to 435 ft. Supplies service station. 2/
607	Bobby Smith	Sugg and Smith Drilling Co.	1969	322	4 2 1/2	300 322	CL	40	175	Mar. 10, 1969	Sub, E 2	D	Screen from 307 to 322 ft. Reported yield 28 gpm with 24 ft. drawdown when drilled. 2/
701	Harris County WC and ID No. 21	Layne Texas Co.	1951	902	16 8	710 902	E	36	208.5 235.7	July 18, 1951 Feb. 20, 1959	T, E 100	P	102 ft. of screen between 719 and 890 ft. Reported yield 760 gpm with 45 ft. drawdown when drilled. 2/ 3/

See footnotes at end of table.

Records of wells in Harris County--Continued

No.	Owner	Driller	Date completed	Depth of well (ft.)	Casing		Water bearing unit	Altitude of land surface (ft.)	Water Level		Method of lift	Use of Water	Remarks
					Diameter (in.)	Depth (ft.)			Above (+) below land surface datum (ft.)	Date of Measurement			
65-16-702	Harris County WC and ID No. 21	Layne Texas Co.	1949	663	10 6	391 663	CL	33	156	June 30, 1949	T,E	P	93 ft. of screen between 398 and 680 ft. Reported yield 500 gpm with 68 ft. drawdown when drilled.
703	San Jacinto Inn	L. Patterson	1936	650	4	650	E	5	--	--	N	N	Screen from 622 to 644 ft. Well destroyed. 2/
704	Old River Terrace Well 2	A. E. Fawcett, Jr.	1947	276	8	276	C	33	--	--	N	N	Reported 43 ft. of screen. Well destroyed.
705	Old River Terrace Well 3	A. E. Fawcett, Sr.	1943	238	6	238	C	34	--	--	N	N	Reported 25 ft. of screen.
706	Old River Terrace Well 1	do	1947	304	6	304	CL	36	70	Jan. 11, 1949	N	N	Screen from 283 to 304 ft.
707	Harris County F.W.S.D. No. 6	McMasters and Pomeroy	1940	640	8 6	600 640	CL	34	--	--	T,E 10	P	Reported 40 ft. of screen.
708	Jacintoport Corp. Well 1	Layne Texas Co.	1941	449	8 6	374 449	CL	30	95 256.3	Aug. 18, 1941 Mar. 8, 1966	N	N	Screen from 399 to 449 ft. Reported yield 210 gpm with 12 ft. drawdown when drilled. Well destroyed. 2/ 3/
709	Jacintoport Corp. Well 5	do	1941	447	8 6	372 447	CL	31	95 239.3	Aug. 10, 1941 Feb. 23, 1971	N	N	Screen from 397 to 447 ft. Reported yield 210 gpm with 12 ft. drawdown when drilled. 1/ 2/
710	Harris County WC and ID No. 21	Katy Drilling Co.	1966	1,220	16 10	710 1,220	E	33	276.2	Aug. 20, 1966	T,E 150	P	200 ft. of screen between 730 and 1,210 ft. Reported yield 1,000 gpm with 107 ft. drawdown when drilled. Test hole drilled to 1,309 ft. 2/
711	San Jacinto Inn	A. Chrysty Kuhlmann	1962	376	4 2 1/2	-- 376	CL	5	--	--	Sub,E 1	P	Screen from 366 to 376 ft. 2/
712	Humble Oil and Refining Co.	Lowry Water Wells	1963	320	4 2 1/2	304 320	CL	33	200	Mar. 3, 1963	Sub,E 1 1/2	Ind	Screen from 307 to 317 ft. Supplies service station. 2/
714	Harris County F.W.D. No. 6	Layne Texas Co.	1965	645	8 6	560 645	CL	33	154	Aug. 28, 1965	T,E 20	P	58 ft. of screen between 565 and 638 ft. Reported yield 311 gpm with 28 ft. drawdown when drilled. 2/
715	Key Oil Co.	Lowry Water Wells	1968	454	4 2 1/2	-- 454	CL	33	221	May 14, 1968	Sub,E 5	Ind	Screen from 417 to 447 ft. Supplies service station. 2/
716	Production Systems International	B. J. Swinehart Co.	1968	468	4 2	442 468	CL	5	254	Apr. 1968	Sub,E 5	Ind	Screen from 446 to 466 ft. 2/
717	Texaco Inc.	Lowry Water Wells	1964	233	4 2 1/2	214 233	CL	32	176	June 16, 1964	Sub,E 2	Ind	Screen from 218 to 233 ft. Supplies service station. 2/
718	Hutchinson-Hayes International, Inc.	A. Chrysty Kuhlmann	1969	612	8 4	588 612	CL	30	277	June 1969	Sub,E 15	Ind	Screen from 590 to 612 ft. 2/
719	Key Oil Co.	Lowry Water Wells	1968	455	4 2 1/2	423 455	CL	33	221	Nov. 7, 1968	Sub,E 5	Ind	Screen from 425 to 455 ft. Supplies service station. 2/
720	San Jacinto Inn	A. Chrysty Kuhlmann	1970	644	4 2 1/2	617 644	E	5	300	June 1970	Sub,E	P	Screen from 619 to 644 ft. Reported yield 50 gpm with 20 ft. drawdown when drilled. Supplies restaurant. 2/
801	Gulf Pipe Line Co.	Layne Texas Co.	1929	434	6	434	CL	5	84.2 223.3	Sept. 23, 1943 Feb. 19, 1971	Sub,E	Ind	Screen from 328 to 415 ft. 1/ 2/
802	Texas Highway Department Lynchburg Ferry	B. J. Swinehart Co.	1964	440	4	440	CL	5	200	June 2, 1964	Sub,E	D	Screen from 419 to 439 ft. 2/

See footnotes at end of table.

WELL USED
FOR DEPTH
TO WATER

Records of wells in Harris County--Continued

No.	Owner	Driller	Date completed	Depth of well (ft.)	Casing		Water bearing unit	Altitude of land surface (ft.)	Water Level		Method of lift	Use of Water	Remarks
					Diam-eter (in.)	Depth (ft.)			Above (+) below land surface datum (ft.)	Date of Measurement			
65-16-803	W. A. Hill	Lowry Water Wells	1965	355	4 2 1/2	322 355	CL	32	205	Nov. 12, 1965	Sub. E 2	D	20 ft. of screen between 324 and 355 ft. Test hole drilled to 359 ft. 2/
804	C. S. Todd	A and L Pump and Well Service	1966	360	4 2 1/2	345 360	CL	36	194	Mar. 19, 1966	Sub. E 1 1/2	D	Screen from 345 to 360 ft. 2/
901	Humble Oil and Refining Co.	Layne Texas Co.	1947	471	3	471	CL	29	72.5 137.2	Dec. 1947 June 4, 1964	N	N	Screen from 458 to 471 ft. Drilled to 2,145 ft. Humble test well No 44. Plugged back to 471 ft. Well destroyed. 3/
902	City of Baytown Craigmont Well	do	1957	500	14 8	370 500	CL	24	178	June 19, 1957	T. E	P	Screen from 384 to 490 ft. Reported yield 1,022 gpm with 50 ft. drawdown when drilled.
903	Harris County F.W.D. No. 27 Coady	Lowry Water Wells	1954	480	10 5	400 480	CL	30	152	Feb. 1954	T. E 40	P	Screen from 400 to 480 ft.
904	City of Baytown Well 6	Layne Texas Co.	1952	512	12 6	-- 512	CL	24	190 203 223.1	Sept. 10, 1952 Feb. 7, 1956 May 11, 1962	T. E	P	Screen from 418 to 500 ft. Reported yield 524 gpm with 32 ft. drawdown when drilled. 2/
905	City of Baytown Well 13	do	1952	500	12 6	-- 500	CL	23	165	July 22, 1952	T. E	P	Screen from 408 to 488 ft. Reported yield 608 gpm with 40 ft. drawdown when drilled.
906	Humble Oil and Refining Co. Well 46	do	1948	1,601	10	--	E	30	--	--	N	N	Drilled to 1,601 ft. Humble test well.
907	Humble Oil and Refining Co. Well 47	do	1949	1,727	24 12 10	770 1,131 1,727	E	27	151 231.4	Oct. 1953 Feb. 28, 1971	N	N	330 ft. of screen between 776 and 1,724 ft. 1/
908	Humble Oil and Refining Co. Well 48	do	1949	1,583	6 4	216 1,583	E	29	195 216.9	Dec. 11, 1950 Oct. 9, 1968	N	N	53 ft. of screen between 803 and 1,550 ft. Drilled to 1,616 ft. Humble test well. Plugged back to 1,583 ft. 2/ 3/
909	Humble Oil and Refining Co. Well 29	Texas Water Wells, Inc.	1941	509	24 12	274 609	CL	30	129	1944	N	N	167 ft. of screen between 270 and 504 ft. Reported yield 2,500 gpm when drilled. Well destroyed.
910	Humble Oil and Refining Co. Well 30	Texas Water Supply Corp.	1941	525	24 12	261 525	CL	31	126 240.8	Sept. 26, 1944 1967	N	N	127 ft. of screen between 379 and 521 ft. Well destroyed. 3/
911	City of Baytown Well 14	Katy Drilling Co.	1961	510	20 14	380 510	CL	29	214	July 1, 1961	T. E 150	P	Screen from 401 to 507 ft. Reported yield 1,506 gpm with 39 ft. drawdown when drilled. Test hole drilled to 603 ft. 2/
912	City of Baytown Well 11	do	1962	496	20 14	380 496	CL	25	203	June 10, 1962	T. E 200	P	Screen from 386 to 492 ft. Reported yield 1,515 gpm with 42 ft. drawdown when drilled. Test hole drilled to 627 ft. 2/
913	Golden	J. W. Evans	1940	338	3 2	-- 338	CL	31	--	--	N	N	Screen from 328 to 338 ft.
914	Q. G. Barber	Layne Texas Co.	1938	520	8 6	466 520	CL	28	103	Mar. 31, 1938	N	N	Screen from 466 to 516 ft. Reported yield 200 gpm with 9 ft. drawdown when drilled. Well destroyed.

See footnotes at end of table.

Records of wells in Harris County--Continued

No.	Owner	Driller	Date completed	Depth of well (ft.)	Casing		Water bearing unit	Altitude of land surface (ft.)	Water Level		Method of lift	Use of water	Remarks
					Diameter (in.)	Depth (ft.)			Above (+) below land surface datum (ft.)	Date of measurement			
65-16-915	Humble Oil and Refining Co. Well 24	Layne Texas Co.	1938	905	6 2 1/2	206 905	E	28	60	July 1938	N	N	Screen from 883 to 905 ft. Test hole drilled to 961 ft. Plugged back to 905 ft. Well destroyed.
916	Humble Oil and Refining Co. Well 50	do	1952	546	20 14	425 546	CL	28	190 243	Aug. 27, 1952 Jan. 13, 1966	T, E	Ind	Reported 100 ft. of screen. Reported yield 2,300 gpm with 70 ft. drawdown when drilled. 2/
917	Humble Oil and Refining Co. Well 29A	do	1961	512	24 16 10	390 -- 512	CL	27	249 247	Sept. 5, 1963 Jan. 14, 1966	T, E	Ind	80 ft. of screen between 400 and 500 ft. Reported yield 1,980 gpm with 51 ft. drawdown Jan. 14, 1966. Test hole drilled to 598 ft. 2/
918	Ashland Chemical Co. Well 2	McMasters and Pomeroy	1958	458	8	458	CL	27	265	Feb. 3, 1971	T, E 40	Ind	80 ft. of screen between 315 and 439 ft.
919	Ashland Chemical Co. Well 3	Layne Texas Co.	1946	517	16 8	-- 517	CL	27	159 259	Oct. 1946 July 1966	T, E 100	Ind	Screen from 401 to 502 ft. Reported yield 1,760 gpm with 36 ft. drawdown when drilled.
920	Ashland Chemical Co. Well 4	do	1956	514	20 12	-- 514	CL	27	209 238	June 11, 1956 May 10, 1963	T, E 125	Ind	Screen from 395 to 500 ft. Reported yield 1,060 gpm with 31 ft. drawdown when drilled. 2/

See footnotes at end of table.




Figure 7
Locations of Wells in Area 6

Base from U.S. Geological Survey
topographic quadrangles

Records of wells in Harris County--Continued

No.	Owner	Driller	Date completed	Depth of well (ft.)	Casing		Water bearing unit	Altitude of land surface (ft.)	Water Level		Method of lift	Use of Water	Remarks
					Diame-ter (in.)	Depth (ft.)			Above (+) below land surface datum (ft.)	Date of Measure-ment			
65-23-203	Crown Central Petroleum Co. Well 8	McMasters and Pomeroy	1944	1,262	12 10 8	-- 1,262	E	31	272	Sept. 1950	T, E 125	Ind	175 ft. of screen between 680 and 1,256 ft. <u>2/</u>
204	Crown Central Petroleum Co. Well 9	Layne Texas Co.	1950	1,274	16 8	-- 1,274	E	32	288	July 17, 1950	T, E 125	Ind	197 ft. of screen between 816 and 1,263 ft. Test hole drilled to 1,300 ft. <u>2/</u>
205	Araco Steel Corp. Well 1	do	1943	1,385	18 10	505 1,385	E	25	260	Jan. 18, 1951	T, E 150	Ind	217 ft. of screen between 950 and 1,350 ft. Reported yield 1,365 gpm with 55 ft. drawdown Jan. 1951.
206	Araco Steel Corp. Well 2	do	1943	1,266	18 10	492 1,266	E	30	254 327	Jan. 4, 1951 Mar. 6, 1962	T, E 150	Ind	161 ft. of screen between 831 and 1,238 ft. Reported yield 1,266 gpm with 61 ft. drawdown Jan. 4, 1951.
207	Araco Steel Corp. Well 3	do	1943	1,255	18 10	381 1,255	E	30	254	Jan. 11, 1951	T, E 150	Ind	190 ft. of screen between 778 and 1,252 ft. Reported yield 1,266 gpm with 64 ft. drawdown Jan. 11, 1951.
208	Olin Corp.	do	1948	412	10 8	190 412	CL	15	160	1958	T, E 40	Ind	111 ft. of screen between 219 and 410 ft. Reported yield 280 gpm with 50 ft. drawdown in 1958.
209	do	do	1948	918	10 8	200 918	E	15	--	--	N	N	111 ft. of screen between 756 and 906 ft.
210	do	McMasters and Pomeroy	1944	673	8 5	320 673	CL	15	--	--	N	N	100 ft. of screen between 342 and 673 ft. Well destroyed. <u>2/</u>
211	do	do	1944	705	8 5	330 705	E, CL	15	--	--	N	N	100 ft. of screen between 364 and 705 ft. Well destroyed. <u>2/</u>
212	Olin Corp. Well 3	Layne Texas Co.	1951	982	12 8	820 982	E	15	272	June 20, 1951	T, E	Ind	80 ft. of screen between 830 and 970 ft. Reported yield 530 gpm with 38 ft. drawdown when drilled.
213	Phillips Chemical Co. Well 4	do	1951	884	22 10	612 884	E	30	262 310	Sept. 1951 1962	T, E 125	Ind	100 ft. of screen between 697 and 866 ft. Reported yield 767 gpm with 36 ft. drawdown when drilled.
214	Phillips Chemical Co. Well 5	do	1952	1,967	20 12	1,220 1,967	E	25	275 353	July 29, 1952 May 1970	T, G	Ind	216 ft. of screen between 1,429 and 1,955 ft. Reported yield 1,705 gpm with 60 ft. drawdown when drilled. <u>1/</u>
215	Phillips Chemical Co. Well 6	do	1952	1,220	20 12	695 1,220	E	25	388	Sept. 15, 1970	T, E	Ind	210 ft. of screen between 730 and 1,200 ft. Reported yield 1,500 gpm with 30 ft. drawdown Sept. 1970.
216	Phillips Chemical Co. Well 3	McMasters and Pomeroy	1943	639	8 5	284 639	CL	10	86	June 9, 1943	N	N	95 ft. of screen between 351 and 639 ft. Reported yield 380 gpm when drilled. <u>2/</u>
217	Ethyl Corp. Well 1A	Layne Texas Co.	1951	459	8 8	387 459	CL	15	159	June 12, 1951	N	N	Screen from 394 to 450 ft. Construction well for plant. Well destroyed.
218	Ethyl Corp. Well 5A	do	1951	453	14 10	308 453	CL	18	159 267	June 1951 Feb. 23, 1971	T, E	Ind	Screen from 309 to 440 ft. Reported yield 1,543 gpm with 46 ft. drawdown when drilled. <u>1/</u>
219	Ethyl Corp. Well 4L	do	1951	1,252	20 12 10	692 1,050 1,252	E	21	275 366	Feb. 15, 1955 Feb. 23, 1971	T, E	Ind	290 ft. of screen between 698 and 1,235 ft. Reported yield 1,800 gpm with 54 ft. drawdown Dec. 1954. <u>1/</u>
220	Ethyl Corp. Well 3A	do	1951	477	14 10	328 477	CL	20	155.2 269	May 10, 1951 Feb. 23, 1971	T, E	Ind	Screen from 329 to 465 ft. Reported yield 1,515 gpm with 60 ft. drawdown when drilled. <u>1/</u>

See footnotes at end of table.




Figure 9
Locations of Wells in Area 8

Records of wells in Harris County--Continued

No.	Owner	Driller	Date completed	Depth of well (ft.)	Casing		Water bearing unit	Altitude of land surface (ft.)	Water Level		Method of lift	Use of Water	Remarks
					Di- am- eter (in.)	Depth (ft.)			Above (+) below land surface datum (ft.)	Date of Measure- ment			
64-17-111	City of Goose Creek Well 1	Layne Texas Co.	1927	838	10 6	735 838	E	33	--	--	N	N	Screen from 735 to 834 ft. Well destroyed.
112	City of Goose Creek Well 2	Humble Oil and Refining Co.	1927	970	8 6	370 970	E	33	--	--	N	N	Well destroyed.
113	Humble Oil and Refining Co.	Pitre Water Wells	1962	105	4	105	CU	33	32	Aug. 1962	J.E 2	Ind	Screen from 73 to 95 ft. <u>2/</u>
201	City of Baytown Well 1-A	Layne Texas Co.	1952	390	14 8 6	284 294 390	CL	22	80 147 162	July 16, 1952 Feb. 16, 1955 May 23, 1962	T.E 75	P	Screen from 300 to 380 ft. Reported yield 554 gpm with 44 ft. drawdown when drilled.
202	City of Baytown Well 1	do	1952	541	--	--	CL	22	--	--	N	N	Screen from 450 to 530 ft. Well never completed. Water too salty.
401	City of Morgan Point	Unknown	1936	450	3	450	CL	32	182.5 254.3	Aug. 2, 1956 Feb. 17, 1971	N	N	Formerly private owner. Taken over by City of Morgan Point and abandoned. <u>1/</u>
402	do	McMasters and Pomeroy	1952	411	4	411	CL	32	156 253.1	Jan. 1952 Feb. 17, 1971	N	N	Screen from 390 to 411 ft. Formerly private owner. Taken over by City of Morgan Point and abandoned. <u>1/</u> <u>2/</u>
403	Captain Crotty	Unknown	1906	450	2 1 1/2	-- 450	CL	6	63.6 117.3	Jan. 18, 1939 Feb. 16, 1949	N	N	Well destroyed. <u>3/</u>
404	U.S. Corps of Engineers	Bucholtz	1914	450	4	450	CL	8	61.6 77.7	Jan. 18, 1939 Aug. 23, 1943	N	N	Well destroyed. <u>3/</u>
405	Mrs. H. S. Mitchell	Layne Bowler Co.	--	1,374	--	--	E	27	--	--	N	N	106 ft. of screen between 915 and 1,294 ft. Well destroyed. <u>2/</u>
406	A. Vandervoort	Layne Texas Co.	1936	494	4 3 2	-- -- 494	CL	20	64	July 3, 1936	N	N	Screen from 479 to 494 ft. Well destroyed.
407	City of Morgan Point	Pomeroy Drilling Co.	1966	462	12 6	395 462	CL	27	185	Feb. 1966	T.E 40	P	Screen from 352 to 462 ft. Reported yield 400 gpm with 32 ft. drawdown when drilled.
408	Boys Harbor	T. C. Russell and Son	1968	600	6 4	512 600	CL	21	220	May 15, 1968	Sub.E 20	P	30 ft. of screen between 512 and 537 ft. Supplies boys home. <u>2/</u>

- * Chemical analysis available.
1/ Active water level observation well.
2/ Drillers log available.
3/ Former water level observation well.

F-6-8707-10

	POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT	REGION 6	SITE NUMBER (to be assigned by HQ) TXD981052475
--	--	--------------------	---

GENERAL INSTRUCTIONS: Complete Sections I and III through XV of this form as completely as possible. Then use the information on this form to develop a Tentative Disposition (Section II). File this form in its entirety in the regional Hazardous Waste Log File. Be sure to include all appropriate Supplemental Reports in the file. Submit a copy of the forms to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION

A. SITE NAME Goodson & Son Trucking (Landfill)		B. STREET (or other identifier) 17300 block of Market Street		
C. CITY Channelview	D. STATE TX	E. ZIP CODE 77530	F. COUNTY NAME Harris	
G. SITE OPERATOR INFORMATION				
1. NAME Goodson & Son Trucking (Kyle Goodson)		2. TELEPHONE NUMBER (713) 452-9084		
3. STREET 15937 Ridlon	4. CITY Channelview	5. STATE TX	6. ZIP CODE 77530	
H. REALTY OWNER INFORMATION (if different from operator of site)				
1. NAME Same as Above		2. TELEPHONE NUMBER		
3. CITY	4. STATE		5. ZIP CODE	
I. SITE DESCRIPTION Low lying area filled with cement flue dust. High pH water is leaving area.				
J. TYPE OF OWNERSHIP <input type="checkbox"/> 1. FEDERAL <input type="checkbox"/> 2. STATE <input type="checkbox"/> 3. COUNTY <input type="checkbox"/> 4. MUNICIPAL <input checked="" type="checkbox"/> 5. PRIVATE				

II. TENTATIVE DISPOSITION (complete this section last)

A. ESTIMATE DATE OF TENTATIVE DISPOSITION (mo., day, & yr).	B. APPARENT SERIOUSNESS OF PROBLEM <input type="checkbox"/> 1. HIGH <input checked="" type="checkbox"/> 2. MEDIUM <input type="checkbox"/> 3. LOW <input type="checkbox"/> 4. NONE		
C. PREPARER INFORMATION			
1. NAME Terry D. Pierce, ICF Technology, FIT	2. TELEPHONE NUMBER (214) 744-1641	3. DATE (mo., day, & yr.) November 10, 1987	

III. INSPECTION INFORMATION

A. PRINCIPAL INSPECTOR INFORMATION			
1. NAME Mark Hansen		2. TITLE Environmental Engineer	
3. ORGANIZATION ICF Technology, 1509 Main Street, Suite 900, Dallas, TX 75201		4. TELEPHONE NO. (area code & no.) (214) 744-1641	

B. INSPECTION PARTICIPANTS

1. NAME	2. ORGANIZATION	3. TELEPHONE NO.
Terry D. Pierce	ICF Technology; Dallas, Texas	(214) 744-1641

C. SITE REPRESENTATIVES INTERVIEWED (corporate officials, workers, residents)

1. NAME	2. TITLE & TELEPHONE NO.	3. ADDRESS
Kyle Goodson	Owner - (713) 452-9084	15937 Ridlon Channelview, TX 77530
Teo Galvan, Jr.	Engineer - Southwestern Bell Telephone - (713) 660-5050	939 West Greens Road Houston, TX 77067

IV. SAMPLING INFORMATION (continued)

G. PHOTOS 1. TYPE OF PHOTOS <input checked="" type="checkbox"/> a. GROUND <input type="checkbox"/> b. AERIAL		2. PHOTOS IN CUSTODY OF: EPA Region 6 (see attached photos and negatives)
D. SITE MAPPED? <input checked="" type="checkbox"/> YES. SPECIFY LOCATION OF MAPS: Topo and site sketch attached.		
E. COORDINATES 1. LATITUDE (deg.-min.-sec.) 29° 47' 22" N		
2. LONGITUDE (deg.-min.-sec.) 95° 05' 13" W		

V. SITE INFORMATION

A. SITE STATUS <input type="checkbox"/> 1. ACTIVE (Those industrial or municipal sites which are being used for waste treatment, storage, or disposal on a continuing basis, even if infrequently.)		<input checked="" type="checkbox"/> 2. INACTIVE (Those sites which no longer receive wastes.)		<input type="checkbox"/> 3. OTHER (specify): (Those sites that include such incidents like "midnight dumping" where no regular or continuing use of the site for waste disposal has occurred.)	
B. IS GENERATOR ON SITE? <input checked="" type="checkbox"/> 1. NO <input type="checkbox"/> 2. YES (specify generator's four-digit SIC Code):					
C. AREA OF SITE (in acres) 4.5			D. ARE THERE BUILDINGS ON THE SITE? <input checked="" type="checkbox"/> 1. NO <input type="checkbox"/> 2. YES (specify):		

VI. CHARACTERIZATION OF SITE ACTIVITY

State the major site activity(ies) and details relating to each activity by marking 'X' in the appropriate boxes.

X	A. TRANSPORTER	X	B. STORER	X	C. TREATER	X	D. DISPOSER
	1. RAIL		1. PILE		1. FILTRATION		1. LANDFILL
	2. SHIP		2. SURFACE IMPOUNDMENT		2. INCINERATION		2. LANDFARM
	3. BARGE		3. DRUMS		3. VOLUME REDUCTION		3. OPEN DUMP
X	4. TRUCK		4. TANK, ABOVE GROUND		4. RECYCLING/RECOVERY		4. SURFACE IMPOUNDMENT
	5. PIPELINE		5. TANK, BELOW GROUND		5. CHEM./PHYS./TREATMENT		5. MIDNIGHT DUMPING
	6. OTHER (specify):		6. OTHER (specify):		6. BIOLOGICAL TREATMENT		6. INCINERATION
					7. WASTE OIL REPROCESSING		7. UNDERGROUND INJECTION
					8. SOLVENT RECOVERY	X	8. OTHER (specify):
					9. OTHER (specify):		Backfill of low lying areas.

E. SUPPLEMENTAL REPORTS: If the site falls within any of the categories listed below, Supplemental Reports must be completed. Indicate which Supplemental Reports you have filled out and attached to this form.

<input type="checkbox"/> 1. STORAGE	<input type="checkbox"/> 2. INCINERATION	<input type="checkbox"/> 3. LANDFILL	<input type="checkbox"/> 4. SURFACE IMPOUNDMENT	<input type="checkbox"/> 5. DEEP WELL
<input type="checkbox"/> 6. CHEM/BIO/PHYS TREATMENT	<input type="checkbox"/> 7. LANDFARM	<input type="checkbox"/> 8. OPEN DUMP	<input type="checkbox"/> 9. TRANSPORTER	<input type="checkbox"/> 10. RECYCLOR/RECLAIMER

VII. WASTE RELATED INFORMATION

A. WASTE TYPE <input type="checkbox"/> 1. LIQUID <input checked="" type="checkbox"/> 2. SOLID <input type="checkbox"/> 3. SLUDGE <input type="checkbox"/> 4. GAS	
B. WASTE CHARACTERISTICS <input checked="" type="checkbox"/> 1. CORROSIVE <input type="checkbox"/> 2. IGNITABLE <input type="checkbox"/> 3. RADIOACTIVE <input type="checkbox"/> 4. HIGHLY VOLATILE <input checked="" type="checkbox"/> 5. TOXIC <input type="checkbox"/> 6. REACTIVE <input type="checkbox"/> 7. INERT <input type="checkbox"/> 8. FLAMMABLE <input checked="" type="checkbox"/> 9. OTHER (specify): High pH	
C. WASTE CATEGORIES 1. Are records of wastes available? Specify items such as manifests, inventories, etc. below. No records exist for this site.	

VIII. HAZARD DESCRIPTION (continued)

☐ B. NON-WORKER INJURY/EXPOSURE☒ C. WORKER INJURY/EXPOSURE

Workers from Southwestern Bell Telephone who worked in a manhole chamber below the site complained of headaches and eye and respiratory irritation. The last occurrence was in February 1985.

☐ D. CONTAMINATION OF WATER SUPPLY☐ E. CONTAMINATION OF FOOD CHAIN☐ F. CONTAMINATION OF GROUND WATER☒ G. CONTAMINATION OF SURFACE WATER

FIT measured the pH of the water in the north drainage ditch approximately 400 feet from the west end of the fill area. The pH was 13.0. This ditch drains into a small cove approximately 200 feet from the fill area.

VIII. HAZARD DESCRIPTION (continued)

☐ N. FIRE OR EXPLOSION☐ O. SPILLS/LEAKING CONTAINERS/RUNOFF/STANDING LIQUID☐ P. SEWER, STORM DRAIN PROBLEMS☒ Q. EROSION PROBLEMS

FIT observed evidence of erosion from the site into the north and south drainage ditches. See photo 9.

☒ R. INADEQUATE SECURITY

There are no barriers, man-made or natural, to prevent access to the site.

☐ S. INCOMPATIBLE WASTES

Continued From Page 8

X. WATER AND HYDROLOGICAL DATA (continued)

LIST ALL DRINKING WATER WELLS WITHIN A 1/4 MILE RADIUS OF SITE

1. WELL	2. DEPTH (specify unit)	3. LOCATION (proximity to population/buildings)	4. NON-COM- MUNITY (mark 'X')	5. COMMUN- ITY (mark 'X')
		None - See Attachment A		

RECEIVING WATER

1. NAME

Old River

☐ 2. SEWERS☒ 3. STREAMS/RIVERS☐ 4. LAKES/RESERVOIRS☐ 5. OTHER (specify):

6. SPECIFY USE AND CLASSIFICATION OF RECEIVING WATERS

Navigable waterway, recreation

XI. SOIL AND VEGETATION DATA

LOCATION OF SITE IS IN:

☐ A. KNOWN FAULT ZONE☐ B. KARST ZONE☒ C. 100 YEAR FLOOD PLAIN☐ D. WETLAND☐ E. A REGULATED FLOODWAY☐ F. CRITICAL HABITAT☐ G. RECHARGE ZONE OR SOLE SOURCE AQUIFER**XII. TYPE OF GEOLOGICAL MATERIAL OBSERVED**

Mark 'X' to indicate the type(s) of geological material observed and specify where necessary, the component parts.

<input checked="" type="checkbox"/> A. CVERBURDEN	<input checked="" type="checkbox"/> B. BEDROCK (specify below)	<input checked="" type="checkbox"/> C. OTHER (specify below)
1. SAND	See Attachment A	
2. CLAY		
3. GRAVEL		

XIII. SOIL PERMEABILITY☐ A. UNKNOWN☐ B. VERY HIGH (100,000 to 1000 cm/sec.)☐ C. HIGH (1000 to 10 cm/sec.)☐ D. MODERATE (10 to .1 cm/sec.)☐ E. LOW (.1 to .001 cm/sec.)☒ F. VERY LOW (.001 to .00001 cm/sec.)**G. RECHARGE AREA**☐ 1. YES☒ 2. NO

3. COMMENTS:

H. DISCHARGE AREA☐ 1. YES☒ 2. NO

3. COMMENTS:

I. SLOPE

1. ESTIMATE % OF SLOPE

0-1%

2. SPECIFY DIRECTION OF SLOPE, CONDITION OF SLOPE, ETC.

East, silty soil

J. OTHER GEOLOGICAL DATA

The soil type in the area is the Aldine-Urban series. This series consists of deep loamy soils. The soils have a loamy surface with a clayey subsoil. The clay subsoil typically begins at a dept of 20 inches. These soils are poorly drained with slow runoff and low permeability. Permeability is greater than 10^{-7} cm/sec but less than 10^{-5} cm/sec.

ATTACHMENT A

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT SUPPLEMENT SHEET

Instruction - This sheet is provided to give additional information in explanation of a question on the form T2070-3.

Corresponding
number on form

Additional Remark and/or Explanation

IV.A.3.G.

ORGANICS

Gulf South Research Institute
5010 LeRoy Johnson Road
New Orleans, LA 70126
Attention: Darryl Brock
(504) 283-4223

INORGANICS

Rocky Mountain Analytical Lab
4955 Yarrow Street
Arvada, CO 80002
Attention: Tony Maiorana
(303) 421-6611

IV.B.1.

Measurement Location No. 1

Type - pH and conductivity measurement.

Location - In the north ditch approximately 400 feet from the west end of the fill area in an easterly direction. Measurements were taken 5 inches below the water surface.

Results - pH 13.0
conductivity 41,000 umhos

Measurement Location No. 2

Type - pH and conductivity measurement.

Location - In the north ditch approximately 50 feet east of the fill area. Measurements were taken 3 inches below the water surface.

Results - pH 11.1
conductivity 6,200 umhos

ATTACHMENT A

POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT SUPPLEMENT SHEET

Instruction - This sheet is provided to give additional information in explanation of a question on the form T2070-3.

Corresponding
number on form

Additional Remark and/or Explanation

IV.B.1.
(continued)

Measurement Location No. 3

Type - pH and conductivity measurement.

Location - In the south ditch approximately 50 feet east of the fill area. Measurements were taken 2 inches below the water surface.

Results - pH 12.5
conductivity 21,000 umhos

Measurement Location No. 4

Type - pH and conductivity measurements.

Location - In the south ditch approximately 75 feet from the east end of the fill area in a westerly direction. The pool of water was approximately 2 feet in diameter and 2 inches deep. Small tadpoles or minnows were thriving in this pool of water.

Results - pH 7.4
conductivity 950 umhos

Measurement equipment

Portable pH meter with pH probe.
Portable conductivity meter with conductivity probe.

VII.C.2.c.3.

Workers for McClelland Engineers, Inc. detected a "diesel" odor from a well which had been drilled near the telephone company manhole. The source of this odor has not been identified.

VII.C.2.e.6.

FTT measured the area of the fill site. The amount was calculated by FTT using the following figures:

200 ft. wide X 1000 ft. long X 10 ft. deep = 74,074 cubic
27 cubic ft. yards
1 cubic yard

ATTACHMENT A

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT SUPPLEMENT SHEET

Instruction - This sheet is provided to give additional information in explanation of a question on the form T2070-3.

Corresponding
number on form

Additional Remark and/or Explanation

VIII.U

material was approximately 1 to 3 inches below the water surface. The water had a coffee colored appearance at measurement locations no. 1, no. 2 and no. 3 (See attached site sketch). The high pH water drains into a small cove which is a part of the Old River and San Jacinto River bodies (See attached topo map and site sketch).

Although the fill area was well packed, the top 0.5 to 1 inch of the surface consists of very fine and powdery material which is easily kicked up into a dust cloud. There may be a potential for an air release hazard from the fill area. Evidence of erosion was observed from the fill area into both the north and south ditches. Erosion is more severe on the north side of the fill area. There is no evidence of dikes or other engineering controls to prevent or slow the erosion process. Although workers for McClelland Engineers, Inc. noticed a "diesel" odor, FIT did not observe such an odor during this inspection.

The piezometer well which was drilled near the telephone company manhole is screened in a very shallow aquifer, which is not used for drinking water purposes. The water in this aquifer is brackish and may be influenced by tidal movements.

A soil sample was caught by FIT in the north ditch near the underground storm conduit. The results from the laboratory shows an elevated level of calcium (71,100 mg/kg). Also, several organic compounds were found in the sample, mostly alkanes. FIT believes the elevated level of calcium is causing the high pH of the water in the north and south ditches. Therefore, FIT recommends sampling to determine if the fill area is contributing to the pH of the water. See attachment B for the recommended sampling plan.

X.A.

No water wells were observed within 0.25 miles of the fill area.

XII.A.

The overburden near the site is recent alluvium. This alluvium consists of clay, silt, sand, and gravel. Organic matter is locally abundant. The alluvium is made up of several different kinds of deposits such as; point bar, natural levee, stream channel, back swamp, mud flat, dune and oyster reefs.

The overburden is underlain by the Pleistocene Beaumont

ATTACHMENT A

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT SUPPLEMENT SHEET

Instruction - This sheet is provided to give additional information in explanation of a question on the form T2070-3.



Corresponding
number on form

Additional Remark and/or Explanation

XII.A.

formation which consists of barrier islands and beach deposits. The formation consists principally of clay, silt and sand and also includes stream channel, point bar, natural levee, marsh and mudflat deposits. This formation is approximately 100 feet thick and has moderate to low permeability.

SITE NAME: GOODSON AND SON TRUCKING (LANDFILL)



CONTOUR INTERVAL 5 FEET
NATIONAL GEODETIC VERTICAL DATUM OF 1929
SOUNDINGS IN FEET-GULF COAST LOW WATER DATUM
SHORELINE SHOWN REPRESENTS THE APPROXIMATE LINE OF MEAN HIGH WATER
THE MEAN RANGE OF TIDE IS 6" GLIDEABLE

EPA ID # TXD981052475

TDD# F-06-8707-10

ICF TECHNOLOGY

The Kirby Building, 1509 Main Street, Suite 900, Dallas, TX 75201

HIGHLANDS QUADRANGLE
TEXAS-HARRIS CO.
7.5 MINUTE SERIES (TOPOGRAPHIC)



QUADRANGLE LOCATION
HIGHLANDS, TEX.
N2945-W9500/7.5

1982

DMA 6045 1 SE-SERIES V082

NOT TO SCALE

SITE SKETCH

GOODSON & SON TRUCKING (LANDFILL)

TDD No. F-06-8707-10 CERCLIS No. TXD981052475

Convenience store

Service Road

Interstate Highway 10

Magnolia

On ramp

Underground storm conduit

Houses

Fill Area

1000 ft.

Fill Area

South Ditch

North Ditch

Bridge

Market Street

Truck repair shops

Texas Gulf Asphalt (business)

Insulated Tanks

Dirt Road

Dirt Road

• Soil Sample Location

♦ Conductivity + pH Measurement Location

+ Piezometer

• Telephone Company Manhole



Surface water

ICF TECHNOLOGY

The ICF Group, 1500 Main Street, Suite 1001, Dallas, TX 75201

ATTACHMENT B

SAMPLING PLAN
GOODSON AND SON TRUCKING (LANDFILL)
CHANNELVIEW, TX

CERCLIS NO. TXD981052475 TDD NO. F-06-8707-10

Laboratory Requirements - Routine Analytical Services, Organics and Inorganics.

Sample Locations

Station 1 - Soil sample from the fill area. Low concentration. Station 1 is also a QA/QC sample.

Station 2 - Soil/sediment sample from the north ditch near the underground storm conduit. Low concentration.

Station 3 - Soil/sediment sample from the south ditch near the fill area. Low concentration.

Station 4 - Soil sample upgradient from the north ditch. Low concentration.

Station 5 - Soil sample upgradient from the south ditch. Low concentration.

Station 6 - Water sample from the north ditch near the underground storm conduit. Low concentration. This sample is also a QA/QC sample.

Station 7 - Water sample from the north ditch in an area near the cove located east of the fill area. Low concentration.

Station 8 - Water sample from the south ditch near the fill area. Low concentration.

Station 9 - Water sample from the south ditch near the cove located east of the fill area. Low concentration.

Station 10 - Water sample located upgradient from the north ditch. Low concentration.

Station 11 - Water sample located upgradient from the south ditch. Low concentration.

Station 12 - Soil duplicate sample from the same location as Station 1.

Station 13 - Water duplicate sample from the same location as Station 6.

Station 14 - Water rinsate sample.

ATTACHMENT B

SAMPLING PLAN
GOODSON AND SON TRUCKING (LANDFILL)
CHANNELVIEW, TX

CERCLIS NO. TXD981052475 TDD NO. F-06-8707-10

Justification of Sample Locations

Station 1 is a bias grab soil sample from the fill area. This sample will determine the composition of the fill material and will act as a basis for associating the material to the ditches.

Stations 2 and 3 are bias grab soil/sediment samples. These samples will determine if the fill material has eroded into the ditches.

Stations 4 and 5 are bias grab soil samples located upgradient from the fill area. These samples are intended to show that the fill material is not located in the surrounding area.

Stations 6 and 8 are bias grab water samples located adjacent to the fill area.


Stations 7 and 9 are bias grab water samples located near the cove. These samples will show whether high pH water is migrating from the fill area.

Stations 10 and 11 are bias grab water samples located upgradient from the fill area. These samples will show whether high pH water is associated with an upgradient source from the fill area or if the high pH water begins near the fill area.

Stations 12, 13 and 14 are required duplicate and rinsate samples.

Conductivity and pH measurements will be taken at the water sample locations. The measurement results will be compared to previous measurement data.

SITE SKETCH
GOODSON & SON TRUCKING (LANDFILL)
 TDD No. F-06-8707-10 CERCLIS No. TXD981052475



♦ Piezometer

• Telephone Company
Manhole

Surface water

ICF TECHNOLOGY

12022 Main Street, Suite 900, Dallas, TX 75201

[illegible]

REMARKS

3-10085

DATA EVALUATION

SITE NAME

Goodson & Son Trucking

CASE NO.

7830

PAGE 1 of 1

The case consists of one soil sample analyzed for metals and cyanide. The following qualifications have been placed on the data after review of the QA/QC data.

- 1) The reported results and detection limits for lead and silver are considered estimates (J) due to low matrix spike recoveries. The actual values ^{TOP} ~~for~~ may be as great as 2.5 and 1.6 times the reported values for lead and silver respectively.
- 2) The holding times for mercury and cyanide were out of control limits. The reported results are considered estimates ^{TOP} ~~for~~ (J) and are biased low.
- 3) All other QA/QC criteria were within control limits.

1. INORGANIC ANALYSIS SUMMARY FOR SOIL

SITE NAME AND NUMBER: GOODSON & SON TRUCKING (LTD)

CASE NUMBER: 7530

PAGE 1 OF 1

CONCENTRATIONS IN PARTS PER MILLION (PPM)

TRAFFIC REPORT NUMBER AND STATION LOCATION.

[illegible]

R - DATA IS UNUSABLE DUE TO QA/QC OUT OF CONTROL LIMITS.

J - REPORTED CONCENTRATIONS ARE ESTIMATES DUE TO QA/QC OUT OF CONTROL LIMITS.

B - CONCENTRATION IN SAMPLE ATTRIBUTABLE TO BLANK CONTAMINATION.

U - NOT DETECTED: VALUE REPORTED IS THE DETECTION LIMIT.

DATA EVALUATION

SITE NAME

Goodson & Son Trucking

CASE NO.

7830

PAGE

1

The case consists of one soil sample analyzed for semi-volatile organics. The laboratory received insufficient sample to provide volatile ^{TOP} ~~and pest~~ organics and pesticide/PCB analysis. The following qualifications have been placed on the data after review of the associated QA/QC data.

- 1) The %D of the continuing calibration was out of limits for benzo(k)fluoranthene (30.5%) and benzo(b)fluoranthene (36.1%). Results should be considered as estimates (J).
- 2) One B/N spike recovery was out of limits for the MSD. Reported results should be considered as estimates (J).
- 3) All other QA/QC criteria were within control limits.

ORGANIC ANALYSIS SUMMARY

SITE NAME: Goodson & Son Trucking (Landfill)

CASE NUMBER 7830 PAGE 1 OF 1

CONCENTRATIONS IN PARTS PER BILLION

ORGANIC TRAFFIC NUMBERS AND SAMPLE STATION LOCATION DESCRIPTIONS

144831					
soil sample					
taken in					
north					
ditch					

MATRIX: soil

COMPOUND	CAS#	SCAN	CLASS						
FLUORANTHENE	206-44-0	ABN/11	1401						
NAPHTHALENE	91-20-3	ABN/11	3901						
BIS(2-ETHYLHEXYL)PHTHALATE	117-81-7	ABN/11	740						
BENZOPHTHACENE	56-55-3	ABN/11	1101						
BENZOTA-PYRENE	50-32-8	ABN/11	1101						
BENZOPY-FLUORANTHENE	205-99-2	ABN/11	2400						
CHRYSENE	218-01-9	ABN/11	1400						
PERANTHRENE	95-01-8	ABN/11	1100						
DIBENZOFURAN	132-64-7	ABN/21	1101						
2-METHYLNAPHTHALENE	91-57-6	ABN/21	1301						
not identified	210	ABN/31	100000						
Benzene, ethenyl-	253	ABN/31	30000						
ALKANE	722	ABN/31	17000						
ALKANE	783	ABN/31	15000						
ALKANE	801	ABN/31	58000						
ALKANE	848	ABN/31	30000						
ALKANE	875	ABN/31	79000						
not identified	912	ABN/31	30000						
naphthalene, triethyl- +	920	ABN/31	16000						
ALKANE	978	ABN/31	40000						
ALKANE	1011	ABN/31	150000						
ALKANE	1074	ABN/31	81000						
ALKANE	1080	ABN/31	27000						
ALKANE	1110	ABN/31	14000						
ALKANE	1133	ABN/31	78000						
ALKANE	1190	ABN/31	38000						
ALKANE	1244	ABN/31	32000						

1. PRIORITY POLLUTANT

2. SPECIFIED HAZARDOUS SUBSTANCE

3. TENTATIVELY IDENTIFIED

VOA - VOLATILE

ABN - ACID/BASE/NEUTRAL

PES - PESTICIDE

B - THE ANALYTE IS FOUND IN THE LAB BLANK

J - INDICATES AN ESTIMATED VALUE FOR TENTATIVELY IDENTIFIED COMPOUNDS OR COMPOUNDS FOUND BELOW CONTRACT DETECTION LIMIT

P - PRESENT IN SAMPLE, BUT NOT REPORTED BY LAB

C - CONFIRMED BY MASS SPECTRAL DATA

page 1 of 17

PHOTO #

1

PHOTOGRAPHER

M. Hansen

WITNESS

Pierce

DATE 8/3/87

TIME 09:43

DIRECTION

West

COMMENTS:

distressed vegetation on I-10 right of way



PHOTOGRAPHER

M. Hansen

WITNESS

Pierce

PHOTO #

2

DATE 8/3/87

TIME 09:45

DIRECTION

Down

COMMENTS:

Broken telephone cable sign. Notice powdery material near bottom of sign.



CERCLIS NO. TX0981052475

TDD NO. F-06-8707-10

Photographer / M:

Mark Harsen Terry D. Pierce

Date / Time / Direction

8/3/87 09:50 hours NW to NE

Comments: photos 3 and 4

PANARAMA of NORTH DRAINAGE ditch.

Notice coffee-colored water.

PANARAMA

page 1 of 3

page 2 of 17



CERCLIS NO. TXD981052475

TDD NO. F-06-8707-10

Photographer / 1

Alk Hansen Terry D. Pierce

Date / Time / Direction

8/3/87 ^{TOP} 9:50 HOURS NW to NE

Comments: photos 5 and 6

PANARAMA of NORTH DRAINAGE ditch.

PANARAMA

Page 2 of 3

page 3 of 17



CERCUS no. TXD 9810524 15

TDD no. F-06-8707-10

Adel Hansen Terry D. Prece

Date / Time / Direction

8/3/87 09:50 hours NW to NE

Comments: photo 7

PANARAMA of north drainage ditch,

PANARAMA page 3 of 3

page 4 of 17




PHOTO # 8

PHOTOGRAPHER M. Hargis WITNESS Pierce DATE 8/3/87 TIME 09:54 DIRECTION North


COMMENTS: locked well with piezometer.

page 5 of 1-



PHOTOGRAPHER M. Hargis WITNESS Pierce PHOTO # 9 DATE 8/3/87 TIME 10:00 DIRECTION West

COMMENTS: Erosion into north ditch from fill area



CERCLIS NO. TXD981052475

PHOTO # 10

TDD NO. F-06-8707-10

PHOTOGRAPHER M. Hargis WITNESS Pierce DATE 8/3/87 TIME 10:05 DIRECTION Down

COMMENTS: MEASUREMENT LOCATION NO. 4 LOCATED IN SOUTH DITCH
(See site sketch)



page 6 of 1-

PHOTOGRAPHER M. Hargis WITNESS Pierce PHOTO # 11 DATE 8/3/87 TIME 10:08 DIRECTION Down

COMMENTS: Animal tracks found on fill area. Notice powdery
texture of fill material.



PHOTOGRAPHER M. Hanger WITNESS Pierce DATE 8/3/87 TIME 11:48 DIRECTION westCOMMENTS: Sampling AT measurement location no. 1 (See site sketch),

page 7 of 17

PHOTOGRAPHER M. Hanger WITNESS Pierce PHOTO # 13 DATE 8/3/87 TIME 11:48 DIRECTION westCOMMENTS: Sampling AT measurement location no. 1 (See site sketch),


ERCLIS NO. TXD981052475

PHOTO # 14

TDD NO. F-06-8707-10

PHOTOGRAPHER M. Hargen WITNESS Pierce DATE 8/3/87 TIME 12:00 DIRECTION South

COMMENTS: Sampling AT measurement location NO. 2 (See site sketch)



page 8 of 17

PHOTOGRAPHER M. Hargen WITNESS Pierce PHOTO # 15 DATE 8/3/87 TIME 12:00 DIRECTION South

COMMENTS: Sampling AT measurement location NO. 2 (See ~~site~~ ^{TOP} site sketch).



TDD no. F-06-8707-10

Nash Harbor Terry Pierce

Date / Time / Direction

8/3/87 12:55 hours W to ESE

Comments: photos 22 and 21


PANARAMA of Old River Slough (cove).

PHOTO SERIES TAKEN FROM RIGHT TO LEFT

PANARAMA

page 1 of 4

page 9 of 17



CERCLIS no. TXD 981052475

TDD no F-06-8707-10

Photographer / W1

Nash Hansen

Terry D. Pierce

Date / Time / Direction

8/3/87 12:55 hours W to ESE

Comments: photos 20 and 19.

PANARAMA of Old River Slough (cove).

photo series taken from right to left.

page 2 of 4

PANARAMA

page 10 of 17



CERCLIS no. ^{TOD} TXD981052475

TDD no. F-06-8707-10

Photographer / M

Clark Hansen Terry D. Pierce

Date / Time / Direction

8/3/87 12:55 hours W to ESE

Comments: photos 18 and 17

panorama of Old River Slough (cove).

photo series taken from right to left.

panorama page 3 of 4

11 of 17
page



CERCLIS NO. TX0981052475

TOD NO. F-06-8707-10

Photographer / 1

Mark Harger Terry D. Pierce

Date / Time / Direction

8/3/87 12:55 hours W to ESE


Comments: photo^{TOP} 16

PANARAMA of Old River Slough (cove).

photo series taken from right to left

PANARAMA PAGE 4 of 4

page 12 of 17



CERCHIS NO. 1X1548105d715

TDD NO. F-06-8707-10

photographer / MI

Alan Hansen Terry D. Pierce

Date / Time / Direction

8/3/87 13:30 hours NORTH TO EAST

Comments: photos 23-26^{TOP} 24

PANARAMA of fill area

Page 1 of 2

PANARAMA



CHECKED NO. 120 1010-2113

TDD NO. F-06-8707-10

FIELD LOG

Mark Hansen Terry D. Pierce

Date / Time / Direction


8/3/87 13:30 hours NORTH TO EAST

Comments: PHOTOS 25 AND 26

PANARAMA of SILL AREA

PANARAMA PAGE 2 of 2

page 14 of 17



CERCLIS no. TXD981052475

TOD no. F-06-8707-10

Photographer / I I

Mark Harrison Terry D. Pierce

Date / Time / Direction

8/3/87 13:45 hours WEST TO EAST

Comments: photos 27 and 28

PANARAMA of measurement location NO. 3

See site sketch

PANARAMA page 1 of 3

page 1 of 17



CERCLIS NO. TXD 981052475

TDD NO. F-06-8707-10

Photographer / W1

Clark Harrison Terry D. Prell

Date / Time / Direction

8/3/87 13:45 hours W to EAST

Comments: PHOTOS 29 AND 30

PANARAMA of measurement location NO. 3

See site sketch


PANARAMA

page 2 of 3

page 16 of 17



SOIL SURVEY OF Harris County, Texas



**United States Department of Agriculture
Soil Conservation Service**

In cooperation with the

**Texas Agricultural Experiment Station and the
Harris County Flood Control District**

Addicks loam makes up 20 to 85 percent of the complex, Urban land 10 to 60 percent, and other soils 5 to 20 percent. The areas are so intricately mixed that it was not practical to separate them at the mapping scale for this survey.

The Addicks soil has a surface layer of friable, neutral, black loam about 11 inches thick. The layer below that is friable, neutral, dark gray loam about 12 inches thick. The next layer is about 26 inches thick and consists of friable, moderately alkaline, light gray loam that is about 20 percent, by volume, visible calcium carbonate. The layer at a depth of about 49 inches is firm, moderately alkaline, light gray loam that has distinct yellow and yellowish brown mottles and is about 5 percent visible calcium carbonate.

Urban land consists of soils that support buildings and other urban structures that have covered or altered the soils so that classification is not practical. Typical structures are single- and multiple-unit dwellings, streets, schools, churches, parking lots, office buildings, and shopping centers less than 40 acres in size. In places Urban land consists of small areas of Addicks loam that has been altered by cutting, filling, and grading. Fill material has altered the soil in places. In some areas the entire profile is covered with 6 to 24 inches of fill material. Soils in the older areas that are drained by road ditches show less evidence of alteration.

Included with this unit in mapping are a few areas of Clodine, Gessner, Bernard, and Midland soils. These soils are unaltered in places.

This mapping unit has moderate to severe limitations for urban development. Poor drainage is the greatest limitation. There are no limitations for landscaping or for gardening. Chlorosis is common in areas where cuts have been made. Most of the acreage was formerly in cropland or native pasture.

Am—Aldine very fine sandy loam. This is a nearly level soil in broad, oblong and oval, wooded areas. The surface is plane to slightly convex. The slope is 0 to 1 percent, but averages about 0.6 percent. Areas of this soil average 200 acres, but some are several hundred acres in size.

The surface layer is friable, medium acid, dark grayish brown very fine sandy loam about 5 inches thick. The layer below that is friable, medium acid, grayish brown very fine sandy loam about 5 inches thick. It tongues into a layer of friable, very strongly acid, yellowish brown loam about 9 inches thick. The next layer, about 11 inches thick, is firm, very strongly acid, gray clay that has mottles of yellowish brown and red. Below that, extending to a depth of 60 inches, is a layer of firm, slightly acid, light gray clay loam that is less mottled with depth.

Included in some mapped areas of this soil are small areas of Atasco, Bissonnet, Aris, Hockley, Segno, and Ozan soils. These soils make up less than 10 percent of any mapped area. Low, sandy, circular mounds are common in a few places. These rise 6 to 30 inches above the surface and are 15 to 50 feet in diameter.

This Aldine soil is used mainly for timber and woodland. The native vegetation is chiefly pine, hardwoods, sedge, beaked panicum, longleaf uniola, and little bluestem. Some small open or cleared areas are used as pasture or home gardens.

This soil is somewhat poorly drained. Surface runoff is slow, and permeability is very slow. The available water capacity is high. This soil is saturated at a depth of 20 to 30 inches during cool months and in periods of excessive rainfall.

Cultivated areas of this soil are difficult to manage. Fertilizer, lime, and drainage systems are beneficial to pasture and row crops. Capability unit IIIw-1; rice group 2; pasture and hayland group 8A; woodland suitability group 2w9; Flatwoods woodland grazing group.

An—Aldine-Urban land complex. This is a nearly level to gently sloping complex in metropolitan areas and in rural areas where the population is increasing. This mapping unit is of minor extent. Areas are irregular in shape and generally range from 30 to 250 acres in size. One area, however, covers 1,200 acres. Boundaries commonly coincide with the outer limits of subdivisions and built-up areas. The slope is mainly 0 to 2 percent but ranges to 3 percent. In a few places along drainageways the slope is 5 percent. Native pine and hardwoods are common in most areas.

The Aldine soil makes up 25 to 75 percent of this complex, Urban land 10 to 70 percent, and other soils 5 to 20 percent. The areas are so intricately mixed that it was not feasible to separate them at the mapping scale for this survey.

The surface layer of the Aldine soil is friable, medium acid, dark grayish brown very fine sandy loam about 5 inches thick. The layer below that is friable, medium acid, grayish brown very fine sandy loam about 5 inches thick. It tongues into a layer of friable, very strongly acid, yellowish brown loam about 9 inches thick. The next layer, about 11 inches thick, is firm, very strongly acid, gray clay that has mottles of yellowish brown and red. Below that, extending to a depth of 60 inches, is a layer of firm, slightly acid, light gray clay loam that has less mottles with depth.

Urban land consists of soils that have been altered or obscured by buildings and other urban structures, making their classification impractical. Typical structures are single- multiple-unit dwellings, garages, sidewalks, patios, driveways, streets, schools, churches, shopping centers, office buildings, paved parking lots, and industrial parks. Included with Urban land in mapping are small areas of the Aldine soil that have been altered by cutting, filling, and grading. In places, 6 to 24 inches of fill material has been added to improve drainage.

Included with this unit in mapping are a few areas of Atasco, Bissonnet, Aris, Hockley, Segno, Vamont, and Ozan soils. These soils are unaltered in places.

This mapping unit has moderate to severe limitations for urban development. It has severe limitations for use as septic tank filter fields because the clayey subsoil is

very slowly permeable and has a high shrink-swell potential and a high corrosion potential. The areas were once in timber, so homeowners may have problems with tree stumps and roots.

Ap—Aris fine sandy loam. This is a nearly level soil in broad areas on the coastal prairie. The areas generally are several hundred acres in size and slightly lower on the landscape than those of adjacent or surrounding soils. The surface is plane to slightly concave. The slope averages about 0.2 percent.

The surface layer is friable, neutral, dark grayish brown fine sandy loam about 7 inches thick. The layer below that is friable, slightly acid, grayish brown fine sandy loam that extends to a depth of 21 inches. The next layer, extending to a depth of 28 inches, is firm, medium acid, gray sandy clay loam that contains tongues and interfingers. The layer below that, extends to a depth of 46 inches and is very firm, strongly acid, dark gray clay mottled with red and strong brown. The next layer is very firm, medium acid, gray clay that extends to a depth of 60 inches, where it grades to very firm, slightly acid, light gray clay loam.

Included with this soil in mapping are small areas of Katy, Gessner, Clodine, Ozan, Wockley, and Addicks soils. These soils make up less than 10 percent of the mapped acreage. There are low, sandy, circular mounds in a few undisturbed areas.

This soil is used mainly for rice, native pasture, and improved pasture. A few areas are used for corn and grain sorghum. The native vegetation is chiefly longleaf uniola, beaked panicum, little bluestem, indiangrass, greenbrier, berryvines, forbs, and annual weeds. Grasses for improved pastures mainly are common bermudagrass, Coastal bermudagrass, and Pensacola bahiagrass.

This soil is poorly drained. Surface runoff and internal drainage are slow. Permeability is very slow. A perched water table is above the tongued layer in the cool months or in periods of excess rainfall. The available water capacity is medium.

Poor drainage is the main limitation. Fertilizer, lime, and drainage systems are beneficial to crops and pasture. Capability unit IIIw-1; rice group 2; pasture and hayland group 8E; Loamy Prairie range site; woodland suitability group 2w8; Flatwoods woodland grazing group.

Ar—Aris-Gessner complex. This is a nearly level complex in large, irregular areas that are 100 to 1,000 acres in size. The complex consists of 30 to 50 percent Aris soil, 20 to 30 percent Gessner soil, and 20 to 30 percent other soils. The Aris soil is nearly level and slightly higher on the landscape than adjacent soils. The Gessner soil is in depressions that generally are either long, narrow meanders or circular in shape. The soils in this complex are so intricately mixed that separation was not feasible at the mapping scale for this survey. Furthermore, in leveling some areas for farming, part of the surface layer of the Aris soil has been distributed over the lower lying Gessner soil.

The Aris soil has a surface layer of friable, neutral, dark grayish brown fine sandy loam about 7 inches thick. The layer below that is friable, slightly acid, grayish brown fine sandy loam that extends to a depth of 21 inches. The next layer, extending to a depth of 28 inches, is firm, medium acid, gray sandy-clay loam that tongues and interfingers. The layer below that extends to a depth of 46 inches and is very firm, strongly acid, dark gray clay mottled with red and strong brown. The next layer is very firm, medium acid, gray clay that extends to a depth of 60 inches, where it grades to very firm, slightly acid, light gray clay loam.

The Gessner soil has a surface layer of friable, slightly acid, dark grayish brown loam about 7 inches thick. The layer below that is about 9 inches thick and is friable, slightly acid, grayish brown loam. It tongues into the next layer, which is friable, neutral, dark gray loam that is slightly more clayey. That layer extends to a depth of 34 inches. The layer below that is friable, moderately alkaline, light brownish gray loam about 19 inches thick. Below that, extending to a depth of 84 inches, is a layer of firm, moderately alkaline, light gray sandy clay loam that has distinct mottles of yellowish brown and brownish yellow.

Included in mapping are small areas, less than 10 acres in size, of Clodine, Wockley, Ozan, and Katy soils.

The soils making up this complex are used mainly for rice, native pasture, and improved pasture. The native vegetation is chiefly andropogons, panicums, paspalums, and annual weeds. Grasses for improved pasture are mainly common bermudagrass, Coastal bermudagrass, and Pensacola bahiagrass.

The soils are poorly drained and are saturated with water part of the year. Excess water ponds on the Gessner soil and for long periods. Permeability is moderate to very slow. The available water capacity is medium.

Poor drainage is the main management concern. Drainage, land smoothing, and fertilization are beneficial practices for crops and pasture. Capability unit IIIw-1; rice group 2; pasture and hayland group 8E; Loamy Prairie range site, Aris soil, and Lowland range site, Gessner soil; woodland suitability group 2w8; Flatwoods woodland grazing group.

As—Aris-Urban land complex. This is a nearly level complex in broad, irregular areas that are 30 to 1,000 acres in size. Slopes range from 0 to 1 percent but average about 0.3 percent. Wooded areas are generally the result of encroachment or of the planting of trees during urban development.

The Aris soil makes up 20 to 75 percent of the complex; Urban land 10 to 75 percent, and other soils 5 to 20 percent. The areas are so intricately mixed that separation was not practical at the mapping scale for this survey.

The surface layer of the Aris soil is friable, neutral, dark grayish brown fine sandy loam about 7 inches thick. The layer below that is friable, slightly acid, grayish brown fine sandy loam that extends to a depth of 21

cool months and in periods of excess rainfall. Surface runoff is slow to very slow. Internal drainage is slow. Permeability is very slow. The available water capacity is high.

Poor surface drainage is the major limitation. Fertilizer, lime, and artificial drainage are beneficial to pasture and crops. Capability unit IIIw-1; rice group 2; pasture and hayland group 8A; Loamy Prairie range site; woodland suitability group 2w8; Sandy Loam woodland grazing group.

Kn—Kenney loamy fine sand. This is a nearly level to gently sloping soil along ridges and natural drainageways. Soil areas are oblong and irregular and average about 100 acres, but some are 500 acres in size. The surface is plane to slightly convex. Slopes are mainly 0 to 1 percent, but the range is 0 to 3 percent.

The surface layer is about 9 inches thick. It is very friable, slightly acid, dark grayish brown loamy fine sand in the upper 5 inches and loose, slightly acid, dark brown loamy fine sand in the lower 4 inches. The layer below that is loose, medium acid, light yellowish brown loamy fine sand that extends to a depth of 56 inches. The next layer, extending to a depth of 80 inches, is friable, strongly acid, strong brown sandy clay loam.

Included with this soil in mapping are small areas of Hockley, Segno, and Boy soils. These soils make up less than 15 percent of the mapped area.

This soil is used mainly for woodland grazing. A few areas are used for timber, improved pasture, and cultivated crops. Loblolly pine and oak are common in most areas. Native grasses are mainly andropogons and panicums. Coastal bermudagrass, Pensacola bahiagrass, and weeping lovegrass are the principal improved pasture plants. A few areas are used for peanuts and watermelons, but inadequate moisture and fertility are limitations. A few areas of this soil are mined for sand for use in construction.

This soil is well drained. Surface runoff is very slow. Internal drainage is rapid, and permeability is moderately rapid. The available water capacity is low. Adequate moisture and improved fertility are needed for crops. Capability unit IIIs-1; pasture and hayland group 9B; Sandy Prairie range site; woodland suitability group 3s2; Sandy woodland grazing group.

Kū—Kenney-Urban land complex. This complex is made up of nearly level to gently sloping soils along ridges and natural drainageways. It consists of built-up areas and new subdivisions. Soil areas are oblong and irregular and average about 50 acres, but some are 200 acres in size. The surface is plane to convex. Slopes range from 0 to 3 percent, but the average is 1 percent.

Kenney soils make up about 30 to 80 percent of this unit; Urban land, about 10 to 50 percent; and other soils, about 10 to 15 percent. The soils of this unit are so intricately mixed that separation was not feasible at the scale used in mapping.

The surface layer of the Kenney soils is very friable, slightly acid, dark grayish brown loamy fine sand in the

upper 5 inches and loose, slightly acid, dark brown loamy fine sand in the lower 4 inches. The layer below that is loose, medium acid, light yellowish brown loamy fine sand that extends to a depth of 56 inches. The next layer, extending to a depth of 80 inches, is friable, strongly acid, strong brown sandy clay loam.

Urban land consists of soils that have been altered or covered by buildings and other urban structures. The main structures are single unit dwellings, garages, sidewalks, patios, driveways, streets, schools, churches, and paved parking lots. Urban land also consists of areas that have been altered by cutting, filling, or grading. Classification of all of these areas is not practical.

Included with this complex in mapping are Hockley, Segno, and Boy soils.

This mapping unit has moderate limitations for urban development. The thick sandy surface layer is low in fertility and is droughty. Lawns and shrubs are difficult to establish; adequate water and fertilizer are needed. The dry loose sand is unstable for traffic. Streets and roads need to be oiled, paved, or graveled.

LcA—Lake Charles clay, 0 to 1 percent slopes. This is a nearly level soil in broad, irregular areas that are 50 to several hundred acres in size. Slopes average 0.2 percent. Undisturbed areas are characterized by gilgai microrelief, which is destroyed in cultivation. In undisturbed areas, a mulch of fine, discrete, very hard aggregates is on the surface.

In the center of microdepressions, the surface layer is about 36 inches thick. In the upper 22 inches it is very firm, neutral, black clay. In the lower 14 inches it is very firm, mildly alkaline, very dark gray clay. The layer below that is about 16 inches thick and consists of very firm, mildly alkaline, dark gray clay that has intersecting slickensides. The next layer, to a depth of 74 inches, is very firm, mildly alkaline, gray clay that is mottled olive brown and yellowish brown.

Included with this soil in mapping are small areas of Beaumont, Bernard, Midland, Addicks, and Vamont soils and a few areas of this soil that are adjacent to Harris clay and that are slightly saline. These inclusions make up less than 10 percent of any mapped area.

This soil is used for cultivated crops, improved pasture, and native pasture. Rice is the main cultivated crop, but some areas are used for corn, cotton, and grain sorghum. Principal improved pasture plants are bermudagrass and dallisgrass. Native pastures support andropogons and paspalums. Live oak and huisache are common in places.

This soil is somewhat poorly drained. Surface runoff is very slow. Permeability and internal drainage are very slow. The available water capacity is high. When this soil is dry, deep wide cracks form on the surface. Water enters rapidly through the cracks, but it enters very slowly when the soil is wet and the cracks are sealed.

Favorable structure and tilth are difficult to maintain in this soil, and the moisture range in which the soil can be cultivated is narrow. Surface crusts and plowpans are common in cultivated fields. Runoff is very slow in large,

TABLE 17.--PHYSICAL AND CHEMICAL PROPERTIES OF SOILS

Dashes indicate data were not available. The symbol < means less than; > means greater than. The erosion tolerance factor (T) is for the entire profile. Absence of an entry means data were not estimated.]


Soil name and map symbol	Depth	Permeability	Available water capacity	Soil reaction	Shrink-swell potential	Risk of corrosion		Erosion factors	
						Uncoated steel	Concrete	K	T
Addicks:	<u>In</u>	<u>In/hr</u>	<u>In/in</u>	<u>pH</u>					
Ad-----	0-11	0.6-2.0	0.15-0.24	6.1-8.4	Low-----	High-----	Low-----	0.32	5
	11-49	0.6-2.0	0.15-0.24	6.6-8.4	Low-----	High-----	Low-----	0.37	
	49-78	0.6-2.0	0.15-0.24	6.6-8.4	Moderate	High-----	Low-----	0.37	
Ak:									
Addicks part-----	0-11	0.6-2.0	0.15-0.24	6.1-8.4	Low-----	High-----	Low-----	0.32	5
	11-49	0.6-2.0	0.15-0.24	6.6-8.4	Low-----	High-----	Low-----	0.37	
	49-78	0.6-2.0	0.15-0.24	6.6-8.4	Moderate	High-----	Low-----	0.37	
Urban land part.									
Aldine:									
Am-----	0-10	0.6-2.0	0.13-0.20	4.5-6.0	Low-----	High-----	High-----	0.43	5
	10-19	0.2-0.6	0.13-0.20	4.5-6.0	Moderate	High-----	High-----	0.43	
	19-60	<0.06	0.15-0.20	4.5-6.5	High-----	High-----	High-----	0.32	
An:									
Aldine part-----	0-10	0.6-2.0	0.13-0.20	4.5-6.0	Low-----	High-----	High-----	0.43	5
	10-19	0.2-0.6	0.13-0.20	4.5-6.0	Moderate	High-----	High-----	0.43	
	19-60	<0.06	0.15-0.20	4.5-6.5	High-----	High-----	High-----	0.32	
Urban land part.									
Aris:									
Ap-----	0-21	0.6-2.0	0.11-0.15	5.6-7.3	Low-----	High-----	Moderate-----	0.37	5
	21-28	0.2-0.6	0.12-0.17	5.1-6.5	Moderate	High-----	Moderate-----	0.32	
	28-60	<0.06	0.12-0.18	5.1-6.5	High-----	High-----	Moderate-----	0.32	
	60-78	<0.06	0.12-0.18	5.1-7.3	High-----	High-----	Moderate-----	0.32	
Ar:									
Aris part-----	0-21	0.6-2.0	0.11-0.15	5.6-7.3	Low-----	High-----	Moderate-----	0.37	5
	21-28	0.2-0.6	0.12-0.17	5.1-6.5	Moderate	High-----	Moderate-----	0.32	
	28-60	<0.06	0.12-0.18	5.1-6.5	High-----	High-----	Moderate-----	0.32	
	60-78	<0.06	0.12-0.18	5.1-7.3	High-----	High-----	Moderate-----	0.32	
Gessner part-----	0-16	0.6-2.0	0.10-0.15	6.1-7.8	Low-----	High-----	Low-----	0.43	5
	16-80	0.6-2.0	0.15-0.20	6.6-8.4	Low-----	High-----	Low-----	0.43	
As:									
Aris part-----	0-21	0.6-2.0	0.11-0.15	5.6-7.3	Low-----	High-----	Moderate-----	0.37	5
	21-28	0.2-0.6	0.12-0.17	5.1-6.5	Moderate	High-----	Moderate-----	0.32	
	28-60	<0.06	0.12-0.18	5.1-6.5	High-----	High-----	Moderate-----	0.32	
	60-78	<0.06	0.12-0.18	5.1-7.3	High-----	High-----	Moderate-----	0.32	
Urban land part.									
Atasco:									
AtB-----	0-16	0.6-2.0	0.14-0.18	5.1-6.5	Low-----	Low-----	Low-----	0.37	5
	16-19	0.2-0.6	0.15-0.19	4.5-6.0	Low-----	Moderate-----	Moderate-----	0.37	
	19-60	<0.06	0.15-0.22	4.5-6.0	Moderate	High-----	Moderate-----	0.32	
Beaumont:									
Ba-----	0-21	0.06-0.2	0.15-0.20	4.5-6.0	High-----	High-----	Moderate-----	0.32	5
	21-59	<0.06	0.15-0.20	4.5-5.5	High-----	High-----	Moderate-----	0.32	
	59-73	<0.06	0.15-0.20	5.1-7.8	High-----	High-----	Moderate-----	0.32	
Be:									
Beaumont part-----	0-21	0.06-0.2	0.15-0.20	4.5-6.0	High-----	High-----	Moderate-----	0.32	5
	21-59	<0.06	0.15-0.20	4.5-5.5	High-----	High-----	Moderate-----	0.32	
	59-73	<0.06	0.15-0.20	5.1-7.8	High-----	High-----	Moderate-----	0.32	
Urban land part.									

See footnotes at end of table.

TABLE 17.--PHYSICAL AND CHEMICAL PROPERTIES OF SOILS--Continued

Soil name and map symbol	Depth	Permeability	Available water capacity	Soil reaction	Shrink-swell potential	Risk of corrosion		Erosion factors	
						Uncoated steel	Concrete	K	T
	In	In/hr	In/in	pH					
Ijam:									
Is-----	0-8	<0.06	0.10-0.12	6.6-9.0	High-----	High-----	High-----	0.32	5
	8-60	<0.06	0.10-0.12	6.6-9.0	High-----	High-----	High-----	0.32	
Kaman:									
Ka-----	0-70	<0.06	0.15-0.20	5.6-7.8	High-----	High-----	Moderate-----	0.32	5
Katy:									
Kf-----	0-28	0.6-2.0	0.15-0.20	5.6-6.5	Low-----	Moderate-----	Moderate-----	0.37	5
	28-65	<0.2	0.12-0.18	5.1-7.3	Moderate	High-----	Moderate-----	0.32	
Kenney:									
Kn-----	0-56	6.0-20	0.06-0.10	5.1-6.5	Low-----	Low-----	Moderate-----	0.17	5
	56-80	2.0-6.0	0.11-0.15	5.1-6.5	Low-----	Low-----	Moderate-----	0.24	
¹ Ku:									
Kenney part-----	0-56	6.0-20	0.06-0.10	5.1-6.5	Low-----	Low-----	Moderate-----	0.17	5
	56-80	2.0-6.0	0.11-0.15	5.1-6.5	Low-----	Low-----	Moderate-----	0.24	
Urban land part.									
Lake Charles:									
LcA, LcB-----	0-22	0.06-0.2	0.15-0.20	6.1-7.8	High-----	High-----	Low-----	0.32	5
	22-74	<0.06	0.15-0.20	6.6-8.4	High-----	High-----	Low-----	0.32	
¹ Lu:									
Lake Charles part	0-22	0.06-0.2	0.15-0.20	6.1-7.8	High-----	High-----	Low-----	0.32	5
	22-74	<0.06	0.15-0.20	6.6-8.4	High-----	High-----	Low-----	0.32	
Urban land part.									
Midland:									
Md-----	0-7	0.06-0.2	0.20-0.22	5.1-6.5	Moderate	High-----	Moderate-----	0.37	5
	7-72	<0.06	0.18-0.20	5.6-8.4	High-----	High-----	Low-----	0.32	
¹ Mu:									
Midland part-----	0-7	0.06-0.2	0.20-0.22	5.1-6.5	Moderate	High-----	Moderate-----	0.37	5
	7-72	<0.06	0.18-0.20	5.6-8.4	High-----	High-----	Low-----	0.32	
Urban land part.									
Nahatche:									
Na-----	0-18	0.6-2.0	0.10-0.15	5.1-7.8	Moderate	Moderate-----	Moderate-----	0.28	5
	18-30	0.6-2.0	0.10-0.15	5.1-7.8	Moderate	High-----	Moderate-----	0.28	
	30-60	0.6-2.0	0.10-0.15	5.1-7.8	Moderate	High-----	Moderate-----	0.28	
Ozan:									
Oa-----	0-18	0.6-2.0	0.14-0.17	4.5-6.0	Low-----	High-----	High-----	0.37	5
	18-65	0.06-0.2	0.15-0.18	4.5-6.0	Low-----	High-----	High-----	0.37	
¹ On:									
Ozan part-----	0-18	0.6-2.0	0.14-0.17	4.5-6.0	Low-----	High-----	High-----	0.37	5
	18-65	0.06-0.2	0.15-0.18	4.5-6.0	Low-----	High-----	High-----	0.37	
Urban land part.									
Segno:									
SeA, SeB-----	0-13	0.6-2.0	0.10-0.15	5.1-6.5	Low-----	Low-----	Moderate-----	0.24	5
	13-42	0.2-0.6	0.10-0.15	4.5-6.0	Low-----	Moderate-----	High-----	0.32	
	42-75	0.2-0.6	0.08-0.12	4.5-6.0	Low-----	Moderate-----	High-----	0.24	
Urban land:									
Ur.									
Vamont:									
VaA, VaB-----	0-8	0.06-0.2	0.15-0.2	4.5-7.3	High-----	High-----	Moderate-----	0.32	5
	8-70	<0.06	0.15-0.2	5.1-7.3	High-----	High-----	Moderate-----	0.32	
	70-80	<0.06	0.15-0.2	5.6-7.8	High-----	High-----	Moderate-----	0.32	

See footnotes at end of table.




Each area outlined on this map consists of more than one kind of soil. The map is thus meant for general planning rather than a basis for decisions on the use of specific tracts.

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
TEXAS AGRICULTURAL EXPERIMENT STATION
AND
HARRIS COUNTY FLOOD CONTROL DISTRICT

GENERAL SOIL MAP
HARRIS COUNTY, TEXAS

Scale 1:316,800
0 1 2 3 4 5 Miles





ICF TECHNOLOGY INCORPORATED

TO: Ed Sierra, Region VI RPO

THRU: K.H. Malone, Jr., FITOM *KHm*

THRU: Tim A. Hall, AFITOM *TAH*

FROM: Victor Cason, FIT Chemist *V*

DATE: February 28, 1989

SUBJECT: Sampling Inspection for Goodson & Son Trucking, Channelview, Texas. TDD# F-6-8809-29, CERCLIS# TXD9801052475, PAN FTX0557SBF

1. INTRODUCTION

During the week of November 14 - 17, 1988 a five member FIT team consisting of Victor Cason, Steve Cowan, Joe Phillips, Derrick Johnson and Terry Pierce, performed a sampling inspection at the Goodson & Son Trucking site in Channelview, Texas. Eight soil samples and eight water samples were collected at the site. All sixteen samples were analyzed for full RAS TCL at Environmental Industrial Research (EIRA) and for full RAS TAL at Century Laboratories.

2. SITE HISTORY

The site originally existed as a low lying area between the I-10 East Freeway and the 17300 block of Market Street (Figure 1). During the summer of 1979, the owner, Kyle Goodson, filled the area with cement flue dust purchased from Ideal Basic Industries, Lone Star Industries, and Gulf Coast Portland Cement. Complaints regarding airborne dust were received by the Harris County Pollution Control Department (HPCPD) and they performed a site inspection on April 29, 1981. High pH water was noted on-site and in the runoff from the fill area.

FIT performed a site inspection on August 3, 1987 and discovered high pH water in both the north and south ditches. Analysis of a soil sample collected in the north ditch revealed the presence of several polynuclear aromatic compounds and high levels of calcium, magnesium, potassium and sodium (Exhibit 1).

3. SITE OPERATIONS

On November 15, 1988, four soil samples and three water samples were collected and shipped to CLP labs for analysis. At three locations along the south

ditch, both a water and a soil sample were collected (Figure 2). Each soil sample was collected with a dedicated stainless steel trowel. All water samples were collected with dedicated stainless steel beakers and stainless steel buckets. The water samples ranged in pH from 7.1 to 7.3. A sample of the fill material was collected from the center of the fill area at a depth of 6 inches to 1 foot. The material was excavated with the aid of a pick and stainless steel trowel.

The original sampling plan requested two samples of fill material from Station 01. However, Station 01 was also designated as the soil QA/QC sample. Therefore, a duplicate sample of the fill material would have been redundant. Instead a duplicate soil sample was collected at a different location. All of the samples were decontaminated using a distilled water rinse followed by a deionized water rinse. A trip blank was prepared and kept with the sample bottles.

On November 16, 1988, four soil samples and five water samples were shipped to the CLP labs for analysis. Station 10 was designated as the north ditch background water sample. However, no water was present in the north ditch upgradient of the storm sewer outfall, so a sample was collected from a manhole adjacent to the access road for I-10. The manhole received water from a conduit upgradient of the site and fed into the storm sewer in the north ditch. A sediment sample could not be collected from the manhole, therefore, a soil sample was collected in the north ditch upgradient of the storm sewer outfall. Station 06 was the water QA/QC sample. Sufficient volume for the sample was collected in two stainless steel buckets. The water was poured from one bucket to the other to ensure a homogenous sample. Duplicate water and soil samples were collected from the east end of the north ditch. Again all samples were decontaminated according to the procedure previously mentioned. The trip blank was one of the samples shipped on this day. The soil samples were collected with dedicated stainless steel trowels. All water samples were collected with dedicated stainless steel beakers and stainless steel buckets. The pH range of the water samples was 6.9 to 11.7. Table 1 shows the conductivity, temperature and pH measurements of the water samples.

4. RESULTS

A. ORGANIC ANALYSIS

Organic analysis of the fill material, Station 01, revealed the presence of bis (2-ethylhexyl)phthalate, 4,4'-DDT, 4,4'-DDE and 4,4'-DDD (Exhibit 2). From the north ditch, Station 02 contained 4,4'-DDT in a concentration of 94 ppb. Bis (2-ethylhexyl)phthalate, 4,4'-DDT, 4,4'-DDE and 4,4'-DDD were also present in Station 04. Station numbers 12 and 15, collected from the north ditch near the cove, contained bis(2-ethylhexyl)phthalate, phenanthrene and many semi-volatile tentatively identified compounds (TICs).

In the south ditch near the site entrance, Station 03 contained bis (2-ethylhexyl) phthalate, di-n-butylphthalate, 4,4'-DDT, 4,4'-DDE, 4,4'-DDD and several TICs. However, the soil sample near the southern edge of the site

contained only three TICs. The background sample for the south ditch contained very few organic constituents.

The water sample in the north ditch adjacent to the storm sewer contained ethylbenzene, methylene chloride, acetone, styrene, xylene, pentachlorophenol, phenol, fluoranthene, naphthalene, phenanthrene, benzoic acid, 4-methylphenol, 2-methylnaphthalene and a large number of semi-volatile TICs. Several TICs were present in the water samples taken in the north ditch near the cove.

Several semi-volatile TICs were found in the water samples collected in the south ditch adjacent to the site, Stations 08 and 16. The background water sample for the south ditch contained acetone, carbon disulfide and a few semi-volatile TICs.

A broad, unresolved peak was noticed in the chromatographs for sample stations 03, 05, 06, 10, 12, 13, and 15. This suggests the samples contained an oily matrix.

B. INORGANIC ANALYSIS

The sample of fill material from Station 01 contained high concentrations of calcium, potassium and sodium (Exhibit 3). All soil samples collected from the north ditch contained high concentrations of calcium and sodium. Aluminum, and potassium were reported in elevated concentrations in soil samples 02 and 04 (Exhibit 2).

Soil samples from the south ditch contained high concentrations of aluminum, calcium, iron, potassium and sodium as compared to the background south ditch sample.

Elevated levels of barium, calcium, potassium and sodium were found in the water samples from the north ditch as compared to the north ditch background sample, Station 10. Aluminum, arsenic, barium, iron and manganese were also present in elevated levels in Station 06.

Potassium and sodium in high concentrations were found in the water samples collected from the south ditch as compared to Station 11, the south ditch background water. Station 09 also contained elevated levels of barium and magnesium.

5. DISCUSSION & CONCLUSION

In the organic fraction, the on-site sample contained bis (2-ethylhexyl) phthalate, 4,4'-DDT and its degradation products. Three soil samples collected in the drainage pathways also contained one or more of the pesticide compounds. The presence of the degradation products in three of the samples indicates that a period of time had passed since the introduction of the DDT to the site and surrounding area. However, the sample in the north ditch adjacent to the storm sewer, Station 02, exhibited no degradation products and DDT was present in a higher concentration than the other samples. Since the



use of DDT was banned in the early 1970s, the origin of the pesticide at the Goodson & Son Trucking site and surrounding area is not known. DDT was not detected in any of the water samples, including the sample station adjacent to the storm sewer.

The presence of broad, unresolved chromatographic peaks in several samples indicates the presence of an oily matrix for those samples. Upgradient of the site, several truck repair stations and a truck wash are present and are the most probable cause of the oil in the samples. Station 06 contained several aromatic and polyaromatic compounds typical of oil matrices.

The inorganic analysis of the samples revealed high levels of calcium, potassium and sodium. High calcium concentrations were expected since the fill material is concrete flue dust. The concrete dust is composed of calcium carbonate to a large extent. The presence of some potassium and sodium in the same matrix is not uncommon. The high pH in the north ditch can be attributed somewhat to the calcium carbonate which is soluble in water. However, a pH greater than 11.5 is unusual. The presence of high concentrations of potassium and sodium could indicate that metal hydroxides may also be present in the fill material. A very small quantity of calcium, sodium, or potassium hydroxides can significantly raise the pH in a body of water.

Without further investigation, only the calcium, potassium and sodium contaminants can be attributed to the site. The source of DDT in the north ditch near the sewer as well as on-site is not known at this time. The oil constituents probably entered the north and south ditches from upgradient sources.


Figure 1



Site Location Map
GOODSON & SON TRUCKING
 CHANNELVIEW, TX
 TDD NO. F-6-8809-29
 CERCLIS NO. TXD981052475



Figure 2



↑
N
NOT TO SCALE

Site Sketch/Sample Location
GOODSON & SON TRUCKING
CHANNELVIEW, TX
TDD NO. F-6-8809-29
CERCLIS NO. TXD981052475

Exhibit 1

**Inorganic and Organic Analyses
of Soil Sample Collected on
August 3, 1987 at Goodson & Son Trucking**

INORGANIC ANALYSIS SUMMARY FOR SOIL

SITE NAME AND NUMBER: SOGDSON & SON TRUCKING (LF)

CASE NUMBER: 7530

PAGE 1 OF 1

CONCENTRATIONS IN PARTS PER MILLION (PPM)

TRAFFIC REPORT NUMBER AND STATION LOCATION.

		MFE733				
1						
SOIL SAMPLE						
IN THE NORTH						
DITCH NEAR						
CONDUIT.						
MATRIX	SOIL					
% MOISTURE	22	0	0	0	0	0
CAS NO.						
ALUMINUM	7429-90-5	2860	0	0	0	0
ANTHONY	7440-36-0	160	0	0	0	0
ARSENIC	7440-38-2	6.400U	0	0	0	0
BARIUM	7440-39-3	112	0	0	0	0
BERYLLIUM	7440-41-7	0.640U	0	0	0	0
CADMIUM	7440-43-9	2.600U	0	0	0	0
CALCIUM	7440-70-2	71100	0	0	0	0
CHROMIUM	7440-47-3	19	0	0	0	0
COBALT	7440-48-4	5.800U	0	0	0	0
COPPER	7440-50-8	12	0	0	0	0
IRON	7439-89-6	7820	0	0	0	0
LEAD	7439-92-1	443	0	0	0	0
MAGNESIUM	7439-95-4	1550	0	0	0	0
MANGANESE	7439-96-5	131	0	0	0	0
MERCURY	7439-97-6	0.130U	0	0	0	0
NICKEL	7440-02-0	7.800	0	0	0	0
POTASSIUM	7440-09-7	4320	0	0	0	0
SELENIUM	7782-49-2	3.200U	0	0	0	0
SILVER	7440-22-4	2.600U	0	0	0	0
SODIUM	7440-23-5	1350	0	0	0	0
THALLIUM	7440-28-0	6.400U	0	0	0	0
TIN	7440-31-5	140	0	0	0	0
VANADIUM	7440-62-2	12	0	0	0	0
ZINC	7440-66-6	58	0	0	0	0
CYANIDE		0.640U	0	0	0	0
HARDNESS		0	0	0	0	0
ALKALINITY		0	0	0	0	0

R - DATA IS UNUSABLE DUE TO QA/QC OUT OF CONTROL LIMITS.

J - REPORTED CONCENTRATIONS ARE ESTIMATES DUE TO QA/QC OUT OF CONTROL LIMITS.

B - CONCENTRATION IN SAMPLE ATTRIBUTABLE TO BLANK CONTAMINATION.

U - NOT DETECTED; VALUE REPORTED IS THE DETECTION LIMIT.

DATA EVALUATION

SITE NAME Goodson & Son Trucking CASE NO. 7830 PAGE 1 of 1

The case consists of one soil sample analyzed for metals and cyanide. The following qualifications have been placed on the data after review of the QA/QC data.

- 1) The reported results and detection limits for lead and silver are considered estimates (J) due to low matrix spike recoveries. The actual values ^{TOP} may be as great as 2.5 and 1.6 times the reported values for lead and silver respectively.
- 2) The holding times for mercury and cyanide were out of control limits. The reported results are considered estimates ^{TOP} (J) and are biased low.
- 3) All other QA/QC criteria were within control limits.

ORGANIC ANALYSIS SUMMARY

ITE NAME: Goodson & Son Trucking (Landfill)

AGE NUMBER 7830 PAGE 1 OF 1

CONCENTRATIONS IN PARTS PER BILLION

ORGANIC TRAFFIC NUMBERS AND SAMPLE STATION LOCATION DESCRIPTIONS

11831					
soil sample					
taken in					
north					
ditch					
MATRIX soil					
COMPOUND	CAS#	SCAN CLASS			
FLUORANTHENE	206-44-0	ABN/11	340J		
PHANTHRENE	91-20-3	ABN/11	390J		
1,2-DIETHYLHEXYL PHTHALATE	117-81-7	ABN/11	740		
1,2,3,4-TETRACHLOROPHTHALATE	56-55-3	ABN/11	130J		
1,2,3,4-TETRACHLOROPHTHALATE	50-32-8	ABN/11	120J		
1,2,3,4-TETRACHLOROPHTHALATE	105-99-2	ABN/11	240J		
1,2,3,4-TETRACHLOROPHTHALATE	218-01-9	ABN/11	140J		
1,2,3,4-TETRACHLOROPHTHALATE	85-01-8	ABN/11	620		
1,2,3,4-TETRACHLOROPHTHALATE	132-64-4	ABN/21	120J		
1,2,3,4-TETRACHLOROPHTHALATE	91-57-6	ABN/21	280J		
not identified	210	ABN/31	110000J		
benzene, ethenyl-	253	ABN/31	3000J		
ALKANE	722	ABN/31	2900J		
ALKANE	783	ABN/31	1500J		
ALKANE	801	ABN/31	5800J		
ALKANE	848	ABN/31	3000J		
ALKANE	875	ABN/31	7900J		
not identified	912	ABN/31	3000J		
naphthalene, triethyl-	920	ABN/31	1600J		
ALKANE	978	ABN/31	4000J		
ALKANE	1011	ABN/31	15000J		
ALKANE	1074	ABN/31	6100J		
ALKANE	1080	ABN/31	2700J		
ALKANE	1110	ABN/31	1400J		
ALKANE	1133	ABN/31	7800J		
ALKANE	1190	ABN/31	5800J		
ALKANE	1244	ABN/31	3200J		

1. PRIORITY POLLUTANT

2. SPECIFIED HAZARDOUS SUBSTANCE

3. TENTATIVELY IDENTIFIED

VOL - VOLATILE

ABN - ACID/BASE/NEUTRAL

PES - PESTICIDE

B - THE ANALYTE IS FOUND IN THE LAB BLANK

J - INDICATES AN ESTIMATED VALUE FOR TENTATIVELY IDENTIFIED COMPOUNDS OR COMPOUNDS FOUND BELOW CONTRACT DETECTION LIMIT

P - PRESENT IN SAMPLE, BUT NOT REPORTED BY LAB

C - CONFIRMED BY MASS SPECTRAL DATA

DATA EVALUATION

TE NAME Goodson & Son Trucking CASE NO. 7830 PAGE 1

The case consists of one soil sample analyzed for semi-volatile organics. The laboratory received insufficient sample to provide volatile ^{TOP} and pest organics and pesticide / PCB analysis. The following qualifications have been placed on the data after review of the associated QA/QC data.

- 1) The %D of the continuing calibration was out of limits for benzo(k)fluoranthene (30.5%) and benzo(b)fluoranthene (36.1%). Results should be considered as estimates (J).
- 2) One B/N spike recovery was out of limits for the MSD. Reported results should be considered as estimates (J).
- 3) All other QA/QC criteria were within control limits.

Exhibit 2

Organic Analysis Results

DATA QUALITY ASSURANCE REVIEW

SITE NAME GOODSON & SON TRUCKING Channelview, TX
SITE CODE TKD981052475
PAN ITX0557SBF
CASE NUMBER 10883
LABORATORY EIRA

SAMPLE NUMBERS

<u>FJ-110</u>	<u>FJ-111</u>	<u>FJ-112</u>	<u>FJ-113</u>
<u>FJ-114</u>	<u>FJ-115</u>	<u>FJ-116</u>	<u>FJ-117</u>
<u>FJ-118</u>	<u>FJ-119</u>	<u>FJ-120</u>	<u>FJ-121</u>
<u>FJ-122</u>	<u>FJ-123</u>	<u>FJ-124</u>	<u>FJ-125</u>
<u> </u>	<u> </u>	<u> </u>	<u> </u>

Ja
2-7-89

REVIEWER Victor Cason, ICF Technology

DATA EVALUATION

SITE NAME: Goodson & Son Trucking

CASE NUMBER: 10883

SAMPLE NUMBERS: FJ110, FJ111, FJ112, FJ113, FJ114, FJ115, FJ116, FJ117, FJ118, FJ119, FJ120, FJ121, FJ122, FJ123, FJ124, FJ125

The data package consists of 8 water and 8 soil samples analyzed for VOAs, ABNs and Pesticides/PCBs using low concentration protocols. The following qualifications are placed on the data.

VOA FRACTION:

1. Sample FJ115 was analyzed at a 1 to 10 dilution. Samples FJ119 and FJ122 were analyzed at 1 to 2 dilutions. Dilutions result in higher sample detection limits.
2. Due to calibration criteria out of control limits, reported concentrations of 2-butanone in samples FJ111, FJ114 and FJ122 are considered estimates (J flag). All reported detection limits for 2-butanone in the remaining samples are considered unusable.
3. All reported detection limits for 2-hexanone are considered unusable due to unacceptable calibration criteria.
4. Calibration criteria for methylene chloride and acetone were out of control limits in the continuing calibrations for all samples. All reported concentrations and detection limits for methylene chloride and acetone are considered estimates (J flag).
5. Vinyl chloride was out of the CCC control limits in the soil continuing calibration on 11/18/88 at 0607 hours. A new initial calibration was not conducted and the samples were not reanalyzed, therefore the laboratory is in violation of their contract.
6. Calibration criteria out of control limits were noted in both VOA continuing calibrations, however none of these compounds were detected in the samples and the effect is that the reported detection limits for these compounds are considered estimates.
7. Methylene chloride and acetone were detected in the soil method blank. Sample concentrations of these analytes less than ten times their concentration in the method blank are flagged "B" on the data summary.

ABN FRACTION

1. Samples FJ114, FJ119, FJ122 FJ122MS and FJ122MSD were all analyzed at 1 to 2 dilutions. Sample FJ115 was analyzed at no and 1 to 2 dilutions. Dilutions have the effect of raising sample detection limits.
2. The reported concentration of benzoic acid in sample FJ115 is considered

an estimate due to calibration criteria out of control limits. Reported detection limits for benzoic acid in the remaining samples, except FJ110 are considered unusable due to unacceptable calibration criteria.

3. Calibration criteria out of control limits were noted for several other compounds in continuing calibrations, however these compounds were not detected in the associated samples and the effect is that detection limits for these compounds are considered estimates.

4. TIC compounds were detected in both of the water method blanks. Sample concentrations of these TICs less than 5 times their method blank concentration are flagged "B" of the summary sheets.

5. Recoveries of surrogates were out of control limits in the analysis of samples FJ121 and FJ118MSD, however the data is not significantly affected.

6. Recoveries of the matrix spike compounds were consistently low in the matrix spike duplicate analysis of water sample FJ118, with six of the eleven compounds having recoveries below control limits. The poor recovery of 4-nitrophenol may be due to low response factors noted in all of the continuing calibrations. The generally poor recoveries may be due to poor spiking techniques by the laboratory.

7. Samples FJ112, FJ114, FJ115, FJ116, FJ119, FJ120, FJ121, FJ122, and FJ124 each contained a broad, poorly resolved chromatographic peak. Chromatographic peaks of this type are generally associated with oily materials.

PESTICIDE/PCB FRACTION

1. Sample FJ118 was analyzed at a 1 to 3 dilution. Samples FJ111, FJ118MS and FJ118MSD were analyzed at 1 to 5 dilutions. Samples FJ115, FJ116, FJ117, FJ120, FJ124 and FJ125 were analyzed at 1 to 10 dilutions. Sample FJ119 was analyzed at a 1 to 1000 dilution. Dilutions have the effect of raising the sample detection limits.

2. Reported concentrations and detection limits for sample FJ112 are all off by a factor of 2 since the laboratory did not take into account that the sample size was 15 grams instead of 30 grams.

3. Reported detection limits in sample FJ118 are all off by a factor of 1.67 since the laboratory did not take into account that the sample size was 300ml instead of 500ml. This results in a surrogate recovery of approximately 27% which is within control limits.

4. The laboratory reported that surrogate was diluted out in samples FJ111, FJ119, FJ122 and FJ123. Sample FJ123 was not analyzed at a dilution, indicating the possibility that the sample was not spiked, as does the 0% recovery of the surrogate in the soil method blank.

5. Recovery of the surrogate was high in sample FJ110. No qualification are placed on the data at this time.

6. Recoveries of the matrix spike compounds were very inconsistent in the

water matrix spike and duplicate, however the recoveries were all within limits for the soil matrix spike and duplicate. The data is not qualified at this time.

Chemical Data Summary

SITE NAME AND CODE: GOODSON & SON TRUCKING

CASE NUMBER: 10883

Page 1 of 8

CONCENTRATIONS IN PARTS PER BILLION (ug/L WATER, ug/kg SOIL)

Compiled by : Ecology & Environment, Inc.

TRAFFIC REPORT NUMBER AND STATION LOCATION

	Organic Traffic Number	FJ-110	FJ-111	FJ-112	FJ-113	FJ-114	FJ-115	FJ-116	FJ-117	FJ-118	FJ-119
	Matrix	:SOIL	:SOIL	:SOIL	:SOIL	:SOIL	:WATER	:WATER	:WATER	:WATER	:SOIL
	Percent Moisture	:34	:26	:33	:25	:14	:	:	:	:	:22
	Location	:STATION #01	:STATION #02	:STATION #03	:STATION #04	:STATION #05	:STATION #06	:STATION #07	:STATION #08	:STATION #09	:STATION #12
	And/or	:FILL MATERIAL	:NORTH DITCH	:SOUTH DITCH	:NORTH DITCH	:SOUTH DITCH	:NORTH DITCH	:NORTH DITCH	:SOUTH DITCH	:SOUTH DITCH	:NORTH DITCH
	Sample	:FROM CENTER	:NEAR UNDER-	:NEAR SITE	:ABOVE STORM	:BACKGROUND	:NEAR STORM	:NEAR COVE	:NEAR SITE	:NEAR COVE	:NEAR COVE
	Description	:OF SITE	:GROUND STORM	:ENTRANCE	:SEWER	:WEST OF	:CONDUIT	:	:ENTRANCE	:	:
			:CONDUIT	:	:	:MAGNOLIA	:	:	:	:	:
						:STREET	:	:	:	:	:
Compound Name	CAS/SCAN	CLASS									
ETHYLBENZENE	100-41-4	VDA/1:						77			
METHYLENE CHLORIDE	175-09-2	VDA/1:	21 BJ:	13 BJ:	61 BJ:	20 BJ:	18 BJ:	1800 J:			24 BJ:
TOLUENE	108-88-3	VDA/1:									
ACETONE	167-64-1	VDA/1:	14 BJ:				13 BJ:	150 BJ:			110 J:
2-BUTANONE	178-93-3	VDA/1:		9 J:			14 J:				
CARBON DISULFIDE	175-15-0	VDA/1:							3 J:		
STYRENE	100-42-5	VDA/1:						1600			15
TOTAL XYLENES	1330-20-7	VDA/1:						120			14
PENTACHLOROPHENOL	187-86-5	ABN/1:						22 J:			
PHENOL	108-95-2	ABN/1:						52			
FLUORANTHENE	1206-44-0	ABN/1:						8 J:			
NAPHTHALENE	91-20-3	ABN/1:						25			
BIS(2-ETHYLHEXYL)PHTHALATE	1117-81-7	ABN/1:	160 J:		250 J:	190 J:					450 J:
D1-N-BUTYL PHTHALATE	184-74-2	ABN/1:			830						
PHENANTHRENE	185-01-8	ABN/1:						22			590 J:
BENZOIC ACID	165-85-0	ABN/1:						430 J:			
4-METHYL PHENOL	1106-44-5	ABN/1:						19			
2-METHYLNAPHTHALENE	191-57-6	ABN/1:						58			
1,4'-DDT	150-29-3	PES/1:	33	94	28	21					
1,4'-DDE	172-55-9	PES/1:	15		9.8 J:	20					
1,4'-DDD	172-54-8	PES/1:	6.9 J:		2.8 J:						
UNKNOWN	12169	VDA/2:									20 J:
HYDROCARBON	12587	VDA/2:									90 J:
HYDROCARBON	12653	VDA/2:									300 J:
UNKNOWN	12777	VDA/2:									10 J:
UNKNOWN	12970	VDA/2:									20 J:
UNKNOWN	13257	VDA/2:									50 J:
UNKNOWN	13326	VDA/2:									60 J:
UNKNOWN	1648	ABN/2:						400 J:			
UNKNOWN	1711	ABN/2:							30 BJ:		
UNKNOWN	1729	ABN/2:			500 J:						
UNKNOWN	1732	ABN/2:									
UNKNOWN	1735	ABN/2:								20 BJ:	
UNKNOWN	1751	ABN/2:						70 BJ:		10 BJ:	
UNKNOWN	1770	ABN/2:									
UNKNOWN	1773	ABN/2:									
UNKNOWN	1774	ABN/2:						20 BJ:			
UNKNOWN	1799	ABN/2:									
UNKNOWN	1880	ABN/2:								8 J:	
UNKNOWN	1904	ABN/2:							10 J:		
UNKNOWN									40 J:		

VOA - VOLATILE ABN - ACID/BASE/NEUTRAL PES - PESTICIDE/PCB

1 - TARGET COMPOUND LIST COMPOUND (TCL) 2 - TENTATIVELY IDENTIFIED COMPOUND (TIC)

1 - ESTIMATED CONCENTRATION (TIC, TOL LESS THAN FROM OR TOL WITH NO/ON OUT OF CONTROL LIMITS) 0 - UNDETECTED DETECTION LIMIT

Chemical Data Summary

ITE NAME AND CODE: GOODSON & SON TRUCKING

ASE NUMBER: 10883

Page 2 of 8

CONCENTRATIONS IN PARTS PER BILLION (ug/L WATER, ug/kg SOIL)

Compiled by : Ecology & Environment, Inc.

TRAFFIC REPORT NUMBER AND STATION LOCATION

Organic Traffic Number	IFJ-110	IFJ-111	IFJ-112	IFJ-113	IFJ-114	IFJ-115	IFJ-116	IFJ-117	IFJ-118	IFJ-119
Matrix	:SOIL	:SOIL	:SOIL	:SOIL	:SOIL	:WATER	:WATER	:WATER	:WATER	:SOIL
Percent Moisture	:34	:26	:33	:25	:14					:22
Location	:STATION #01	:STATION #02	:STATION #03	:STATION #04	:STATION #05	:STATION #06	:STATION #07	:STATION #08	:STATION #09	:STATION #12
And/Or	:FILL MATERIAL	:NORTH DITCH	:SOUTH DITCH	:NORTH DITCH	:SOUTH DITCH	:NORTH DITCH	:NORTH DITCH	:SOUTH DITCH	:SOUTH DITCH	:NORTH DITCH
Sample	:FROM CENTER	:NEAR UNDER-	:NEAR SITE	:ABOVE STORM	:BACKGROUND	:NEAR STORM	:NEAR COVE	:NEAR SITE	:NEAR COVE	:NEAR COVE
Description	:OF SITE	:GROUND STORM	:ENTRANCE	:SEWER	:WEST OF	:CONDUIT		:ENTRANCE		
		:CONDUIT			:MAGNOLIA					
					:STREET					
Compound Name	CAS/SCAN	CLASS								
UNKNOWN	:1169	:ABN/2:				50	J:			
UNKNOWN ALKANE	:1177	:ABN/2:				60	J:			
UNKNOWN	:1196	:ABN/2:						20	J:	
UNKNOWN	:1197	:ABN/2:								
UNKNOWN	:1306	:ABN/2:								3000 J:
UNKNOWN	:1325	:ABN/2:						10	J:	
UNKNOWN	:1329	:ABN/2:				40	J:			
UNKNOWN	:1426	:ABN/2:								
UNKNOWN	:1427	:ABN/2:				200	J:			4000 J:
UNKNOWN	:1442	:ABN/2:				60	J:			
UNKNOWN	:1460	:ABN/2:				70	J:	10	J:	
UNKNOWN	:1464	:ABN/2:				40	J:			2000 J:
UNKNOWN	:1483	:ABN/2:				80	J:			
UNKNOWN	:1485	:ABN/2:								2000 J:
UNKNOWN	:1498	:ABN/2:				60	J:			2000 J:
UNKNOWN	:1540	:ABN/2:				40	J:			
UNKNOWN	:1544	:ABN/2:								
UNKNOWN	:1585	:ABN/2:								
UNKNOWN	:1602	:ABN/2:								
UNKNOWN	:1603	:ABN/2:						10	J:	
UNKNOWN	:1621	:ABN/2:						20	J:	
UNKNOWN	:1633	:ABN/2:							10	J:
UNKNOWN	:1638	:ABN/2:				30	J:			
UNKNOWN	:1639	:ABN/2:								2000 J:
UNKNOWN	:1640	:ABN/2:								
UNKNOWN	:1646	:ABN/2:								6000 J:
UNKNOWN	:1646	:ABN/2:						10	J:	
UNKNOWN	:1650	:ABN/2:							10	J:
UNKNOWN	:1657	:ABN/2:						20	J:	
UNKNOWN	:1661	:ABN/2:								
UNKNOWN	:1674	:ABN/2:						10	BJ:	10 BJ:
UNKNOWN	:1682	:ABN/2:						10	J:	
UNKNOWN	:1698	:ABN/2:								
UNKNOWN	:1747	:ABN/2:				70	J:			6000 J:
UNKNOWN	:1750	:ABN/2:								
UNKNOWN	:1752	:ABN/2:				40	J:	20	J:	5000 J:
UNKNOWN	:1755	:ABN/2:								
UNKNOWN	:1758	:ABN/2:								
UNKNOWN	:1764	:ABN/2:							8	J:
UNKNOWN	:1769	:ABN/2:						10	J:	900 J:

OR - VOLATILE ABN - ACID/BASE/NEUTRAL PES - PESTICIDE/PCB

2 - TARGET COMPOUND LIST COMPOUND (TCL) 2 - TENTATIVELY IDENTIFIED COMPOUND (TIC)

- ESTIMATED CONCENTRATION (TIC, TCL LESS THAN CROL, OR TCL WITH OR/OC OUT OF CONTROL LIMITS) U - UNDETECTED, DETECTION LIMIT

SITE NAME AND CODE: GOODSON & SON TRUCKING

CASE NUMBER: 10883

Page 3 of 8

CONCENTRATIONS IN PARTS PER BILLION (ug/L WATER, ug/kg SOIL)

Compiled by : Ecology & Environment, Inc.

TRAFFIC REPORT NUMBER AND STATION LOCATION

Organic Traffic Number	FJ-110	FJ-111	FJ-112	FJ-113	FJ-114	FJ-115	FJ-116	FJ-117	FJ-118	FJ-119
Matrix	SOIL	SOIL	SOIL	SOIL	SOIL	WATER	WATER	WATER	WATER	SOIL
Percent Moisture	34	26	33	25	14					22
Location	STATION #01	STATION #02	STATION #03	STATION #04	STATION #05	STATION #06	STATION #07	STATION #08	STATION #09	STATION #12
And/Or	FILL MATERIAL	NORTH DITCH	SOUTH DITCH	NORTH DITCH	SOUTH DITCH	NORTH DITCH	NORTH DITCH	SOUTH DITCH	SOUTH DITCH	NORTH DITCH
Sample	FROM CENTER	NEAR UNDER-	NEAR SITE	ABOVE STORM	BACKGROUND	NEAR STORM	NEAR COVE	NEAR SITE	NEAR COVE	NEAR COVE
Description	OF SITE	GROUND STORM	ENTRANCE	SEWER	WEST OF	CONDUIT		ENTRANCE		
		CONDUIT			MAGNOLIA					
Compound Name	CAS/SCAN	CLASS			STREET					
UNKNOWN	1771	ABN/2								
UNKNOWN	1772	ABN/2						10	J	
UNKNOWN	1774	ABN/2								
UNKNOWN	1778	ABN/2								
UNKNOWN	1780	ABN/2					8	J		
UNKNOWN	1783	ABN/2								
UNKNOWN	1788	ABN/2				20	J			
UNKNOWN	1790	ABN/2								2000
UNKNOWN	1792	ABN/2								
UNKNOWN	1796	ABN/2					8	J		
UNKNOWN	1801	ABN/2						10	J	
UNKNOWN	1801	ABN/2								
UNKNOWN	1809	ABN/2						8	J	
UNKNOWN	1818	ABN/2						8	J	
UNKNOWN	1851	ABN/2					10	J		900
UNKNOWN	1879	ABN/2								
UNKNOWN	1882	ABN/2								1000
UNKNOWN	1885	ABN/2								
UNKNOWN	1903	ABN/2								
UNKNOWN	1928	ABN/2				60	J	10	J	1000
UNKNOWN	1929	ABN/2								
UNKNOWN	1934	ABN/2								5000
UNKNOWN	1974	ABN/2					10	J		
UNKNOWN	2006	ABN/2								900
UNKNOWN	2019	ABN/2				50	J	20	J	5000
UNKNOWN	2072	ABN/2					10	J		
UNKNOWN	2083	ABN/2								
UNKNOWN	2102	ABN/2				30	J	10	J	3000
UNKNOWN	2182	ABN/2				60	J			2000
UNKNOWN	2257	ABN/2				30	J			1000
UNKNOWN ALKANE	2534	ABN/2		200	J					
UNKNOWN	2584	ABN/2	500	J						
UNKNOWN ALKANE	2597	ABN/2		300	J					
UNKNOWN	2622	ABN/2		300	J					
UNKNOWN ALKANE	2661	ABN/2		400	J					
UNKNOWN	2676	ABN/2		200	J					
UNKNOWN	2775	ABN/2			500	J	1000	J		
UNKNOWN	2803	ABN/2				300	J			
UNKNOWN ALKANE	2815	ABN/2		700	J					
UNKNOWN	2858	ABN/2				300	J			

VDA - VOLATILE ABN - ACID/BASE/NEUTRAL PES - PESTICIDE/PCB

1 - TARGET COMPOUND LIST COMPOUND (TCL) 2 - TENTATIVELY IDENTIFIED COMPOUND (TIC)

J - ESTIMATED CONCENTRATION (TIC, TCL LESS THAN CRCL, OR TCL WITH OR/OC OUT OF CONTROL LIMITS) U - UNDETECTED, DETECTION LIMIT

R - DATA FOR ANALYTE IS UNUSABLE B - ANALYTE DETECTED AT COMPARABLE CONCENTRATION IN ASSOCIATED BLANK

Chemical Data Summary

SITE NAME AND CODE: GOODSON & SON TRUCKING

CASE NUMBER: 10883

Page 4 of 8

CONCENTRATIONS IN PARTS PER BILLION (ug/L WATER, ug/kg SOIL)

Compiled by : Ecology & Environment, Inc.

TRAFFIC REPORT NUMBER AND STATION LOCATION

[illegible]

VOA - VOLATILE ABN - ACID/BASE/NEUTRAL PES - PESTICIDE/PCB

1 - TARGET COMPOUND LIST COMPOUND (TCL) 2 - TENTATIVELY IDENTIFIED COMPOUND (TIC)

[illegible]

Chemical Data Summary

SITE NAME AND CODE: GOODSON & SON TRUCKING

CASE NUMBER: 10883

Page 5 of 8

CONCENTRATIONS IN PARTS PER BILLION (ug/L WATER, ug/kg SOIL)

Compiled by : Ecology & Environment, Inc.

TRAFFIC REPORT NUMBER AND STATION LOCATION

Organic Traffic Number	IFJ-120	IFJ-121	IFJ-122	IFJ-123	IFJ-124	IFJ-125																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
------------------------	---------	---------	---------	---------	---------	---------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

VDA - VOLATILE ABN - ACID/BASE/NEUTRAL PES - PESTICIDE/PCB

1 - TARGET COMPOUND LIST COMPOUND (TCL) 2 - TENTATIVELY IDENTIFIED COMPOUND (TIC)

J - ESTIMATED CONCENTRATION (TIC, TCL LESS THAN CRL, OR TCL WITH DA/DC OUT OF CONTROL LIMITS) U - UNDETECTED, DETECTION LIMIT

Chemical Data Summary

SITE NAME AND CODE: GOODSON & SON TRUCKING

CASE NUMBER: 10883

Page 6 of 8

CONCENTRATIONS IN PARTS PER BILLION (ug/L WATER, ug/kg SOIL)

Compiled by : Ecology & Environment, Inc.

TRAFFIC REPORT NUMBER AND STATION LOCATION

[illegible]

VOA - VOLATILE ABN - ACID/BASE/NEUTRAL PES - PESTICIDE/PCB

1 - TARGET COMPOUND LIST COMPOUND (TCL) 2 - TENTATIVELY IDENTIFIED COMPOUND (TIC)

1 - ESTIMATED CONCENTRATION (11C, 12C, 13C, 14C, 15C, 16C, 17C, 18C, 19C, 20C, 21C, 22C, 23C, 24C, 25C, 26C, 27C, 28C, 29C, 30C, 31C, 32C, 33C, 34C, 35C, 36C, 37C, 38C, 39C, 40C, 41C, 42C, 43C, 44C, 45C, 46C, 47C, 48C, 49C, 50C, 51C, 52C, 53C, 54C, 55C, 56C, 57C, 58C, 59C, 60C, 61C, 62C, 63C, 64C, 65C, 66C, 67C, 68C, 69C, 70C, 71C, 72C, 73C, 74C, 75C, 76C, 77C, 78C, 79C, 80C, 81C, 82C, 83C, 84C, 85C, 86C, 87C, 88C, 89C, 90C, 91C, 92C, 93C, 94C, 95C, 96C, 97C, 98C, 99C, 100C, 101C, 102C, 103C, 104C, 105C, 106C, 107C, 108C, 109C, 110C, 111C, 112C, 113C, 114C, 115C, 116C, 117C, 118C, 119C, 120C, 121C, 122C, 123C, 124C, 125C, 126C, 127C, 128C, 129C, 130C, 131C, 132C, 133C, 134C, 135C, 136C, 137C, 138C, 139C, 140C, 141C, 142C, 143C, 144C, 145C, 146C, 147C, 148C, 149C, 150C, 151C, 152C, 153C, 154C, 155C, 156C, 157C, 158C, 159C, 160C, 161C, 162C, 163C, 164C, 165C, 166C, 167C, 168C, 169C, 170C, 171C, 172C, 173C, 174C, 175C, 176C, 177C, 178C, 179C, 180C, 181C, 182C, 183C, 184C, 185C, 186C, 187C, 188C, 189C, 190C, 191C, 192C, 193C, 194C, 195C, 196C, 197C, 198C, 199C, 200C, 201C, 202C, 203C, 204C, 205C, 206C, 207C, 208C, 209C, 210C, 211C, 212C, 213C, 214C, 215C, 216C, 217C, 218C, 219C, 220C, 221C, 222C, 223C, 224C, 225C, 226C, 227C, 228C, 229C, 230C, 231C, 232C, 233C, 234C, 235C, 236C, 237C, 238C, 239C, 240C, 241C, 242C, 243C, 244C, 245C, 246C, 247C, 248C, 249C, 250C, 251C, 252C, 253C, 254C, 255C, 256C, 257C, 258C, 259C, 260C, 261C, 262C, 263C, 264C, 265C, 266C, 267C, 268C, 269C, 270C, 271C, 272C, 273C, 274C, 275C, 276C, 277C, 278C, 279C, 280C, 281C, 282C, 283C, 284C, 285C, 286C, 287C, 288C, 289C, 290C, 291C, 292C, 293C, 294C, 295C, 296C, 297C, 298C, 299C, 300C, 301C, 302C, 303C, 304C, 305C, 306C, 307C, 308C, 309C, 310C, 311C, 312C, 313C, 314C, 315C, 316C, 317C, 318C, 319C, 320C, 321C, 322C, 323C, 324C, 325C, 326C, 327C, 328C, 329C, 330C, 331C, 332C, 333C, 334C, 335C, 336C, 337C, 338C, 339C, 340C, 341C, 342C, 343C, 344C, 345C, 346C, 347C, 348C, 349C, 350C, 351C, 352C, 353C, 354C, 355C, 356C, 357C, 358C, 359C, 360C, 361C, 362C, 363C, 364C, 365C, 366C, 367C, 368C, 369C, 370C, 371C, 372C, 373C, 374C, 375C, 376C, 377C, 378C, 379C, 380C, 381C, 382C, 383C, 384C, 385C, 386C, 387C, 388C, 389C, 390C, 391C, 392C, 393C, 394C, 395C, 396C, 397C, 398C, 399C, 400C, 401C, 402C, 403C, 404C, 405C, 406C, 407C, 408C, 409C, 410C, 411C, 412C, 413C, 414C, 415C, 416C, 417C, 418C, 419C, 420C, 421C, 422C, 423C, 424C, 425C, 426C, 427C, 428C, 429C, 430C, 431C, 432C, 433C, 434C, 435C, 436C, 437C, 438C, 439C, 440C, 441C, 442C, 443C, 444C, 445C, 446C, 447C, 448C, 449C, 450C, 451C, 452C, 453C, 454C, 455C, 456C, 457C, 458C, 459C, 460C, 461C, 462C, 463C, 464C, 465C, 466C, 467C, 468C, 469C, 470C, 471C, 472C, 473C, 474C, 475C, 476C, 477C, 478C, 479C, 480C, 481C, 482C, 483C, 484C, 485C, 486C, 487C, 488C, 489C, 490C, 491C, 492C, 493C, 494C, 495C, 496C, 497C, 498C, 499C, 500C, 501C, 502C, 503C, 504C, 505C, 506C, 507C, 508C, 509C, 510C, 511C, 512C, 513C, 514C, 515C, 516C, 517C, 518C, 519C, 520C, 521C, 522C, 523C, 524C, 525C, 526C, 527C, 528C, 529C, 530C, 531C, 532C, 533C, 534C, 535C, 536C, 537C, 538C, 539C, 540C, 541C, 542C, 543C, 544C, 545C, 546C, 547C, 548C, 549C, 550C, 551C, 552C, 553C, 554C, 555C, 556C, 557C, 558C, 559C, 560C, 561C, 562C, 563C, 564C, 565C, 566C, 567C, 568C, 569C, 570C, 571C, 572C, 573C, 574C, 575C, 576C, 577C, 578C, 579C, 580C, 581C, 582C, 583C, 584C, 585C, 586C, 587C, 588C, 589C, 590C, 591C, 592C, 593C, 594C, 595C, 596C, 597C, 598C, 599C, 600C, 601C, 602C, 603C, 604C, 605C, 606C, 607C, 608C, 609C, 610C, 611C, 612C, 613C, 614C, 615C, 616C, 617C, 618C, 619C, 620C, 621C, 622C, 623C, 624C, 625C, 626C, 627C, 628C, 629C, 630C, 631C, 632C, 633C, 634C, 635C, 636C, 637C, 638C, 639C, 640C, 641C, 642C, 643C, 644C, 645C, 646C, 647C, 648C, 649C, 650C, 651C, 652C, 653C, 654C, 655C, 656C, 657C, 658C, 659C, 660C, 661C, 662C, 663C, 664C, 665C, 666C, 667C, 668C, 669C, 670C, 671C, 672C, 673C, 674C, 675C, 676C, 677C, 678C, 679C, 680C, 681C, 682C, 683C, 684C, 685C, 686C, 687C, 688C, 689C, 690C, 691C, 692C, 693C, 694C, 695C, 696C, 697C, 698C, 699C, 700C, 701C, 702C, 703C, 704C, 705C, 706C

Chemical Data Summary

SITE NAME AND CODE: GOODSON & SON TRUCKING

CASE NUMBER: 10883

Page 7 of 8

CONCENTRATIONS IN PARTS PER BILLION (ug/L WATER, ug/kg SOIL)

Compiled by : Ecology & Environment, Inc.

TRAFFIC REPORT NUMBER AND STATION LOCATION

[illegible]

VOA - VOLATILE ABN - ACID/BASE/NEUTRAL PES - PESTICIDE/PCB

1 - TARGET COMPOUND LIST COMPOUND (TCL) 2 - TENTATIVELY IDENTIFIED COMPOUND (TIC)

J - ESTIMATED CONCENTRATION (TIC, TEL LESS THAN CROL, OR TEL WITH DA/DC OUT OF CONTROL LIMITS) U - UNDETECTED, DETECTION LIMIT

Chemical Data Summary

ITE NAME AND CODE: GOODSON & SON TRUCKING
ASE NUMBER: 10883

Page 8 of 8

CONCENTRATIONS IN PARTS PER BILLION (ug/L WATER, ug/kg SOIL).

Compiled by : Ecology & Environment, Inc.

TRAFFIC REPORT NUMBER AND STATION LOCATION

[illegible]

:OA - VOLATILE ABN - ACID/BASE/NEUTRAL PES - PESTICIDE/PCB

1 - TARGET COMPOUND LIST COMPOUND (TCL) 2 - TENTATIVELY IDENTIFIED COMPOUND (TIC)

Exhibit 3

Inorganic Analysis Results

DATA QUALITY ASSURANCE REVIEW

SITE NAME GOODSON & SON TRUCKING Channelview, TX

SITE CODE TKD981052475

PAN ITX0557SBF

CASE NUMBER 10883

LABORATORY Century Laboratories

SAMPLE NUMBERS

<u>MFH-407</u>	<u>MFH-411</u>	<u>MFH-415</u>	<u>MFH-419</u>
<u>MFH-408</u>	<u>MFH-412</u>	<u>MFH-416</u>	<u>MFH-420</u>
<u>MFH-409</u>	<u>MFH-413</u>	<u>MFH-417</u>	<u>MFH-421</u>
<u>MFH-410</u>	<u>MFH-414</u>	<u>MFH-418</u>	<u>MFH-422</u>

REVIEWER Victor Cason, ICF Technology

DATA EVALUATION

SITE NAME: Goodson & Son Trucking

CASE NUMBER: 10883

SAMPLE NUMBERS: MFH-407, MFH-408, MFH-409, MEH-410, MFH-411, MFH-412,
MFH-413, MFH-414, MFH-415, MFH-416, MFH-417, MFH-418, MFH-419, MFH-420,
MFH-421, AND MFH-422.

This data package consists of eight water and eight soil samples analyzed for metals and cyanide using low concentration protocols. The following qualifications are placed on the data.

Contractual Violations

1. The laboratory failed to analyze the CRDL standard for arsenic, lead, selenium and thallium.
2. The laboratory failed to analyze an aqueous Laboratory Control Sample for mercury or solid Laboratory Control Sample for mercury and cyanide.
3. The laboratory failed to report the Standard Addition results for lead in samples MFH-410, MFH-411, MFH-415, MFH-416 and MFH-422 on Form 8. Results were within control limits and correct results were reported on Form 1s.
4. A post digestion spike was not analyzed for antimony in the water matrix.
5. A time period of greater than 2 hours between calibration verification was noted in the ICP analysis sequence. The data quality does not appear to be affected significantly.

Data Transcription Errors

Numerous errors were noted in the labs transfer of the raw data to the forms and in flagging the data. These errors are detailed below.

1. Incorrect values for aluminum and calcium were listed on ICP Interference Check Samples (Form 4). Actual values were within control limits, therefore, the data is not affected.
2. The sample result for cyanide was listed incorrectly on the water spike sample recovery Form 5A for sample MFH-412S.
3. Spike sample results for barium and manganese were listed incorrectly on soil spike recovery Form 5A for sample MFH-409S. Corrected recovery for barium remained out of control limits, however, manganese recovery was within control limits.
4. Duplicate results for chromium in water sample MFH-417D were not flagged * as being out of control limits. Form 1s were also not flagged.
5. Incorrect values for the duplicate results of magnesium and sodium were reported in water sample MFH-417D. The lab reported the original instead of the dilution analysis. Results were within control limits when the correct values were used. The Form 1s needs corrections.
6. Duplicate results for cyanide in water sample MFH-412D were flagged by the lab as being out of control limits when in fact they are within control limits.
7. Duplicate results for cobalt in soil sample MFH-409D were flagged by the lab as being out of control limits when in fact they are within control limits.

8. The laboratory failed to flag aluminum, calcium, iron and zinc on Form 1s in the water samples and calcium, copper and nickel on Form 1s in the soil samples to indicate ICP serial dilutions out of control limits.

9. Required W flags were not included for selenium and thallium in several samples.

Sample Specific QA/QC

1. Reported results for calcium in sample MFH-407, MFH-408 and MFH-409 were outside of the reported linear range of the ICP. The samples were not diluted and reanalyzed. Reported concentrations of calcium in these samples are considered estimates (J flag).

2. The recovery of aluminum was out of control limits in one of the continuing calibration verifications. As a result, the reported concentrations of aluminum in samples MFH-410, MFH-409L, MFH-417L, the final CRDL sample of the sequence, and the final interference check are considered estimates (J flag).

3. Reported detection limits for selenium in samples MFH-407, MFH-412 and MFH-415 were incorrect as the lab did not take into account sample dilutions.

General QA/QC

1. Antimony and calcium were detected in both the water and soil method blanks at concentrations below the CRDL. Sample concentrations of these metals less than 5 times their concentrations in the associated method blank are flagged "B" on the data summary.

2. The holding time of 14 days for cyanide analysis was exceeded for all samples. Therefore, all cyanide results are considered estimates (J flag).

3. Due to ICP Serial Dilution criteria out of control limits for aluminum, calcium, iron and zinc, all results for these metals in water samples have been flagged as estimates (J flag).

4. Due to ICP Serial Dilution criteria out of control limits for calcium, copper and nickel, all results for these metals in soil samples have been flagged as estimates (J flag).

5. The recovery for mercury in the water matrix spike was unacceptable. The data is considered unusable (R flag) in the water samples.

6. The recoveries for antimony, lead and copper in the soil matrix spike were unacceptable and the data is considered unusable (R flag) in all soil samples.

7. Recoveries for lead, and thallium were out of control limits in the water matrix spike. Reported concentrations and detection limits for these elements are considered estimates in all water samples (J flag). The actual concentrations for lead and thallium could be as great as 1.5 or 2.1 times the reported values, respectively.

8. Recovery of antimony was high in the water matrix spike. Reported concentrations of antimony are considered as estimates (J flag) and actual concentrations may be as low as 0.23 times that reported. Reported detection limits are acceptable.

9. Recoveries for arsenic, barium, beryllium, cadmium, chromium, cobalt, nickel, selenium, silver, thallium, vanadium, and zinc were out of control limits in the soil matrix spike, MFH-409S. Reported concentrations and detection limits of these metals are considered estimates (J flag). The actual concentrations could be as great as 1.4, 1.5, 1.4, 1.6, 1.5, 1.5, 1.4, 3.3, 2.6, 1.3, 1.5. and 1.5 times the reported values, respectively.

10. Most recoveries in the soil post digestion spike, MFH-409, were within control limits. This indicates that there was a problem with the digestion procedure. Those elements still out of control limits were antimony and copper indicating possible matrix problems with these metals.
11. Reported concentrations for chromium in water samples are considered estimates (J flag) due to duplicate criteria out of control limits.
12. Results for copper in the soil duplicate were unacceptable and all results have been flagged as unusable (R flag) in the soil samples.

INORGANIC ANALYSIS SUMMARY FOR SOIL

SITE NAME AND NUMBER: GOODSON & SON TRUCKING
CASE NUMBER: 10883 PAGE 1 OF 2
CONCENTRATIONS IN PARTS PER MILLION (PPM)

TRAFFIC REPORT NUMBER AND STATION LOCATION.

		MFH-407	MFH-408	MFH-409	MFH-410	MFH-411
		STATION #01	STATION #02	STATION #03	STATION #04	STATION #05
		FILL MATERIAL	NORTH DITCH NEAR STORM SEWER	SOUTH DITCH	NORTH DITCH ABOVE SEWER	SOUTH DITCH BACKGROUND
	MATRIX	SOIL	SOIL	SOIL	SOIL	SOIL
	% MOISTURE	35	27	32	31	14
	CAS NO.					
ALUMINUM	7429-90-5	9890	5940	8790	9340J	2170
ANTIMONY	7440-36-0	OR	OR	OR	OR	OR
ARSENIC	7440-38-2	5.800J	2.800J	4.110J	4.400J	1.400J
BARIUM	7440-39-3	29.400J	53.400J	55.400J	138J	84.400J
BERYLLIUM	7440-41-7	0.920UJ	0.830UJ	0.880UJ	0.870UJ	0.700UJ
CADMIUM	7440-43-9	1.500J	1.600J	2.050J	2.040J	0.930J
CALCIUM	7440-70-2	159000J	138000J	153000J	151000J	17200J
CHROMIUM	7440-47-3	9.800J	6.050J	15.200J	16.300J	5.350J
COBALT	7440-48-4	1.530UJ	1.380UJ	2.350J	2.300J	1.160UJ
COPPER	7440-50-8	OR	OR	OR	OR	OR
IRON	7439-89-6	9130	6460	8660	8190	3500
LEAD	7439-92-1	OR	OR	OR	OR	OR
MAGNESIUM	7439-95-4	1920	2110	3100	3240	1069
MANGANESE	7439-96-5	96.300	69.900	149	177	111
MERCURY	7439-97-6	0.150U	0.140U	0.140U	0.140U	0.110U
NICKEL	7440-02-0	7.400J	7.900J	13.500J	18.500J	3.950J
POTASSIUM	7440-09-7	8240	4301	5510	4210	497
SELENIUM	7782-49-2	9.200UJ	0.830UJ	0.880UJ	0.870UJ	0.700UJ
SILVER	7440-22-4	0.920UJ	0.830UJ	0.880UJ	0.870UJ	0.700UJ
SODIUM	7440-23-5	2000	2047	865	634	80
THALLIUM	7440-28-0	1.230UJ	1.100UJ	1.170UJ	1.170UJ	0.930J
TIN	7440-31-5	ONA	ONA	ONA	ONA	ONA
VANADIUM	7440-62-2	17.200J	15.400J	17J	21.600J	7.700J
ZINC	7440-66-6	38.300J	33.600J	37.600J	58.600J	76J
CYANIDE		3J	1.300UJ	1.320UJ	1.400UJ	1.200UJ
HARDNESS		ONA	ONA	ONA	ONA	ONA
ALKALINITY		ONA	ONA	ONA	ONA	ONA

R - DATA IS UNUSABLE DUE TO QA/QC OUT OF CONTROL LIMITS.

J - REPORTED CONCENTRATIONS OR DETECTION LIMITS ARE ESTIMATES DUE TO QA/QC OUT OF CONTROL LIMITS.

B - CONCENTRATION IN SAMPLE ATTRIBUTABLE TO BLANK CONTAMINATION.

U - NOT DETECTED; VALUE REPORTED IS THE DETECTION LIMIT.

NA - NOT ANALYZED

INORGANIC ANALYSIS SUMMARY FOR SOIL

FILE NAME AND NUMBER: EGODSON & SON TRUCKING

PAGE 2 OF 2

CONCENTRATIONS IN PARTS PER MILLION (PPM)

TRAFFIC REPORT NUMBER AND STATION LOCATION.

	MFH-416	MFH-419	MFH-420		
	STATION #12	STATION #15	STATION #16		
	NORTH DITCH NEAR COVE	NORTH DITCH NEAR COVE DUPLICATE	SOUTH DITCH NEAR COVE		
MATRIX	SOIL	SOIL	SOIL		
% MOISTURE	18	19	19	0	0
CAS NO.					
ALUMINUM	7429-90-5	801	687	8310	0 0
ANTIMONY	7440-36-0	OR	OR	OR	0 0
ARSENIC	7440-38-2	0.980UJ	0.990UJ	3.200J	0 0
BARIUM	7440-39-3	15.900J	18.800J	100J	0 0
BERYLLIUM	7440-41-7	0.730UJ	0.740UJ	0.740J	0 0
CADMIUM	7440-43-9	0.730J	0.740J	1.200J	0 0
CALCIUM	7440-70-2	21000J	21000J	38500J	0 0
CHROMIUM	7440-47-3	5.100J	4.200J	10.600J	0 0
COBALT	7440-48-4	1.220UJ	1.200UJ	3.450J	0 0
COPPER	7440-50-8	OR	OR	OR	0 0
IRON	7439-89-6	1800	2050	9440	0 0
LEAD	7439-92-1	OR	OR	OR	0 0
MAGNESIUM	7439-95-4	1490	1540	2530	0 0
MANGANESE	7439-96-5	6030	61.100	177	0 0
MERCURY	7439-97-6	0.100U	0.080U	0.370	0 0
NICKEL	7440-02-0	2.700J	2.700J	7.600J	0 0
POTASSIUM	7440-09-7	249	220	2630	0 0
SELENIUM	7782-49-2	0.730UJ	0.740UJ	0.740UJ	0 0
SILVER	7440-22-4	0.730UJ	0.740UJ	0.740UJ	0 0
SODIUM	7440-23-5	1080	960	5100	0 0
THALLIUM	7440-28-0	0.980UJ	0.990UJ	0.990UJ	0 0
TIN	7440-31-5	ONA	ONA	ONA	0 0
VANADIUM	7440-62-2	3.700J	3.200J	24.700J	0 0
ZINC	7440-66-6	18.300J	14.100J	46.400J	0 0
CYANIDE		1.200J	1.020UJ	0.990UJ	0 0
HARDNESS		ONA	ONA	ONA	0 0
ALKALINITY		ONA	ONA	ONA	0 0

R - DATA IS UNUSABLE DUE TO QA/QC OUT OF CONTROL LIMITS.

J - REPORTED CONCENTRATIONS OR DETECTION LIMITS ARE ESTIMATES DUE TO QA/QC OUT OF CONTROL LIMITS.

B - CONCENTRATION IN SAMPLE ATTRIBUTABLE TO BLANK CONTAMINATION.

U - NOT DETECTED: VALUE REPORTED IS THE DETECTION LIMIT.

NA - NOT ANALYZED

INORGANIC ANALYSIS SUMMARY FOR WATER

SITE NAME AND NUMBER: GOODSON & SON TRUCKING
CASE NUMBER: 10883 PAGE 1 OF 2
CONCENTRATIONS IN PARTS PER BILLION (PPB)

TRAFFIC REPORT NUMBER AND STATION LOCATION.

	DRINKING WATER CRITERIA	MFH-412	MFH-413	MFH-414	MFH-415	MFH-417
		STATION #06	STATION #07	STATION #08	STATION #09	STATION #13
	P - PRIMARY	NORTH DITCH	NORTH DITCH	SOUTH DITCH	SOUTH DITCH	NORTH DITCH
	S - SECONDARY	NEAR STORM SEWER	NEAR COVE	NEAR SITE ENTRANCE	NEAR COVE	NEAR COVE
MATRIX		WATER	WATER	WATER	WATER	WATER
% MOISTURE		100	100	100	100	100
CAS NO.						
ALUMINUM	7429-90-5	2850J	435J	114J	128J	476J
ANTIMONY	7440-36-0	68JB	61JB	21JB	69JB	58JB
ARSENIC	7440-38-2 50P	25	4U	4U	4U	4U
BARIUM	7440-39-3 1000P	180	94	4U	116	94
BERYLLIUM	7440-41-7	3U	3U	3U	3U	3U
CADMIUM	7440-43-9 10P	7	9	7	13	8
CALCIUM	7440-70-2	65200J	93798J	22500J	179080J	93600J
CHROMIUM	7440-47-3 50P	21J	25J	7J	43J	28J
COBALT	7440-48-4	5U	5U	5U	6	5U
COPPER	7440-50-8 1000S	30	12	30	5	11
IRON	7439-89-6 300S	2820J	495J	415J	173J	539J
LEAD	7439-92-1 50P	20J	10J	12J	10J	10J
MAGNESIUM	7439-95-4	5560	185000	3810	511000	184000
MANGANESE	7439-96-5 50S	214	87	69	215	89
MERCURY	7439-97-6 2P	0R	0R	0R	0R	0R
NICKEL	7440-02-0	45	33	21	48	32
POTASSIUM	7440-09-7	1950000	136000	12200	155631	174000
SELENIUM	7782-49-2 10P	30U	3U	3U	30U	3U
SILVER	7440-22-4 50P	3U	5J	3U	8J	4J
SODIUM	7440-23-5	912000	1740000	814000	4870000	1700000
THALLIUM	7440-28-0	4UJ	4UJ	4UJ	4UJ	4UJ
TIN	7440-31-5	0NA	0NA	0NA	0NA	0NA
VANADIUM	7440-62-2	12	21	4U	30	20
ZINC	7440-66-6 5000S	249J	121J	125J	557J	337J
CYANIDE		29J	10UJ	10UJ	21J	10UJ
HARDNESS		0NA	0NA	0NA	0NA	0NA
ALKALINITY		0NA	0NA	0NA	0NA	0NA

R - DATA IS UNUSABLE DUE TO QA/QC OUT OF CONTROL LIMITS.

J - REPORTED CONCENTRATIONS OR DETECTION LIMITS ARE ESTIMATES DUE TO QA/QC OUT OF CONTROL LIMITS.

B - CONCENTRATION IN SAMPLE ATTRIBUTABLE TO BLANK CONTAMINATION.

U - NOT DETECTED; VALUE REPORTED IS THE DETECTION LIMIT.

NA - NOT ANALYZED

INORGANIC ANALYSIS SUMMARY FOR WATER

SITE NAME AND NUMBER: GOODSON & SON TRUCKING
CASE NUMBER: 10883 PAGE 2 OF 2
CONCENTRATIONS IN PARTS PER BILLION (PPB)

TRAFFIC REPORT NUMBER AND STATION LOCATION.

	DRINKING WATER CRITERIA		MFH-418	MFH-421	MFH-422		
			STATION #14	STATION #10	STATION #11		
	P - PRIMARY		TRIP BLANK	STORM SEWER	SOUTH DITCH		
	S - SECONDARY			NEAR ACCESS ROAD	BACKGROUND		
MATRIX			WATER	WATER	WATER		
% MOISTURE			100	100	100	0	0
CAS NO.							
ALUMINUM	7429-90-5		17J	256J	314J	0	0
ANTIMONY	7440-36-0		54JB	32JB	24JB	0	0
ARSENIC	7440-38-2	50P	4U	4.010	4U	0	0
BARIUM	7440-39-3	1000P	4U	44	4	0	0
BERYLLIUM	7440-41-7		3U	3U	3U	0	0
CADMIUM	7440-43-9	10P	3	4	3	0	0
CALCIUM	7440-70-2		198J	42200J	19957J	0	0
CHROMIUM	7440-47-3	50P	3UJ	4J	6J	0	0
COBALT	7440-48-4		5U	5U	5U	0	0
COPPER	7440-50-8	1000S	3	13	14	0	0
IRON	7439-69-6	300S	32UJ	430J	484J	0	0
LEAD	7439-92-1	50P	1UJ	4J	4J	0	0
MAGNESIUM	7439-95-4		46	3160	5340	0	0
MANGANESE	7439-96-5	50S	4U	48	55	0	0
MERCURY	7439-97-6	2P	0R	0R	0R	0	0
NICKEL	7440-02-0		8U	13	17	0	0
POTASSIUM	7440-09-7		275	7160	8855	0	0
SELENIUM	7782-49-2	10P	3U	3U	3U	0	0
SILVER	7440-22-4	50P	3U	3U	3U	0	0
SODIUM	7440-23-5		279	34400	316588	0	0
THALLIUM	7440-28-0		4UJ	4UJ	4UJ	0	0
TIN	7440-31-5		0NA	0NA	0NA	0	0
VANADIUM	7440-62-2		4	9	4	0	0
ZINC	7440-66-6	5000S	8J	635J	272J	0	0
CYANIDE			20J	10UJ	10UJ	0	0
HARDNESS			0NA	0NA	0NA	0	0
ALKALINITY			0NA	0NA	0NA	0	0

R - DATA IS UNUSABLE DUE TO QA/QC OUT OF CONTROL LIMITS.

J - REPORTED CONCENTRATIONS OR DETECTION LIMITS ARE ESTIMATES DUE TO QA/QC OUT OF CONTROL LIMITS.

B - CONCENTRATION IN SAMPLE ATTRIBUTABLE TO BLANK CONTAMINATION.

U - NOT DETECTED; VALUE REPORTED IS THE DETECTION LIMIT.

NA - NOT ANALYZED

Exhibit 4

**Commonly Occurring Metals
in the Soil**

by
W.L. Lindsey
(Chemical Equilibria in Soils)
Wiley Intersciences, N.Y.

	PRIMARY DRINKING WATER REGS (PPM)	SECONDARY DRINKING WATER REGS (PPM)	CHARACTERISTIC OF EP TOXICITY (PPM)	U.S. PUBLIC HEALTH SERVICE LIMIT (PPM)	COMMON RANGE IN SOIL (PPM)
ALUMINUM	----	----	----	----	10000-300000
ANTIMONY	----	----	----	----	2-10
ARSENIC	0.05	----	5.0	0.05	1-50
BARIUM	1.0	----	100	----	100-3000
BORON	----	----	----	----	2-100
BERYLLIUM	----	----	----	NOT GIVEN	0.1-40
BROMINE	----	----	----	----	1-10
CADMIUM	0.01	----	1.0	0.01	0.01-0.7
CALCIUM	----	----	----	----	----
CESIUM	----	----	----	----	0.3-25
CHLORINE	----	250	----	----	20-900
CHROMIUM	0.05	----	5.0	0.05	1-1000
COBALT	----	----	----	----	1-40
COPPER	----	1.0	----	1.0	2-100
GALLIUM	----	----	----	----	0.4-300
IODINE	----	----	----	----	0.1-40
IRON	----	0.3	----	0.05	10-4000
LANTHANUM	----	----	----	----	1-5000
LEAD	0.05	----	5.0	0.05	2-200
LITHIUM	----	----	----	----	5-200
MAGNESIUM	----	----	----	----	600-6000
MANGANESE	----	0.05	----	0.05	20-3000
MERCURY	0.002	----	0.2	NOT GIVEN	0.01-0.3
MOLYBDENUM	----	----	----	----	0.2-5
NICKEL	----	----	----	----	5-500
POTASSIUM	----	----	----	----	----
RADIUM	----	----	----	----	8 X 10 ⁻⁵
RUBIDIUM	----	----	----	----	50-500
SELENIUM	0.01	----	1.0	0.01	0.1-2
SILVER	0.05	----	5.0	0.05	0.01-5
SODIUM	----	----	----	----	----
STRONTIUM	----	----	----	----	50-1000
THALLIUM	----	----	----	----	----
TIN	----	----	----	----	2-200
URANIUM	----	----	----	----	0.9-9
VANADIUM	----	----	----	----	20-500
YTTRIUM	----	----	----	----	25-250
ZINC	----	5.0	----	5.0	10-300
ZIRCONIUM	----	----	----	----	60-2000
CYANIDE	----	----	----	----	----
HARDNESS	----	----	----	----	----
ALKALINITY	----	----	----	----	----

TABLE 1
Conductivity, Temperature, and pH
Measurements for all Water Samples
Collected at Goodson & Son Trucking

TABLE 1**WATER SAMPLE MEASUREMENTS**

SAMPLE NUMBER	CONDUCTIVITY (MICROMHOS/CM)	TEMPERATURE °C	pH
6	12000	20	11.7
7	9000	19	8.2
8	1300	24	7.1
9	15000	24	7.3
10	500	21	6.9
11	1200	24	7.3
13	9000	19	8.2

CHAIN OF CUSTODY RECORD

PROJ. NO. 10883		PROJECT NAME				NO. OF CON- TAINERS	<div style="display: flex; justify-content: space-between;"> <div>GC/MS: ARN</div> <div>Pesticide: PCP</div> <div>Veri</div> </div>						REMARKS	
SAMPLERS: (Signature) <i>T.D. Pierce</i>														
STA. NO.	DATE	TIME	COMP.	GRAB	STATION LOCATION	Tag #s						C-LP #		
03	11/15/88	1006 1008		✓	South Ditch	1	✓					6-014023	FJ 112	
03	11/15/88	1006 1008		✓	South Ditch	2		✓				6-014024, 6-014025	FJ 112	
05	11/15/88	0933 0935		✓	South Ditch Background West of Magnolia	1	✓	✓				6-014031	FJ 114	
05	11/15/88	0933 0935		✓	South Ditch Background West of Magnolia	2		✓				6-014032, 6-014033	FJ 114	
16	11/15/88	1036 1038		✓	South ditch near cave	1	✓	✓				6-014107	FJ 123	
16	11/15/88	1036 1038		✓	South ditch near cave	2		✓				6-014108, 6-014109	FJ 123	
01	11/15/88	1054 1056		✓	Fill Material	1	✓	✓				6-014015	FJ - 110	
01	11/15/88	1054 1056		✓	Fill Material	2		✓				6-014016, 6-014017	FJ 110	
11	11/15/88	0933 0941		✓	South Ditch Background West of Magnolia	4	✓	✓				6-014118, 6-014121 6-014120, 6-014122	FJ 125	
11	11/15/88	0933 0941		✓	South Ditch Background West of Magnolia	2		✓				6-014123, 6-014124	FJ 125	
09	11/15/88	1036 1043		✓	South Ditch Near Cave	4	✓	✓				6-014075, 6-014077 6-014076, 6-014078	FJ 118	
09	11/15/88	1036 1043		✓	South Ditch Near Cave	2		✓				6-014079, 6-014080	FJ 118	
08	11/15/88	1005 1012		✓	South Ditch	4	✓	✓				6-014067, 6-014069 6-014068, 6-014070	FJ 117	
08	11/15/88	1005 1012		✓	South Ditch	2		✓				6-014071, 6-014072	FJ 117	

Relinquished by: (Signature) <i>T.D. Pierce</i>	Date / Time 11/15/88 1600	Received by: (Signature) <i>Federal Express</i>	Relinquished by: (Signature)	Date / Time	Received by: (Signature)
Relinquished by: (Signature)	Date / Time	Received by: (Signature)	Relinquished by: (Signature)	Date / Time	Received by: (Signature)
Relinquished by: (Signature)	Date / Time	Received for Laboratory by: (Signature)	Date / Time	Remarks A-111# 9468 32 1380 OTR#	

Distribution: Original Accompanies Shipment; Copy to Coordinator Field Files

6-05921

CHAIN OF CUSTODY RECORD

Organisms

[illegible]

CHAIN OF CUSTODY RECORD

[illegible]

6-05916

[illegible]

6-05915-

Photograph Number 1

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Terry Pierce

Date: November 15, 1988

Time: 0934

Direction: Northeast

Comments: Sample location 05,
west of Market and Magnolia
street intersection.

(This photograph matches negative number 0)



Photograph Number 2

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Terry Pierce

Date: November 15, 1988

Time: 0936

Direction: East

Comments: Sample location 11,
west of Market and Magnolia
street intersection.

(This photograph matches negative number 1)



Photograph Number 3

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Terry Pierce

Date: November 15, 1988

Time: 1008

Direction: North

Comments: Sample location 03,
adjacent to site and between
the two entrances for the site.

(This photograph matches negative number 2)



Photograph Number 4

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Terry Pierce


Date: November 15, 1988

Time: 1009

Direction: Northeast

Comments: Sample location 08,
between the two entrances of the
site in the south ditch.

(This photograph matches negative number 3)



Photograph Number 5

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Terry Pierce

Date: November 15, 1988

Time: 1036

Direction: Northwest

Comments: Sample location 16,
near the southwest corner of
the site in the south ditch.

(This photograph matches negative number 4)



Photograph Number 6

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Terry Pierce

Date: November 15, 1988

Time: 1037

Direction: Northwest

Comments: Sample location 09,
near the southwest corner of the
site in the south ditch.

(This photograph matches negative number 5)



Photograph Number 7

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Terry Pierce

Date: November 15, 1988

Time: 1055

Direction: Northwest

Comments: Sample location 01,
sample of fill material onsite.

(This photograph matches negative number 6)



Photograph Number 3

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Terry Pierce

Date: November 15, 1988

Time: 1055

Direction: Northwest

Comments: Sample location 01,
collection of sample completed.

(This photograph matches negative number 7)



Photograph Number 9

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Joe Phillips


Date: November 16, 1988

Time: 0901

Direction: West

Comments: Sample location 10,
manhole adjacent to highway I-10
access road, north of the site.

(This photograph matches negative number 8)



Photograph Number 10

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Joe Phillips


Date: November 16, 1988

Time: 0903

Direction: Northwest

Comments: Sample location 10,
collection of the sample in the
manhole.

(This photograph matches negative number 9)



Photograph Number 11

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Joe Phillips

Date: November 16, 1988

Time: 0903

Direction: South

Comments: Sample location 04,
between the site and the access
road in the north ditch.

(This photograph matches negative number 10)



Photograph Number 12

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Joe Phillips.

Date: November 16, 1988

Time: 0906

Direction: North

Comments: Sample location 10,
collection of the sample.

(This photograph matches negative number 11)



Photograph Number 13

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Joe Phillips

Date: November 16, 1988

Time: 0907

Direction: Southeast

Comments: Sample location 04,
collection of the sample.

(This photograph matches negative number 12)



Photograph Number 14

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Joe Phillips


Date: November 16, 1988

Time: 0910

Direction: North

Comments: Sample location 10,
taking the conductivity and
pH of the sample.

(This photograph matches negative number 13)



Photograph Number 15

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Joe Phillips

Date: November 16, 1988

Time: 0915

Direction: Northwest

Comments: Sample location 10,
collection was completed.

(This photograph matches negative number 14)



Photograph Number 16

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Steve Cowan

Date: November 16, 1988

Time: 0936

Direction: North

Comments: Sample location 06,
note the oily sheen in the
north drainage ditch.

(This photograph matches negative number 15)



Photograph Number 17

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Steve Cowan

Date: November 16, 1988

Time: 0939

Direction: North

Comments: Sample location 02,
sample from the south side of
the north ditch.

(This photograph matches negative number 16)



Photograph Number 18

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Steve Cowan

Date: November 16, 1988

Time: 0943

Direction: North

Comments: Sample location 06,
collection of water sample from
the north ditch.

(This photograph matches negative number 17)



Photograph Number 19

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Steve Cowan

Date: November 16, 1988

Time: 0945

Direction: North

Comments: Sample location 06,
to provide a homogenous water
sample the water was poured from
one stainless steel bucket to
another.

(This photograph matches negative number 18)



Photograph Number 20

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Derrick Johnson

Witness: Steve Cowan

Date: November 16, 1988

Time: 0954

Direction: North

Comments: Sample location 06,
filling bottles for the sample.
QA/QC volume was taken for this
sample.

(This photograph matches negative number 19)



Photograph Number 21

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Terry Pierce

Witness: Steve Cowan

Date: November 16, 1988

Time: 1103

Direction: South-southwest

Comments: Sample location 15,
soil from the east end of the
north ditch.

(This photograph matches negative number 20)



Photograph Number 22

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Terry Pierce

Witness: Steve Cowan

Date: November 16, 1988

Time: 1107

Direction: South-southwest

Comments: Sample location 13,
water from the east end of the
north ditch.

(This photograph matches negative number 21)



Photograph Number 23

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Steve Cowan

Date: November 16, 1988

Time: 1141

Direction: North

Comments: A view of the office
on the west end of the site.

(This photograph matches negative number 22)



Photograph Number 24

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Steve Cowan


Date: November 16, 1988

Time: 1143

Direction: Northeast

Comments: A view of the entrance
on the southwest end of the site

(This photograph matches negative number 23)



Photograph Number 25

Site Name: Goodson & Son Trucking

CERCLIS: TXD981052475

Location: Channelview, TX

TDD Number: F-6-8809-29

Photographer: Victor Cason

Witness: Steve Cowan

Date: November 16, 1988

Time: 1145

Direction: East

Comments: A view of the south ditch.

(This photograph matches negative number 24)



Dangerous Properties of Industrial Materials

Sixth Edition

N. IRVING SAX

Assisted by:

Benjamin Feiner/Joseph J. Fitzgerald/Thomas J. Haley/Elizabeth K. Weisburger



VAN NOSTRAND REINHOLD COMPANY
New York

TOXICITY DATA: 1

orl-rat LD50: 17 gm/kg
skn-rbt LD50: 7940 mg/kg

CODEN:

AIHAAP 23,95,62
AIHAAP 23,95,62

Reported in EPA TSCA Inventory, 1980.

THR: LOW orl, skn.

Disaster Hazard: When heated to decomp it emits acrid smoke and irr fumes.

BIS(2-ETHYLHEXYL)MALEATE

CAS RN: 142165 NIOSH #: ON 0160000
mf: $C_{20}H_{36}O_4$; mw: 340.56

Liquid. mp: -60° , bp: 164° @ 10 mm, flash p: $365^\circ F$,
d: 0.9436 @ $20^\circ/20^\circ$, vap. d: 11.7.

SYNS:

DI-(2-ETHYLHEXYL)MALEATE "DIOCTYL" MALEATE

TOXICITY DATA: 1

skn-rbt 10 mg/24H MLD
eye-rbt 500 mg
orl-rat LD50: 14 gm/kg
skn-rbt LD50: 15 gm/kg

CODEN:

JIHTAB 31,60,49
JIHTAB 31,60,49
JIHTAB 31,60,49
JIHTAB 31,60,49

Reported in EPA TSCA Inventory, 1980. EPA TSCA
8(a) Preliminary Assessment Information Proposed
Rule FERREAC 45,13646,80.

THR: LOW orl, skn. A skn, eye irr. See also esters.

Fire Hazard: Slight, when exposed to heat or flame; can react with oxidizing materials.

To Fight Fire: Alcohol foam, dry chemical, mist or spray.

Disaster Hazard: When heated to decomp it emits acrid smoke and irr fumes.

BIS((2-(ETHYL)HEXYLOXY)MALEOYLOXY)DI(n-BUTYL)STANNANE

NIOSH #: WH 6717000
mf: $C_{32}H_{56}O_8Sn$; mw: 687.57

SYN: 2-ETHYLHEXYLMALEINAN DI-N-BUTYLCLINICITY (CZECH)

TOXICITY DATA: 3

skn-rbt 500 mg/24H MOD
eye-rbt 100 mg/24H SEV
orl-rat LD50: 284 mg/kg

CODEN:

28ZPAK -,230,72
28ZPAK -,230,72
28ZPAK -,230,72

Occupational Exposure to Organotin Compounds recm
std: Air: TWA 0.1 mg(Sn)/m³ NTIS**.

THR: HIGH orl. A skn, eye irr. See also tin compounds.

Disaster Hazard: When heated to decomp it emits acrid smoke and irr fumes.

BIS(2-ETHYLHEXYL)AZELATE

CAS RN: 103242 NIOSH #: CM 2000000
mf: $C_{25}H_{48}O_4$; mw: 412.73

SYNS:

AZELAIC ACID, DI(2-ETHYL-HEXYL)ESTER DIOCTYL AZELATE

TOXICITY DATA: 2

skn-rbt 10 mg/24H open MLD
ivn-rat LD50: 1060 mg/kg
ivn-rbt LD50: 640 mg/kg

CODEN:

AIHAAP 23,95,62
MRLR** No.256,54
MRLR** No.256,54

Reported in EPA TSCA Inventory, 1980. EPA TSCA
8(a) Preliminary Assessment Information Proposed
Rule FERREAC 45,13646,80.

THR: MOD ivn; A skn irr. See also esters.

Disaster Hazard: When heated to decomp it emits acrid smoke and irr fumes.

BIS(2-ETHYLHEXYL)PHOSPHATE

CAS RN: 298077 NIOSH #: TB 7875000
mf: $C_{16}H_{35}O_4P$; mw: 322.48

SYNS:

BIS(2-ETHYLHEXYL)HYDROGEN PHOSPHATE DI(2-ETHYLHEXYL)PHOSPHATE
BIS(2-ETHYLHEXYL)ORTHOPHOSPHORIC ACID 2-ETHYL-1-HEXANOL HYDROGEN PHOSPHATE
BIS(2-ETHYLHEXYL)PHOSPHORIC ACID

TOXICITY DATA: 3-2-1

skn-rbt 500 mg open MOD
eye-rbt 5 mg MOD
orl-rat LD50: 4940 mg/kg
ipr-mus LDLo: 63 mg/kg
skn-rbt LD50: 1250 mg/kg

CODEN:

UCDS** 5/18/72
UCDS** 5/18/72
UCDS** 5/18/42
CBCCT* 9,132,57
UCDS** 5/18/72

DOT: Corrosive Material, Label: Corrosive FEREAC
41,57018,76. Reported in EPA TSCA Inventory, 1980.

THR: HIGH ipr; MOD skn; LOW orl. MOD skn, eye irr.

Disaster Hazard: When heated to decomp it emits tox fumes of PO_x .

BIS(2-ETHYLHEXYL)PHTHALATE

CAS RN: 117817 NIOSH #: TI 0350000
mf: $C_{24}H_{38}O_4$; mw: 390.62

SYNS:

BIS(2-ETHYLHEXYL)-1,2-BENZENEDICARBOXYLATE DOP
DI(2-ETHYLHEXYL)ORTHOPHTHALATE 2-ETHYLHEXYL PHTHALATE
DI(2-ETHYLHEXYL)PHTHALATE NCI-C52733
DI-SEC-OCTYL PHTHALATE OCTOIL

TOXICITY DATA: 3-2-1

skn-rbt 500 mg/24H MLD
eye-rbt 500 mg
eye-rbt 500 mg/24H MLD
ipr-rat TDLo: 30 gm/kg/(5-15D preg); TER
orl-mus TDLo: 7500 mg/kg/(8D preg); TER

28ZPAK -,48,72
AJOPAA 29,1363,46
28ZPAK -,48,72
JPMSAE 61,51,72

TJADAB 14,259,76

orl-man TDLo: 143 mg/kg; GIT
orl-rat LD50: 31 gm/kg
ipr-rat LD50: 30700 mg/kg
ivn-rat LD50: 250 mg/kg
unk-rat LD50: 37000 mg/kg
orl-mus LD50: 30 gm/kg
ipr-mus LD50: 14 gm/kg
unk-mus LD50: 37000 mg/kg
orl-rbt LD50: 34 gm/kg
skn-rbt LD50: 25 gm/kg
skn-gpg LD50: 10 gm/kg
unk-gpg LD50: 37000 mg/kg
ihl-mam LC50: 30000 mg/m³
orl-rat TDLo: 35 mg/kg (14D male/14D pre)

JIHTAB 27,130,45
UCDS** 7/20/67
JIHTAB 27,130,45
TXAPA9 45,230,78
GTPZAB 24(3),25,80
TJADAB 14,259,76
JPMSAE 55,158,66
GTPZAB 24(3),25,80
EVHPAZ 4,3,73
JIHTAB 27,130,45
EVHPAZ 4,3,73
GTPZAB 24(3),25,80
GTPZAB 24(3),25,80
FCTXAV 15,389,77

482 BIS(2-ETHYLHEXYL)SEBACATE

orl-rat TDLo:8400 ug/kg (7D male) TXAPA9 53,35,80
orl-rat TDLo:17200 mg/kg (MGN) NEZAAQ 31,507,76
orl-rat TDLo:43 gm/kg (MGN) NEZAAQ 31,507,76
ipr-rat TDLo:10 gm/kg (5-15D preg) JPMSAE 61,51,72
ipr-rat TDLo:5 gm/kg (5-15D preg) JPMSAE 61,51,72
orl-mus TDLo:1 gm/kg (7D preg) JEPTDQ 4,533,80
orl-mus TDLo:1260 mg/kg (1-18D preg) ENVRAL 22,245,80
orl-mus TDLo:3420 mg/kg (1-18D preg) ENVRAL 22,245,80
orl-mus TDLo:7200 mg/kg (1-18D preg) ENVRAL 22,245,80

TLV: Air: 5 mg/m³ DTLVS* 4,159,80. *Toxicology Review*: EVHPAZ (3),73,73; RREVAH 54,1,75; JOCMA7 15(10),808,73; CMIVAS 10(3),49,73; ESKHA5 93,1,75; TXAPA9 45,1,78. OSHA Standard: Air: TWA 5 mg/m³ (SCP-D) FERREAC 39,23540,74. NTP Carcinogenesis Bioassay Completed as of December 1980. "NIOSH Manual of Analytical Methods" Vol 1 S40. Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary Assessment Information Proposed Rule FERREAC 45,13646,80.

THR: An exper TER, GIT (man). Possible hmn CARC. HIGH ivn; LOW orl, ipr, unk, skn; MLD skn, eye irr.

Disaster Hazard: When heated to decomp it emits acrid smoke.

For further information see Di-(2-Ethylhexyl)Phthalate, Vol. 1, No. 7 and Vol. 2, No. 2 of *DPIM Report*.

BIS(2-ETHYLHEXYL)SEBACATE

CAS RN: 122623 NIOSH #: VS 1000000
mf: C₂₆H₅₀O₄; mw: 426.76

Light, clear liquid, mild odor. bp: 248° @ 9 mm, fp: -55°, flash p: 410°F, d: 0.913 @ 25°/25°, vap. d: 14.7.

SYNS:

DECANEDIOIC ACID, BIS(2-ETHYLHEXYL) ESTER
DI(2-ETHYLHEXYL)SEBACATE
DIOCTYL SEBACATE
2-ETHYLHEXYL SEBACATE
OCTYL SEBACATE

TOXICITY DATA: 2 CODEN:
orl-rat LD50:1280 mg/kg 14CYAT 2,1883,63
ivn-rat LD50:900 mg/kg MRLR** No.256,54
ivn-rbt LD50:540 mg/kg MRLR** No.256,54

Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary Assessment Information Proposed Rule FERREAC 45,13646,80.

THR: MOD orl, ivn. See also esters.

Fire Hazard: Slight, when exposed to heat or flame; can react with oxidizing materials.

To Fight Fire: Foam, CO₂, dry chemical.

Disaster Hazard: When heated to decomp it emits acrid smoke and irr fumes.

BIS(2-ETHYLHEXYL)SEBACATE and 2,6-DI-t-BUTYL-p-CRESOL

NIOSH #: VS 1010000

SYNS:

SEBACIC ACID, BIS(2-ETHYLHEXYL) ESTER MIXED WITH 2,6-DI-T-BUTYL-P-CRESOL (99.5%:0.5% BY WT)
2,6-DI-T-BUTYL-P-CRESOL MIXED WITH BIS(2-ETHYLHEXYL) SEBACATE

TOXICITY DATA: 2 CODEN:
ivn-rat LD50:900 mg/kg MRLR** No.256,54
ivn-rbt LD50:760 mg/kg MRLR** No.256,54

THR: MOD ivn. See also esters.

Disaster Hazard: When heated to decomp it emits acrid smoke and irr fumes.

BIS(2-ETHYLHEXYL)SEBACATE and PHENOTHIAZINE

NIOSH #: VS 1020000

SYNS:

SEBACIC ACID, BIS(2-ETHYLHEXYL)ESTER MIXED WITH PHENOTHIAZINE (99.5%:0.5% BY WT)
PHENOTHIAZINE MIXED WITH BIS(2-ETHYLHEXYL)SEBACATE

TOXICITY DATA: 2 CODEN:
ivn-rat LD50:900 mg/kg MRLR** No.256,54
ivn-rbt LD50:1060 mg/kg MRLR** No.256,54

THR: MOD ivn. See also esters.

Disaster Hazard: When heated to decomp it emits very tox fumes of NO_x and SO_x.

BIS(2-ETHYLHEXYL)SEBACATE and TRICRESYL PHOSPHATE

NIOSH #: VS 1030000

SYNS:

SEBACIC ACID, BIS(2-ETHYLHEXYL)ESTER MIXED WITH TRICRESYL PHOSPHATE (95%:5% BY WT)
TRICRESYL PHOSPHATE MIXED WITH BIS(2-ETHYLHEXYL) SEBACATE

TOXICITY DATA: 2 CODEN:
ivn-rat LD50:1490 mg/kg MRLR** No.256,54
ivn-rbt LD50:900 mg/kg MRLR** No.256,54

THR: MOD ivn. See also esters.

Disaster Hazard: When heated to decomp it emits tox fumes of PO_x.

BIS(ETHYLMERCURY)PHOSPHATE

CAS RN: 2440451 NIOSH #: OW 4375000
mf: C₄H₁₁Hg₂O₄P; mw: 555.30

Solid

SYNS:

ETHYLMERCURIC PHOSPHATE
ETHYLMERCURY PHOSPHATE
LIGNASAN FUNGICIDE

TOXICITY DATA: 3 CODEN:
scu-mus TDLo:40 mg/kg (10D preg) NISFAY 20,1479,68
orl-rat LD50:30 mg/kg PCOC** -,516,66
unk-rat LD50:30 mg/kg 30ZDA9 -,288,71
orl-mus LD50:61 mg/kg KUMJAX 14,65,61
scu-mus LD50:63 mg/kg KUMJAX 14,65,61

616 CAFFEINE HYDROBROMIDE

ivn-dog LDLo: 4 mg/kg
 orl-cat LDLo: 100 mg/kg
 ipr-cat LDLo: 180 mg/kg
 scu-cat LDLo: 150 mg/kg
 ivn-cat LDLo: 80 mg/kg
 orl-rbt LDLo: 355 mg/kg
 ipr-rbt LDLo: 150 mg/kg
 scu-rbt LDLo: 275 mg/kg
 ivn-rbt LDLo: 80 mg/kg
 ims-rbt LDLo: 200 mg/kg
 orl-gpg LDLo: 280 mg/kg
 ipr-gpg LDLo: 220 mg/kg
 scu-gpg LDLo: 200 mg/kg
 orl-ham LD50: 239 mg/kg
 scu-pgn LDLo: 140 mg/kg
 scu-frg LDLo: 120 mg/kg
 par-frg LDLo: 800 mg/kg

HBAMAK 4,1335,35
 HBAMAK 4,1335,35
 HBAMAK 4,1335,35
 HBAMAK 4,1335,35
 JPETAB 1,572,10
 HBAMAK 4,1335,35
 JPETAB 1,572,10
 HBAMAK 4,1335,35
 JPETAB 1,572,10
 HBAMAK 4,1335,35
 HBAMAK 4,1335,35
 HBAMAK 4,1335,35
 TXAPA9 37,93,76
 JPETAB 1,572,10
 APTOA6 15,331,59
 AEPPAE 166,437,32

Toxicology Review: JIMRBV 2,359,74; 31ZNA4 3(3),345,75; JRPMAP 12(1),27,74; CLPTAT 5,480,64; 32XPAD -,49,75; ADVPA3 4,263,66; FNCSA6 2, 67,73. Selected by NTP Carcinogenesis Bioassay as of December 1980. Reported in EPA TSCA Inventory, 1980.

THR: MUT data. An exper TER. A hmn CNS, IRR. HIGH hmn ivn, orl. HIGH orl, ipr, scu, ivn, ims. MOD par, scu, orl. Implicated in increased fetal losses. An exper carc. A general purpose food additive. Large doses (above 1.0 g) cause palpitation, excitement, insomnia, dizziness, headache and vomiting. Continued excessive use of caffeine in tea or coffee may lead to digestive disturbances, constipation, palpitations, shortness of breath and depressed mental states. It is also implicated in cardiac disorders under those conditions.

Treatment and Antidotes: Evacuate stomach with emetic or stomach tube. Call a physician.

Disaster Hazard: When heated to decomp it emits tox fumes of NO_x.

For further information see Vol. 1, No. 1 of *DPIM Report*.

CAFFEINE HYDROBROMIDE

CAS RN: 5743180 NIOSH #: EV 6599500
 mf: C₈H₁₀N₄O₂·BrH; mw: 275.14

SYNS:

CAFFEINE BROMIDE

3,7-DIHYDRO-1,3,7-TRIMETHYL-
 1H-PURINE-2,6-DIONE,
 MONOHYDROBROMIDE

TOXICITY DATA:

3

orl-rbt LDLo: 400 mg/kg
 scu-rbt LDLo: 150 mg/kg
 ivn-rbt LDLo: 100 mg/kg

CODEN:

HBAMAK 4,1289,35
 HBAMAK 4,1289,35
 HBAMAK 4,1289,35

THR: HIGH orl, scu, ivn. See also caffeine and bromides.

Disaster Hazard: When heated to decomp it emits very tox fumes of NO_x and HBr.

CAJEPUTOL

CAS RN: 470826 NIOSH #: OS 9275000
 mf: C₁₀H₁₈O; mw: 154.28

SYNS:

1,8-CINEOLE
 1,8-EPOXY-P-MENTHANE
 EUCALYPTOL

LIMONENE OXIDE
 NCI-C56573
 1,8-OXIDO-P-MENTHANE

TOXICITY DATA:

3

ipr-mus TDLo: 2400 mg/kg/8W-
 I:ETA

orl-rat LD50: 2480 mg/kg
 scu-mus LDLo: 50 mg/kg
 ims-mus LD50: 100 mg/kg
 scu-dog LDLo: 1500 mg/kg
 ims-gpg LDLo: 2250 mg/kg

CODEN:

CNREA8 33,3069,73

FCTXAV 2,327,64

TFAKA4 1,134,55

JSICAZ 21,342,62

TFAKA4 1,134,55

TFAKA4 1,134,55

Toxicology Review: 27ZTAP 3,69,69. Selected by NTP Carcinogenesis Bioassay as of December 1980. Reported in EPA TSCA Inventory, 1980.

THR: HIGH scu, ims. An exper ETA. MOD orl, scu, ims.

Disaster Hazard: When heated to decomp it emits acrid smoke.

CALCIUM

CAS RN: 7440702

NIOSH #: EV 8040000

af: Ca; aw: 40.08

Silver-white, soft metal. mp: 842°, bp: 1484°, d: 1.54 @ 20°, vap. press: 10 mm @ 983°.

SYNS:

CALCIUM, METAL, CRYSTALLINE CALCIUM, METAL (DOT)
 (DOT)

TOXICITY DATA:

DOT: Flammable Solid, Label: Flammable Solid and Dangerous When Wet FEREAC 41,57018,76. "NIOSH Manual of Analytical Methods" VOL 5 173#. Reported in EPA TSCA Inventory, 1980.

THR: See calcium compounds.

Fire Hazard: Mod, when heated or in intimate contact with moisture or acids, evolves hydrogen. See also hydrogen.

Explosion Hazard: Mod, in intimate contact with very powerful oxidizing agents; i.e., Cl₂, ClF₃, F₂, O₂, Si, S, and V₂O₅.

Disaster Hazard: Dangerous; reacts with moisture or acids to liberate large quantities of hydrogen; can develop explosive pressure in containers. See also hydrogen.

To Fight Fire: Special mixtures of dry chemical.

Incomp: Air; asbestos cement; halogens; lead dichloride; phosphorus (V) oxide; silicon; sodium, mixed oxides; sulfur; water.

CALCIUM ACETARSONE

CAS RN: 64046964

NIOSH #: CF 8575000

mf: C₈H₁₀AsNO₅·xCa; mw: 555.67

SYN: N-ACETYL-4-HYDROXY-M-ARSANILIC ACID CALCIUM SALT

TOXICITY DATA:

3

orl-cat LDLo: 135 mg/kg

CODEN:

PSEBAA 27,267,30

OSHA Standard: Air: TWA 500 ug(As)/m3 FEREAC 39,23540,74.

THR: HIGH orl. See also arsenic compounds.

Disaster Hazard: When heated to decomp it emits very tox fumes of As and NO_x.

TOXICITY DATA: 2

ihl-rat LCLo: 520 mg/m³/4H
 unk-rat LDLo: 452 mg/kg
 unk-mus LDLo: 580 mg/kg

CODEN:

HYSAAV 31,383,66
 HYSAAV 31,383,66
 HYSAAV 31,383,66

THR: MOD ihl, unk. See also esters.

Disaster Hazard: When heated to decomp it emits tox fumes of Cl⁻.

DDT

CAS RN: 50293

NIOSH #: KJ 3325000

mf: C₁₄H₉Cl₅; mw: 354.48

Colorless crystals or white to slightly off-white powder. Odorless or with slight aromatic odor. mp: 108.5°-109°.

SYNS:

ALPHA,ALPHA-BIS(P-CHLORO-PHENYL)-BETA,BETA,BETA-TRICHLOROETHANE
 2,2-BIS(P-CHLOROPHENYL)-1,1,1-TRICHLOROETHANE
 CHLOROPHENOTHANE
 P,P'-DDT
 P,P'-DICHLORODIPHENYLTRI-CHLOROETHANE
 4,4'-DICHLORODIPHENYLTRI-CHLOROETHANE
 DIPHENYLTRICHLOROETHANE

ENT 1,506
 NCI-C00464
 1,1,1-TRICHLOR-2,2-BIS(4-CHLOR FENYL)-ETHAAN (DUTCH)
 1,1,1-TRICHLOR-2,2-BIS(4-CHLOR-PHENYL)-AETHAN (GERMAN)
 1,1,1-TRICHLORO-2,2-DI(4-CHLOROPHENYL)-ETHANE
 1,1,1-TRICLORO-2,2-BIS(4-COLOR-FENIL)-ETANO (ITAL-IAN)

TOXICITY DATA: 3

cyt-hmn:lym 200 ug/L/72H
 dlt-rat-ori 100 mg/kg
 spm-rat-ori 1 gm/kg/2D-I
 cyt-mus-ivr 50 ppm
 cyt-mus-unk 50 mg/kg
 dlt-mus-ori 100 mg/kg
 dlt-mus-unk 200 mg/kg/10W-I
 ori-rat TDLo: 19 gm/kg/2Y-C:NEO
 ori-mus TDLo: 73 mg/kg/26W-C:CAR
 scu-mus TDLo: 370 mg/kg/80W-I:NEO
 ori-mus TD: 11 gm/kg/78W-C:ETA

CODEN:

MUREAV 40,131,76
 FCTXAV 11,53,73
 BECTA6 14,171,75
 CNJGA8 16,491,74
 PHTHDT 6,147,79
 PHTHDT 6,147,79
 PHTHDT 6,147,79
 IJCNAW 19,179,77
 FCTXAV 7,215,69

IJCNAW 19,725,77

NCITR* NCI-CG-TR-131,78
 FCTXAV 11,433,73

ori-mus TD: 7560 mg/kg/90W-C:NEO

ori-mus TD: 5600 mg/kg/80W-I:NEO

ori-rat TD: 8100 mg/kg/2Y-C:ETA

ori-inf LDLo: 150 mg/kg

ori-hmn TDLo: 6 mg/kg:CNS

unk-man LDLo: 221 mg/kg

ori-rat LD50: 113 mg/kg

skn-rat LD50: 1931 mg/kg

ivr-rat LD50: 74 mg/kg

scu-rat LD50: 1500 mg/kg

ivr-rat LDLo: 30 mg/kg

ivr-rat LD50: 68 mg/kg

ori-mus LD50: 135 mg/kg

ivr-mus LD50: 77 mg/kg

ivr-mus LD50: 68500 ug/kg

ori-dog LDLo: 300 mg/kg

ivr-dog LDLo: 75 mg/kg

ori-mky LD50: 200 mg/kg

ivr-mky LDLo: 50 mg/kg

ori-cat LDLo: 250 mg/kg

ivr-cat LDLo: 40 mg/kg

ori-rbt LD50: 250 mg/kg

skn-rbt LD50: 300 mg/kg

scu-rbt LD50: 250 mg/kg

IJCNAW 19,725,77

TXAPA9 11,88,67

BMJOAE 2,845,45

DTLVS* 3,68,71

85DCAI 2,73,70

TXAPA9 2,88,60

SPEADM 74-1,-,74

ANTBAL 14,316,69

BMJOAE 1,865,45

JPETAB 86,213,46

ANTBAL 14,316,69

FEPRA7 12,368,53

ANTBAL 14,316,69

ANTBAL 14,316,69

MEMOAG 4,25,50

JPETAB 86,213,46

AVPCAQ 12,31,75

JPETAB 86,213,46

JPETAB 86,213,46

JPETAB 86,213,46

PCOC** -,347,66

BMJOAE 1,865,45

BMJOAE 1,865,45

ivr-rbt LDLo: 50 mg/kg
 ori-gpg LD50: 150 mg/kg
 skn-gpg LD50: 1000 mg/kg
 scu-gpg LD50: 900 mg/kg
 ori-ckn LDLo: 300 mg/kg
 ori-frg LD50: 7600 ug/kg
 scu-frg LD50: 35 mg/kg
 ori-dom LDLo: 300 mg/kg
 dlt-ola-ori 200 ppm
 cyt-hmn:lym 200 ug/L/72H
 cyt-rat:oth 10 ug/L
 ori-rat TDLo: 390 mg/kg (1-20D preg)
 ivr-rat TDLo: 60 mg/kg (3D pre)
 scu-mus TDLo: 418 mg/kg (6-14D preg)
 unk-mus TDLo: 3 mg/kg (10-17D preg)
 ori-dog TDLo: 3540 mg/kg (MGN)
 ori-rbt TDLo: 150 mg/kg (7-9D preg)
 ori-mus TDLo: 3408 mg/kg (MGN)
 TFX:NEO

JPETAB 86,213,46
 JETOAS 7,159,74
 BMJOAE 1,865,45
 BMJOAE 1,865,45
 MEMOAG 4,25,50
 ENVPAF 20,45,79
 AIPTAK 74,343,47
 MEMOAG 4,25,50
 ETEAAT 12,221,69
 MUREAV 40,131,76
 34LXAP -,555,76
 GISAAA 45(6),14,80
 TXAPA9 18,348,71
 NTIS** PB223-160

TXAPA9 22,327,72

AECTCV 6,83,77

AIPTAK 192,286,71

IJCNAW 11,688,73

Aquatic Toxicity Rating: TLM96:under 1 ppm
 WQCHM* 2,-,74. Carcinogenic Determination: Animal Suspected IARC** 5,83,74. TLV: Air: 1 mg/m³
 DTLVS* 4,117,80; Toxicology Review: JSIRAC 34,462,75; AABIAV 35,505,48; ATXKA8 29,1,72; ADCSAJ 1,160,50; ENVRAL 7(2),243,74; RREVAH 48,141,73; RREVAH 59,119,75; ADCSAJ 1,160,50; RREVAH 61,37,75; NOALA4 41(217),271,75; MZUZA8 (8),90,73; CNDQA8 10(3),43,75; ECMAAI 14(3),141,73; DTTIAF 80(20),485,73; RREVAH 56,107,75; AJDDAL 20,331,53; AJMEAZ 38,409,65; ETOXAC 7,1,76; IRGGAJ 24,193,68; BISNAS 20,958,70; 85CVA2 5,250,70; PTPAD4 7,513,79; CTXAO 13,231,78; EESADV 1,89,77; EESADV 1,503,78; BNYMAM 54,413,78; 27ZTAP 3,45,69. OSHA Standard: Air: TWA 1 mg/m³ (skin) (SCP-S) FEREAC 39,23540,74. DOT: ORM-A, Label: None FEREAC 41,57018,76. NCI Carcinogenesis Bioassay Completed; Results Negative (NCITR* NCI-CG-TR-131,78). "NIOSH Manual of Analytical Methods" VOL 3 S274. Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary Assessment Information Proposed Rule FERREAC 45,13646,80.

THR: HIGH via oral and dermal routes. Used as a food additive permitted in the food and drinking water of animals and/or for the treatment of food-producing animals. Also a food additive permitted in food for human consumption. Note: DDT is a common air contaminant.

DDT is readily absorbed from the intestinal tract and, if it occurs in the air in the form of an aerosol or dust, it may be taken into the lung and readily absorbed. DDT is not, however, absorbed from the skin unless it is in solution. Solutions are absorbed from the skin and, by the same token, emulsions are absorbed to some extent. Likewise, fats and oils from whatever source increase the absorption of DDT from the intestine. DDT acts on the CNS, but the exact mechanism of this action either in man or in animals has not been elucidated. DDT is an exper MUT, CARC, ETA, NEO. See chlorinated hydrocarbons. Large doses of DDT also induce nausea and/or diarrhea in man; how-

ever, whether this is a central or local action is not yet clear. Chronically, DDT produces microscopic changes in the liver and kidneys in some exper animals. This has not been demonstrated in man. DDT is secreted in the milk and, as an acid derivative is excreted in the urine of rabbits, dogs and man. DDT and certain of its degradation products, particularly DDE, are stored in fat. Such storage results either from a single large dose or from repeated small doses. DDT stored in the fat is at least largely inactive since a greater total dose may be stored in an exper animal than is sufficient as a lethal dose for that same animal if given at one time. A study based on 75 human cases reported an average of 5.3 ppm of DDT stored in the fat. A higher content of DDT and its derivatives (up to 434 ppm of DDE and 648 ppm of DDT) was found in workers who had very extensive exposure. Without exception, the samples were taken from persons who were either asymptomatic or suffering from some disease completely unrelated to DDT. Careful hospital examination of workers, who had been very extensively exposed and who had volunteered for examination revealed no abnormality which could be attributed to DDT. Much higher levels than have been found in man have been observed in the fat of exper animals which were apparently asymptomatic. DDT stored in the fat is eliminated only very gradually when further dosage is discontinued. After a single dose, the secretion of DDT in the milk and its excretion in the urine reach their height within a day or two and continue at a lower level thereafter.

Dangerous Acute Dose in Man: A dose of 20 g has proved highly dangerous though not fatal to man. This dose was taken by 5 persons who vomited an unknown portion of the material and even so recovered only incompletely after 5 weeks. Smaller doses produced less important symptoms with relatively rapid recovery. Exper ingestion of 1.5 g resulted in great discomfort and moderate neurological changes including paraesthesia, tremor, moderate ataxia, exaggeration of part of the reflexes, headache, and fatigue. Vomiting followed only after 11 hours. Recovery was complete on the following day. The fatal dose of DDT for man is not known. Judging from the literature, no one has ever been killed by DDT in the absence of other insecticides and/or a variety of toxic solvents. However, these common solvent formulations are highly fatal when taken in small doses, partly because of the toxicity of the solvent, and perhaps because of the increased absorbability of the DDT; several fatal cases in man have been reported. Acute oral toxicity for man = 250 mg/kg. Acute oral LD₅₀ (rat) = 113 mg/kg (tech grade). Federal fruit and vegetable tolerance = 7 ppm.

Dangerous Chronic Dose in Man: Even less is known of the hazard of chronic DDT poisoning. It is known that certain exper animals fed diets containing one part of DDT per million store the compound in their fat. The storage of DDT in man has been mentioned above. The exact significance of these findings is not known and their further investigation is of the

greatest importance. Human volunteers have ingested up to 35 mg/day for 21 months with no ill effects.

Signs and Symptoms of Poisoning in Man: In patients who ate substantial doses of DDT in flour, the symptoms observed were vomiting, numbness and partial paralysis of the extremities, mild convulsions, loss of proprioception and vibratory sensation of the extremities, and hyperactive knee jerk reflexes. Symptoms appeared in 30 to 60 min after eating the DDT. The paralysis and numbness were most evident in the most distal portions of the extremities, and their intensity was directly proportional to the amount of DDT ingested. All the patients were apprehensive and excited; respiration was moderately rapid; pulse remained slow to normal. The immediate protective mechanism in man, following substantial doses, is vomiting. With smaller doses, nausea and vomiting are less prominent, but diarrhea has been observed. Signs and symptoms of chronic poisoning in man are unknown, although, judging from the observed microscopic changes in exper animals, liver and kidney dysfunctions should be looked for. The primary irr of DDT is practically nil, and it has little or no tendency to produce allergy. Dermatitis induced by DDT has occasionally been reported, but these reports are unconfirmed; nevertheless the phenomenon should be expected to occur in rare instances.

Laboratory Findings: Laboratory findings are essentially negative except for the presence of DDT which may be quantitatively measured in stomach contents, urine, or tissues.

Treatment of Poisoning: Depending on the condition of the patient, attention should first be given to the sedation or to the removal of poison which may have been taken internally. Stomach lavage and saline laxatives may be used. Oil laxatives should be avoided; they promote absorption of DDT and of many organic solvents. The five drugs of choice, arranged roughly in order of their effectiveness, are phenobarbital, pentobarbital, paraldehyde, urethane, and calcium gluconate. Phenobarbital, which has been used in doses up to 0.7 g per day in epilepsy, and pentobarbital (0.25 to 0.5 g) are the barbiturates known to control convulsions of central origin. Paraldehyde (average dosage 15 cc orally, 1 cc undiluted intravenously, 35 cc rectally in normal saline) controls the convulsions of DDT-poisoned animals. Urethane (human dosage 1 to 4 g) has proved very effective in rats, but it should be remembered that the hypnotic and narcotic effects of urethane are not correspondingly high in man. Urethane has an added advantage, however, of being tolerated in the young and the aged. The object of sedation is not to induce sleep but to restore a relative calm; however, the proper dosage in the presence of poisoning may be so large that it would induce anesthesia if poisoning were not present.

Calcium gluconate has been used less than the other antidotes, but it is reported to control DDT-induced convulsions in several animals. Since its mechanism

856 DEACETYLCEPHALOTHIN SODIUM SALT

of action is entirely different, it may be used in addition to sedatives. Epinephrine is contraindicated.
For further information see Vol. 1, No. 3 of *DPIM Report*.

DEACETYLCEPHALOTHIN SODIUM SALT

NIOSH #: XI 0383500
mf: $C_{14}H_{13}N_2O_5S_2 \cdot Na$; mw: 376.40

SYN: DESACETYLCEPHALOTHIN SODIUM

TOXICITY DATA:	1	CODEN:
ipr-rat LD50:8877 mg/kg		JJANAX 28,81,75
ivn-rat LD50:6116 mg/kg		JJANAX 28,81,75
ipr-mus LD50:8754 mg/kg		JJANAX 28,81,75
ivn-mus LD50:6600 mg/kg		JJANAX 28,81,75

THR: LOW ipr, ivn.
Disaster Hazard: When heated to decomp it emits very tox fumes of SO_x and NO_x .

DEACETYL-HT-2 TOXIN

CAS RN: 34114-98-2 NIOSH #: YD 0105000
mf: $C_{19}H_{30}O_7$; mw: 370.49

SYNS:

12,13-EPOXY-3-ALPHA,4-BETA,8- ALPHA,15-TETRAHYDROXY TRICHOHEC-9-ENE-8-ISOVAL- ERATE	3-ALPHA,4-BETA,15-TRIHY- DROXY-8-ALPHA (3-METHYL- BUTYRYLOXY)-12,13-EPOXY- TRICHOHEC-9-ENE
--	---

TOXICITY DATA:	3	CODEN:
ori-ckn LD50:30180 ug/kg		AEMIDF 35,636,78

THR: HIGH ori.
Disaster Hazard: When heated to decomp it emits acrid smoke and fumes.

DEACETYLMULDAMINE

CAS RN: 36069462 NIOSH #: QG 1360000
mf: $C_{27}H_{46}NO_2$; mw: 416.74

TOXICITY DATA:	3	CODEN:
ori-ham TDL ₀ :150 mg/kg (7D preg)		JAFCAU 26,561,78

THR: HIGH ori.
Disaster Hazard: When heated to decomp it emits tox fumes of NO_x .

2-DEAMINOACTINOMYCIN D

CAS RN: 10118328 NIOSH #: AU 1595000
mf: $C_{62}H_{85}N_{11}O_{16}$; mw: 1240.0

TOXICITY DATA:	CODEN:
dnd-mam-lym 5200 nmol/L	JMCMAR 20,1055,77

THR: MUT data.
Disaster Hazard: When heated to decomp it emits tox fumes of NO_x .

7-DEAZAINOSINE

CAS RN: 2862160 NIOSH #: UY 9450000
mf: $C_{11}H_{13}N_3O_5$; mw: 267.27

TOXICITY DATA:	3	CODEN:
ori-rat LD50:26 mg/kg		CNREA8 29,116,69
ipr-rat LD50:25 mg/kg		CNREA8 29,116,69
scu-rat LD50:24 mg/kg		CNREA8 29,116,69
ipr-mus LD50:30 mg/kg		CNREA8 29,116,69
ori-dog LDLo:48 mg/kg		CNREA8 29,116,69
ivn-dog LDLo:48 mg/kg		CNREA8 29,116,69

THR: HIGH ori, ipr, scu, ivn.
Disaster Hazard: When heated to decomp it emits tox fumes of NO_x .

DECABORANE(14)

CAS RN: 17702419 NIOSH #: HD 1400000
mf: $B_{10}H_{14}$; mw: 122.24

Colorless needles. mp: 99.7°, d: 0.94. (solid), d: 0.78 (liquid @ 100°), vap. press: 19 mm @ 100°.

SYN:

DECABORANE (DOT)

BORON HYDRIDE

TOXICITY DATA:	3-2	CODEN:
ori-rat LD50:64 mg/kg		MLSR** No.8,51
ihl-rat LC50:46 ppm/4H		AMIHAB 17,362,58
skn-rat LD50:740 mg/kg		AMIHAB 11,132,55
ipr-rat LD50:23 mg/kg		AMIHBC 8,335,33
ori-mus LD50:40 mg/kg		AMIHAB 11,132,55
ihl-mus LC50:12 ppm/4H		NTIS** AD224-006
ipr-mus LD50:32 mg/kg		AMIHAB 11,132,55
ipr-dog LDLo:10 mg/kg		AMRL** TR-65-49
skn-rbt LD50:71 mg/kg		AMIHAB 11,132,55
ipr-rbt LD50:28 mg/kg		AMIHBC 8,335,33

TLV: Air: 0.05 ppm DTLVS* 4,118,80. OSHA Standard:
Air: TWA 300 ug/m³ (skin) (SCP-Q) FEREAC
39,23540,74. DOT: Flammable Solid, Label: Flammable Solid and Poison FEREAC 41,57018,76. Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary Assessment Information Proposed Rule FER-REAC 45,13646,80. AIHQA5 16,280,55.

THR: HIGH ori, ihl, ipr, skn, MOD skn. See also boron compounds and boron hydrides. Self-ignites in O_2 .
Disaster Hazard: When heated to decomp it emits tox fumes of B oxides.

Incomp: ethers, halocarbons; O_2 @ 100°; dimethyl sulfide.

For further information see Vol. 1, No. 8 of *DPIM Report*.

**1,1a,3,3a,4,5,5a,5b,6-
DECACHLOROCTAHYDRO-2-HYDROXY-
1,3,4-METHENO-1H-
CYCLOBUTA(c,d)-PENTALENE-2-LEVULINIC
ACID, ETHYL ESTER**

CAS RN: 4234791 NIOSH #: PC 8400000
mf: $C_{17}H_{12}Cl_{10}O_4$; mw: 634.79

SYNS:
gc-9160

KELEVAN

TOXICITY DATA:	3	CODEN:
ori-rat LD50:255 mg/kg		BESAAT 15,96,69
ori-dog LD50:400 mg/kg		BESAAT 15,96,69
skn-rbt LD50:188 mg/kg		BESAAT 15,96,69

Toxicology Review: RREVAH 63,45,76.

POLYVINYL SULFATE, POTASSIUM SALT

CAS RN: 26837423

NIOSH #: TR 8400000

SYNS:

POTASSIUM SALT OF POLYVINYL SULFATE PVSX

TOXICITY DATA:

3
ipr-mus LD50:225 mg/kg
scu-mus LD50:78 mg/kg

CODEN:

CRSBAW 166,121,72
OSDIAF 5,128,56

Reported in EPA TSCA Inventory, 1980.

THR: HIGH ipr, scu.

Disaster Hazard: When heated to decomp it emits tox fumes of SO₂ and K₂O.

PONDINIL

CAS RN: 5586878

NIOSH #: SH 2100000

mf: C₁₂H₁₈ClN·ClH; mw: 248.22

SYNS:

N-(3-CHLOROPROPYL)-ALPHA-METHYLPHENETHYLAMINE HYDROCHLORIDE

N-(3-CHLOROPROPYL)-1-METHYL-2-PHENYL-AETHYLAMIN-HYDROCHLORID (GERMAN)

TOXICITY DATA:

3
ori-rat LD50:410 mg/kg
ivn-rat LD50:35 mg/kg
ori-mus LD50:230 mg/kg
ipr-mus LD50:144 mg/kg
scu-mus LD50:180 mg/kg
ivn-mus LD50:49 mg/kg
ori-rbt LD50:236 mg/kg

CODEN:

ARZNAD 19,748,69
ARZNAD 19,748,69
ARZNAD 19,748,69
27ZQAG -,356,72
ARZNAD 19,748,69
27ZQAG -,356,72
27ZQAG -,356,72

THR: HIGH ori, ivn, ipr, scu.

Disaster Hazard: When heated to decomp it emits very tox fumes of NO₂, HCl and Cl⁻.

PORTLAND CEMENT

CAS RN: 65997151

NIOSH #: VV 8770000

Containing less than 1% crystalline Silica (FEREAC 39,23540,74)

SYN: PORTLAND CEMENT SILICATE

TOXICITY DATA:

CODEN:
Threshold Limit Value: Air: 30 mppcf DTLVS* 4,345,80.
OSHA Standard: Air: TWA 50 mppcf (SCP-S)-
FEREAC 39,23540,74. Reported in EPA TSCA Inventory, 1980.

THR: See also silicates.

POTASAN

CAS RN: 299-45-6

NIOSH #: GN 7525000

mf: C₁₄H₁₇O₅PS; mw: 328.34

Crystals, weak aromatic odor. mp: 38°; bp: 210° @ 1 mm; d: 1.260 @ 38°/4°.

SYNS:

DIETHOXY THIOPHOSPHORIC ACID ESTER OF 7-HYDROXY-4-METHYL COUMARIN
O,O-DIETHY 0-4-METHYL-COUMARIN-7-YL)MONO-THIOPHOSFAAT (DUTCH)

O,O-DIETHYL-0-(4-METHYL-7-COUMARINYL)PHOSPHOROTHIOATE
7-HYDROXY-4-METHYL COUMARIN, O-ESTER WITH O,O-DIETHYL PHOSPHOROTHIOATE

4-METHYL-7-HYDROXY COUMARIN DIETHOXYTHIOPHOSPHATE

PHOSPHOROTHIOIC ACID, O,O, DIETHYL O-(4-METHYL-2-OXO-2H-1-BENZOPYRAN-7-YL) ESTER (9CI)

TOXICITY DATA:

3
ori-rat LD50:19 mg/kg
ipr-rat LD50:15 mg/kg
unk-rat LD50:19 mg/kg
ori-mus LD50:99 mg/kg
scu-mus LD50:25 mg/kg
skn-rbt LD50:300 mg/kg
ori-gpg LD50:25 mg/kg

CODEN:

JPETAB 105,156,52
AMIHBC 6,9,52
30ZDA9 -,340,71
JPETA8 105,156,52
PAREAQ 11,636,59
WRPCA2 9,119,70
JPETAB 105,156,52

Toxicology Review: PMDCAY 10,85,74

THR: HIGH ori, ipr, unk, scu and dermal. See also parathion.

Disaster Hazard: Dangerous; see parathion.

POTASSIUM

CAS RN: 7440097

NIOSH #: TS 6460000

af: K; aw: 39.10

Soft ductile, silvery-white, very reactive metal. mp: 63.65°, bp: 774°, d: 0.862 @ 20°.

SYN: POTASSIUM, METAL (DOT)

TOXICITY DATA:

DOT: Flammable Solid, Label: Flammable Solid and Dangerous When Wet FEREAC 41,57018,76.
"NIOSH Manual of Analytical Methods" Vol 5 173#.
Reported in EPA TSCA Inventory, 1980.

THR: The toxicity of potassium compounds is almost always that of the anion.

Fire Hazard: Dangerous. Metallic potassium reacts with moisture to form potassium hydroxide and hydrogen. The reaction evolves much heat, causing the potassium to melt and spatter. It also ignites the hydrogen, which burns, or—if there is any confinement—an explosion can occur. Burning potassium is difficult to extinguish; dry powdered soda ash or graphite or special mixtures of dry chemical are recommended. It can ignite spont in moist air.

Explosion Hazard: It reacts violently with the following materials under required conditions of temp., pressure, state of division: C₂H₂, air, (moist air), AlBr₃, metallic halides, ammonium chlorocuprate, NH₄Br, NH₄I, [(NH₄)₂SO₄ + NH₄NO₃], Sb and As halides, (AsH₃ + NH₃), Bi₂O₃, boric acid, BBr₃, Br₂, C, CO₂, CS₂, (CO + O₂), CCl₄, charcoal, chlorinated hydrocarbons, Cl₂, ClO, ClF₃, CHCl₃, CrCl₄, CrO₃, Cu₂OCl₂, CuO, dichloromethane, ethylene oxide, F₂, graphite, (graphite + air), I, (graphite + K₂O₂), HI, H₂O₂, IBr, ICl, IF₅, Pb₂OCl₂, PbO₂, PbSO₄, maleic anhydride, Hg₂O, CH₃Cl, MoO₃, NO₂, P₂NF, peroxides, COCl₂, (PH₃ + NH₃), P, PCl₅, P₂O₅, PBr₃, PCl₃, potassium chlorocuprate, K oxides, KO₃, K₂O₂, KO₂, Se, SeOCl₂, SiCl₄, AgIO₃, NaIO₃, (NH₃ + NaNO₂), Na₂O₂, (SnI₄ + S), SnO₂, S, SBr₂, SCl₂, Te, tetrachloroethane, thiophosphoryl fluoride, VOCl₂, H₂O. Potassium metal will form the peroxide (K₂O₂) and the superoxide (KO₃ or K₂O₄) at room temp. even when stored under mineral oil. Metal which has oxidized on storage under

2268 POTASSIUM (LIQUID ALLOY)

oil may explode violently when handled or cut. Oxide-coated potassium should be destroyed by burning.

Disaster Hazard: Dangerous; a highly reactive alkali metal. See sodium and lithium. In the presence of moist air it can spont catch fire and burn with great intensity. It may even explode. Reacts violently with moisture, acid fumes and oxidizers.

POTASSIUM (LIQUID ALLOY)

CAS RN: 7440097 NIOSH #: TS 6465000

SYN: POTASSIUM, METAL LIQUID ALLOY (DOT)

TOXICITY DATA:

DOT: Flammable Solid, Label: Flammable Solid and Dangerous When Wet FEREAC 41,57018,76. Reported in EPA TSCA Inventory, 1980.

THR: See potassium.

Disaster Hazard: When heated to decomp it emits tox fumes of K_2O .

POTASSIUM ACETATE

CAS RN: 127082 NIOSH #: AJ 3325000
mf: $C_2H_3O_2 \cdot K$; mw: 98.15

White powder; mp: 292°; d: 1.8 @ 20°/20°.

SYN: DIURETIC SALT

TOXICITY DATA: 2 CODEN:
ori-rat LD50: 3250 mg/kg AIHAAP 30,470,69

Reported in EPA TSCA Inventory, 1980.

THR: MOD orl.

Disaster Hazard: When heated to decomp it emits acrid smoke and fumes.

POTASSIUM ACETYLIDE

mf: C_2HK ; mw: 64.13

THR: No tox data. Will hydrolyze to KOH which is very caustic, irr. See also potassium hydroxide.

Disaster Hazard: When heated to decomp it emits tox fumes of K_2O .

Incomp: Chlorine; non-metal oxides.

POTASSIUM ACID FLUORIDE

CAS RN: 7789299 NIOSH #: TS 6650000
mf: $FK \cdot FH$; mw: 78.11

Colorless crystals; mp: decomp.

SYNS:

BIFLUORURE DE POTASSIUM
(FRENCH)

POTASSIUM BIFLUORIDE

POTASSIUM HYDROGEN FLUO-
RIDE

TOXICITY DATA: 3 CODEN:

Toxicology Review: AMSSAQ 400,5,63. Occupational Exposure to Inorganic Fluorides recm std: Air: TWA 2.5 mg(F)/m³ NTIS**. Reported in EPA TSCA Inventory, 1980.

THR: HIGH. A poison. Very reactive, corrosive. Attacks skn, eyes, mu mem. See also fluorides.

Disaster Hazard: When heated to decomp it emits tox fumes of F^- .

POTASSIUM ACID FLUORIDE (SOLUTION)

CAS RN: 7789299 NIOSH #: TS 6655000

SYNS:

POTASSIUM BIFLUORIDE SOLU-
TION (DOT)

POTASSIUM HYDROGEN FLUO-
RIDE SOLUTION (DOT)

TOXICITY DATA: 3

DOT: Corrosive Material, Label: Corrosive FEREAC 41,57018,76. Occupational Exposure to Inorganic Fluorides recm std: Air: TWA 2.5 mg(F)/m³ NTIS**. Reported in EPA TSCA Inventory, 1980.

THR: HIGH. A poison. Very corrosive and reactive. Attacks living tissue. See also fluorides and hydrofluoric acid.

Disaster Hazard: When heated to decomp it emits tox fumes of F^- and HF.

POTASSIUM AMALGAM

Silvery liquid or solid. K + Hg.

THR: HIGH. See potassium and mercury.

Fire Hazard: Mod, by spont chemical reaction; on contact with moisture, hydrogen is liberated. See also potassium.

Explosion Hazard: Mod; liberates hydrogen upon contact with moisture, acids, etc. See also potassium.

Disaster Hazard: Dangerous; when heated to decomp it emits highly tox fumes of Hg and PO_x ; will react with water, steam or acids to produce hydrogen; can react with oxidizing materials.

POTASSIUM AMIDE

mf: H_2KN ; mw: 16.02

THR: No tox data. See also potassium hydroxide, ammonia which are hydrolysis products of KNH_2 .

Disaster Hazard: When heated to decomp it emits very tox fumes of NO_x , NH_3 and K_2O .

Incomp: Potassium nitrite; water.

POTASSIUM-4'-AMINOPHENYL- AZOPHENYLSULFATE

mf: $C_{12}H_{10}N_3O_4S \cdot K$; mw: 331.3

NIOSH #: WS 5800000
SYN: SULFURIC ACID, P-((P-AMINOPHENYL)AZO)PHENYL ESTER, POTASSIUM SALT

TOXICITY DATA:
mma-sat 500 nmol/plate

CODEN:
CALEDQ 8,71,79

THR: MUT data. See also sulfates.

Disaster Hazard: When heated to decomp it emits very tox fumes of NO_x and SO_x .

POTASSIUM ARSENITE

CAS RN: 10124502 NIOSH #: CG 3800000
mf: $AsH_3O_3 \cdot xK$; mw: 399.65

SMOKELESS POWDER

Nitrocellulose containing about 13.1% nitrogen produced by blending material of somewhat lower (12.6%) and slightly higher (13.2%) nitrogen content, converting to a dough with alcohol-ether mixture, extruding, cutting and drying to a hard horny product. Small amounts of stabilizers (amines) and plasticizers are usually present, as well as various modifying agents (nitrotoluene, nitroglycerine, salts). See also nitrocellulose and explosives, high.

SNAKEROOT OIL CANADIAN

CAS RN: 8016691 NIOSH #: VX 8125000

Consists of Linalool, Geraniol, 1-alpha-terpineol, eugenol and methyl eugenol (FCTXAV 16,637,78)

SYN: WILD GINGER OIL

TOXICITY DATA:

ori-rat LD50: 4480 mg/kg

CODEN:

FCTXAV 16,637,78

Reported in EPA TSCA Inventory, 1980.

THR: LOW ori. See also constituents as listed above.

Disaster Hazard: When heated to decompose it emits acrid smoke and fumes.

SODA LIME, (SOLID)

CAS RN: 8006288 NIOSH #: VW 0550000

White to gray granules. Rapidly deteriorates on exposure to air.

TOXICITY DATA:

DOT: Corrosive Material, Label: Corrosive FEREAC 41,57018,76.

THR: No data. A corrosive material irritant to skin, eyes, mucous membranes. See also sodium hydroxide and lime, i.e., $\text{CaO} + 5\text{-}20\% \text{NaOH}$ containing 6-18% H_2O .

SODIUM

CAS RN: 7440235 NIOSH #: VY 0686000

af: Na; aw: 22.99

Light, soft, ductile, malleable, silver-white metal. mp: 97.81° , bp: 881.4° , d: 0.9710 @ 20° , autoign. temp.: $> 115^\circ$ in dry air, vap. press: 1.2 mm @ 400° .

SYNS:

NATRIUM

SODIUM METAL (DOT)

TOXICITY DATA: 3

DOT: Flammable Solid, Label: Flammable Solid and Dangerous When Wet FEREAC 41,57018,76. "NIOSH Manual of Analytical Methods" VOL 5 173#. Reported in EPA TSCA Inventory, 1980.

THR: Sodium in elemental form is highly reactive, particularly with moisture, with which it reacts violently and therefore attacks living tissue. Also, $\text{Na} + \text{HOH}$ yields NaOH . See also sodium hydroxide. Metallic sodium reacts exothermally with the moisture of body or tissue surfaces, causing thermal and chemical burns due to

the reaction with sodium and the sodium hydroxide formed.

Fire Hazard: Dangerous, when exposed to heat and moisture. In dry air it reacts very slowly up to 550° or by chemical reaction with moisture, air, AlBr_3 , AlCl_3 , AlF_3 , NH_4 chlorocuprate, NH_4NO_3 , SbBr_3 , SbCl_3 , SbI_3 , AsCl_3 , AsI_3 , BiBr_3 , BiCl_3 , BiI_3 , Bi_2O_3 , BBr_3 , bromoazide, CO_2 , ($\text{CO} + \text{NH}_3$), CCl_4 , Cl_2 , ClF_3 , CrCl_4 , CrO_3 , CoBr , CoCl , CuCl_2 , CuO , FeBr_3 , FeCl_3 , FeBr_2 , FeCl_2 , FeI_2 , hydrazine hydrate, H_2O_2 , H_2S , HCl , HF , F_2 , 1,2-dichloroethylene, dichloromethane, Br_2 , hydroxylamine, iodine, iodine monochloride, iodine pentafluoride, lead oxide, maleic anhydride, manganous chloride, mercuric bromide, mercuric chloride, mercuric fluoride, mercuric iodide, mercurous chloride, mercurous oxide, methyl chloride, molybdenum trioxide, monoammonium phosphate, nitric acid, nitrogen peroxide, nitrosyl fluoride, nitrous oxide, phosgene, phosphorus, phosphorous pentafluoride, phosphorus pentoxide, phosphorus tribromide, phosphorus trichloride, phosphoryl chloride, potassium oxides, potassium ozonide, potassium superoxide, selenium, silicon tetrachloride, silver bromide, silver chloride, silver fluoride, silver iodide, sodium peroxide, stannic chloride, (stannic iodide + sulfur), stannic oxide, stannous chloride, sulfur, sulfur dibromide, sulfur dichloride, sulfur dioxide, sulfuric acid, tellurium, tetrachloroethane, thallous bromide, thiophosphoryl bromide, trichloroethylene, vanadium pentachloride, vanadyl chloride, zinc bromide, or any oxidizing material, decompose moisture to evolve hydrogen and heat; reacts exothermally with the halogens, acids and halogenated hydrocarbons. Heated sodium is spontaneous flame in air. Can be safely stored under liquid hydrocarbons.

Spontaneous Heating: No.

Explosion Hazard: Dangerous, when exposed to moisture in any form! Keep dry at all times!

Disaster Hazard: Dangerous; when heated in air, emits toxic fumes of sodium oxide; will react with water or steam to produce heat, hydrogen, and flame vapors; can react vigorously to explosively with oxidizing materials. See hydrogen.

To Fight Fire: Soda ash, dry sodium chloride or graphite, in order of preference.

Storage and Handling: In the absence of moisture, oxygen or halides, sodium is safe to handle. As to indoor storage of drums, the important thing in storing sodium is that the storage area must be kept dry, since explosions may result from the contact of sodium with water. No automatic sprinkler system, or water or steam pipes containing water should be allowed in the room. Sufficient heat should be provided (without the use of open flames) to prevent condensation of moisture in the room due to changes in atmospheric conditions. Empty sodium drums should be stored in this same area.

Fire extinguishers (preferably color-coded) must be provided in the storage area, but only those containing sodium chloride, sodium carbonate, or graphite may be used. Pails are adequate for storing extinguishant if special care is taken to insure that the materials are

dry. Water, carbon dioxide, carbon tetrachloride, soda-acid, or conventional dry chemical (bicarbonate) extinguishers must be avoided, and signs should be posted in the storage area warning against their use.

Only that amount of sodium immediately needed should be removed from the storage area. Sodium should not be withdrawn for intermediate storage in reaction areas. A special metal container with a tight fitting cover should be used for transporting sodium bricks to other plant areas, once they have been removed from the original container.

Large-scale outdoor storage tanks such as tank cars are unloaded after melting the sodium by circulating hot oil and withdrawing the molten sodium by vacuum to storage tanks similar in construction to sodium tank cars. Although steam may be used to heat the circulating oil, for use on both tank cars and storage tanks, steam must not be used directly as the heating agent for sodium tanks.

For further information see Vol. 1, No. 8 of *DPIM Report*.

SODIUM (LIQUID ALLOY)

CAS RN: 7440235 NIOSH #: VY 0688000

SYN: SODIUM, METAL LIQUID ALLOY (DOT)

TOXICITY DATA:

DOT: Flammable Solid, label: Flammable Solid and Dangerous When Wet FEREAC 41,57018,76.

THR: See also sodium.

SODIUM, (SOLUTION)

CAS RN: 7440235 NIOSH #: VY 0690000

SODIUM DISPERSIONS. Finely divided metallic sodium suspended in toluene, xylene, naphtha, kerosene, etc.

SYN: SODIUM, METAL DISPERSION IN ORGANIC SOLVENT

TOXICITY DATA: 3

DOT: Flammable Solid, Label: Flammable Solid and Dangerous When Wet FEREAC 41,57018,76. Reported in EPA TSCA Inventory, 1980.

THR: HIGH. See sodium and individual dispersant.

Fire Hazard: Dangerous, when exposed to heat or flame or by chemical reaction. These are very reactive forms of sodium, which if carelessly handled may catch fire. To extinguish, see sodium. After sodium has been extinguished, the burning organic vapor can be dealt with by very cautious use of a carbon dioxide extinguisher. Do not use carbon tetrachloride.

Explosion Hazard: Mod, by chemical reaction. See also sodium.

Disaster Hazard: Dangerous; when heated, it loses the solvent and emits highly tox fumes of sodium, sodium oxide, etc.; will react with water or steam to produce heat and hydrogen; on contact with oxidizing materials, can react vigorously, and on contact with acid or acid fumes, can emit tox fumes.

SODIUM ACETARSONE

CAS RN: 5892488 NIOSH #: CF 8750000
mf: $C_8H_9AsNO_5 \cdot Na$; mw: 297.09

SYN: N-ACETYL-4-HYDROXY-M-ARSANILIC ACID SODIUM SALT

TOXICITY DATA:	3	CODEN:
ori-cat LDLo: 125 mg/kg		PSEBAA 27,267,30
ori-rbf LDLo: 150 mg/kg		PSEBAA 27,267,30
ori-gpg LDLo: 100 mg/kg		PSEBAA 29,125,31

OSHA Standard: Air: TWA 500 ug(As)/m3 FEREAC 39,23540,74.

THR: HIGH orl. See also arsenic compounds.

Disaster Hazard: When heated to decomp it emits very tox fumes of As and NO_x .

SODIUM ACETATE

CAS RN: 127093 NIOSH #: AJ 4375000
mf: $C_2H_3O_2 \cdot Na$; mw: 82.04

White crystals, sol in water. autoign. temp.: 1125°F. d: 1.45; mp: 58°. Decomp @ higher temp.

SYNS:

ANHYDROUS SODIUM ACETATE NATRIUMACETAT (GERMAN)

TOXICITY DATA:	2-1	CODEN:
ori-mus LD50: 6891 mg/kg		JIHTAB 23,78,41
skn-rbt 500 mg/24H MLD		BIOFX* 19-3/71
eye-rbt 10 mg MLD		BIOFX* 19-3/71
ori-rat LD50: 3530 mg/kg		FAONAU 40,127,67
ori-mus LD50: 4960 mg/kg		JIHTAB 23,78,41
scu-mus LD50: 8000 mg/kg		ZGEMAZ 113,536,44
ivn-mus LD50: 335 mg/kg		JLCMAK 29,809,44
ivn-rbt LDLo: 1300 mg/kg		AEXPBL 21,119,1886

Reported in EPA TSCA Inventory, 1980. EPA TSCA 8E No: 04780120—Followup Sent as of April, 1979.

THR: A skn, eye irr. HIGH ivn. MOD orl, ivn; LOW orl, scu. Used as a general-purpose food additive. It is a substance which migrates to food from packaging materials. Violent reaction with F_2 , KNO_3 , diketene.

SODIUM ALGINATE

CAS RN: 9005383 NIOSH #: AZ 5820000
mf: $(C_6H_7O_6Na)_x$; mw: 32000-250,000

Colorless to slight yellow filamentous or granular solid or powder. In H_2O it forms a viscous colloidal sol; not sol in ether, alc, chloroform.

SYNS:


ALGIN (POLYSACCHARIDE) PECTALGINE
ANTIMIGRANT C 45 SNOW ALGIN L

TOXICITY DATA:	3-2	CODEN:
ivn-rat LD50: 1000 mg/kg		FAONAU 53A,382,74
ivn-mus LD50: 200 mg/kg		FAONAU 53A,382,74
ipr-cat LD50: 250 mg/kg		FAONAU 53A,382,74
ivn-rbt LD50: 100 mg/kg		FAONAU 53A,382,74

Reported in EPA TSCA Inventory, 1980.

THR: HIGH ivn, ipr; MOD ivn. A stabilizer food additive.

Disaster Hazard: When heated to decomp it emits acrid smoke.

RECORD OF COMMUNICATION	<div style="text-align: right;">Ref. 9</div> <div style="display: flex; justify-content: space-around; align-items: flex-start;"> <div style="text-align: center;"> <input checked="" type="checkbox"/> Phone Call <input type="checkbox"/> Conference </div> <div style="text-align: center;"> <input type="checkbox"/> Discussion <input type="checkbox"/> Other (Specify) </div> <div style="text-align: center;"> <input type="checkbox"/> Field Trip </div> </div>	
	(Record of Item Checked Above)	
TO: Rickey Hennigan Operator, Harris County WC&ID #21 713-452-0211	FROM: Victor Cason ICF - FIT 214-744-1641	DATE <div style="text-align: right;">3/6/89</div>
		TIME <div style="text-align: right;">1105</div>
SUBJECT Population served by well in water district #21.		
SUMMARY OF COMMUNICATION Mr. Hennigan stated that one well is near Sheldon Road and one well is near the Cedar Lane and I-10 intersection. The wells correspond to 65-16-403 and 65-16-702 in Report 178 of the Texas Water Development Board. Mr. Hennigan stated that approximately 10,000 people are serviced by the wells. <div style="margin-top: 10px;">  </div>		
CONCLUSIONS, ACTION TAKEN OR REQUIRED		
INFORMATION COPIES TO:		
EPA Form 1300-6 (7-72) Replaces EPA HQ Form 5300-3 Which May Be Used Until Supply is Exhausted.		

RECORD OF COMMUNICATION	Ref. 10	
	<input checked="checked" type="checkbox"/> Phone Call <input type="checkbox"/> Conference	<input type="checkbox"/> Discussion <input type="checkbox"/> Other (Specify)
	<input type="checkbox"/> Field Trip	
(Record of Item Checked Above)		
TO: Steve Early Operator, Harris County WD #6 713-452-2232	FROM: Victor Cason ICF - FIT 214-744-1641	DATE 3/6/89
		TIME 1030
SUBJECT Population served by well in water district #6.		
<p>SUMMARY OF COMMUNICATION</p> <p>Mr. Early stated that he operates three wells near Market Street and Sheldon Road in Channelview, TX. His wells correspond to well 65-16-707 65-16-714 in Report 178 of the Texas Water Development Board. The third well is not listed in the above report. The numbering system used by Mr. Early labels the wells as 640, 641 and 3991. He stated that approximately 2500 - 3000 people were serviced by the wells. Mr. Early told me that the water districts were in a process of converting over to surface water soon.</p> <p><i>Victor Cason</i></p>		
CONCLUSIONS, ACTION TAKEN OR REQUIRED		
INFORMATION COPIES TO:		
EPA Form 1300-6 (7-72) Replaces EPA HQ Form 5300-3 Which May Be Used Until Supply is Exhausted.		

PREFACE

U.S. DEPARTMENT OF COMMERCE

LATHUR H. HODGES, Secretary

WEATHER BUREAU

F.W. REICHELDERFER, Chief

TECHNICAL PAPER NO. 40

RAINFALL FREQUENCY ATLAS OF THE UNITED STATES

for Durations from 30 Minutes to 24 Hours and
Return Periods from 1 to 100 Years

Prepared by

DAVID M. HENSHFIELD

Cooperative Studies Section, Hydrologic Services Division

for

Engineering Division, Soil Conservation Service

U.S. Department of Agriculture

THIS ATLAS IS OBSOLETE FOR THE FOLLOWING 11 WESTERN STATES: Arizona, California, Colorado, Idaho, Montana, Nevada, New Mexico, Oregon, Utah, Washington, and Wyoming.

NOAA ATLAS 2: PRECIPITATION-FREQUENCY ATLAS OF THE WESTERN UNITED STATES (GPO: 11 Vols., 1973) supersedes the Technical Paper 40 data for these states.

All but 3 of the 11 state volumes are out of print, and no reprint is presently planned.

Institutions in the eleven western states likely to have copies of these volumes for their state for public inspection are:

US Department of Agriculture Soil Conservation Service Offices
US Army Corps of Engineers Offices
Selected University Libraries
National Weather Service Offices (may also have volumes for adjacent states).
National Weather Service Forecast Offices (may have all eleven volumes)

Elsewhere, libraries of universities where hydrology and meteorology degree programs are offered may shelve some of the eleven volumes.

The three volumes in print as of 1 Jan 1983 at the GPO are:

Vol.	State	GPO Stock Number	Price
IV	New Mexico	003-017-00158-0	\$10.00
VI	Utah	003-017-00160-1	12.00
VII	Nevada	003-017-00161-0	9.50

The GPO Order number is 202-783-3238 for VISA and MASTERCARD orders which

NOTICE


Rainfall-frequency information for durations of 1 hour and less for the Central and Eastern States has been superseded by NOAA Technical Memorandum NWS HYDRO-35 Five to Sixty-Minute Precipitation Frequency for the Eastern and Central United States. This publication (Accession No. PB 272-112/AS) is obtainable from:


National Technical Information Service
5285 Port Royal Road
Springfield, VA 22161



WASHINGTON, D.C.

May 1961



RECORD OF COMMUNICATION	Ref. 12	
	<input checked="checked" type="checkbox"/> Phone Call <input type="checkbox"/> Conference	<input type="checkbox"/> Discussion <input type="checkbox"/> Field Trip <input type="checkbox"/> Other (Specify)
(Record of Item Checked Above)		
TO: Jim Rice TWC, Deer Park 713-479-5981	FROM: Victor Cason ICF - FIT 214-744-1641	DATE 2/17/89
		TIME 1535
SUBJECT Uses of the San Jacinto River.		
SUMMARY OF COMMUNICATION Mr. Rice stated that the San Jacinto River in the area of the site with regards to usage is composed of two sections. Section 1001, north of I-10, is named the San Jacinto River Tidal and has contact recreation, high aquatic life and no domestic water supply uses. Section 1005, south of I-10, is named the San Jacinto River Houston Ship Channel and has these uses: non-contact recreation, high aquatic life and no domestic water supply. There are no water intakes south of the site or north of the site. 		
CONCLUSIONS, ACTION TAKEN OR REQUIRED		
INFORMATION COPIES TO:		
EPA Form 1300-6 (7-72) Replaces EPA HQ Form 5300-3 Which May Be Used Until Supply is Exhausted.		



**TEXAS
PARKS AND WILDLIFE DEPARTMENT**

4200 Smith School Road Austin, Texas 78744

COMMISSIONERS

CHUCK NASH
Chairman, San Marcos

RICHARD R. MORRISON, III
Vice-Chairman
Clear Lake City

CHARLES D. TRAVIS
Executive Director

November 10, 1988

BOB ARMSTRONG
Austin

HENRY C. BECK, III
Dallas

GEORGE R. BOLIN
Houston

DELO H. CASPARY
Rockport

WM. L. GRAHAM
Amarillo

BEATRICE CARR PICKENS
Amarillo

A.R. (TONY) SANCHEZ, JR.
Laredo

C. Victor Cason
ICF Technology Incorporated
1509 Main Street, Suite 900
Dallas, Texas 75201-4809

Dear Mr. Cason:

In response to your request of November 3, 1988 for information on sensitive species and natural communities within the project area in Harris County, we offer the following comments. A search of the Texas Natural Heritage Program Information System revealed no presently known occurrences of special species or natural communities in the general vicinity of the project.

The Heritage Program information included here is based on the best data currently available to the state regarding threatened, endangered, or otherwise sensitive species. However, the data does not provide a definite statement as to the presence or absence of special species or natural communities within your project area, nor can it substitute for an evaluation by qualified biologists. It is intended to assist you in avoiding harm to species that occur on your site. Please contact the Texas Parks and Wildlife Department's Heritage Program before publishing or otherwise disseminating any specific locality information.

Thank you for contacting us. Please feel free to call me at 512/389-4533 if you have questions.


Sincerely,

Dorinda Sullivan, Data Manager
Texas Natural Heritage Program
Resource Protection Division

DLS/ds

RECORD OF COMMUNICATION	Ref. 14	
	<input checked="checked" type="checkbox"/> Phone Call <input type="checkbox"/> Conference	<input type="checkbox"/> Discussion <input type="checkbox"/> Other (Specify)
	<input type="checkbox"/> Field Trip	
(Record of Item Checked Above)		
TO: Ernest Baker Hydrologist, USGS Austin, TX 512-832-5791	FROM: Victor Cason ICF - FIT 214-744-1641	DATE 3/14/89
		TIME 1145
SUBJECT Description of the Alta Loma Sand.		
SUMMARY OF COMMUNICATION Mr. Baker stated that the base of the Alta Loma Sand is approximately 600 feet in the vicinity of the site. The sand is heavily pumped in the area. The upper and lower Chicot aquifers are interconnected. Most wells in the area draw from the Alta Loma Sand since the Evangeline aquifer is slightly salty. <i>Victor Cason</i>		
CONCLUSIONS, ACTION TAKEN OR REQUIRED		
INFORMATION COPIES TO:		
EPA Form 1300-6 (7-72) Replaces EPA HQ Form 5300-3 Which May Be Used Until Supply is Exhausted.		

**TEXAS
WATER
DEVELOPMENT
BOARD**



Report 178

**GROUND-WATER DATA FOR
HARRIS COUNTY, TEXAS
VOLUME I
DRILLERS' LOGS OF WELLS,
1905-71**

November 1973

Drillers' Logs of Wells in Harris County--Continued

	THICKNESS (FEET)	DEPTH (FEET)		THICKNESS (FEET)	DEPTH (FEET)
Well LJ-65-16-714 Owner: Harris County FWD No. 6 Driller: Layne Texas Co.			Shale, tough	58	298
Surface soil	3	3	Sand	16	314
Clay	63	66	Shale, sandy	16	330
Shale, sandy	53	119	Sand	124	454
Sand	49	168	Well LJ-65-16-716 Owner: Productions Systems International Driller: B. J. Swinehart Co.		
Sand and shale	31	199	Clay	18	18
Sand	35	234	Sand	28	46
Shale	24	258	Clay	152	198
Sand	33	291	Sand	14	212
Shale, sandy	12	303	Clay	10	222
Sand	7	310	Sand	18	240
Shale, sandy	19	329	Clay	25	265
Sand	121	450	Sand	36	301
Sand and shale streaks	40	490	Clay	7	308
Shale, sandy	16	506	Sand	14	322
Shale	5	511	Clay	55	377
Shale, sandy	54	565	Sand	20	397
Sand	13	578	Sandrock	44	441
Shale, sandy	4	582	Sand	27	468
Sand	25	607	Well LJ-65-16-717 Owner: Texaco Inc. Driller: Lowry Water Wells		
Shale, sandy	7	614	Surface clay and sand	26	26
Sand and shale streaks	21	635	Clay, white	23	49
Shale, sandy	10	645	Sand	7	56
Well LJ-65-16-715 Owner: Key Oil Co. Driller: Lowry Water Wells			Clay, red	86	142
Clay, red and sand	24	24	Clay, blue	62	204
Sand and clay	24	48	Sand	26	230
Clay, white	48	96	Shale	3	233
Clay, brown	38	134			
Sand	10	144			
Sand, powder	24	168			
Shale, brown	24	192			
Sand	35	227			
Sand and shale	13	240			

RECORD OF COMMUNICATION	<div style="text-align: right;">Ref. 16</div> <div style="display: flex; justify-content: space-around;"> <div> <input checked="" type="checkbox"/> Phone Call <input type="checkbox"/> Conference </div> <div> <input type="checkbox"/> Discussion <input type="checkbox"/> Other (Specify) </div> <div> <input type="checkbox"/> Field Trip </div> </div>	
	(Record of Item Checked Above)	
TO: Jim Rice TWC, Deer Park 713-479-5981	FROM: Victor Cason ICF - FIT 214-744-1641	DATE <div style="text-align: right;">3/20/89</div>
		TIME <div style="text-align: right;">1430</div>
SUBJECT San Jacinto River Tidal		
SUMMARY OF COMMUNICATION Mr. Rice stated that section 1001, San Jacinto River Tidal, does have tidal influence. He stated that sometimes the river is salty all the way to the Houston Lake dam. The area is salty many times a year especially last year when there was little rainfall. <div style="text-align: right; margin-top: 10px;"> <i>Victor Cason</i> </div>		
CONCLUSIONS, ACTION TAKEN OR REQUIRED		
INFORMATION COPIES TO:		
EPA Form 1300-6 (7-72) Replaces EPA HQ Form 5300-3 Which May Be Used Until Supply is Exhausted.		